# CARSON CITY PURCHASING & CONTRACTS 201 North Carson Street Suite 3 Carson City, NV 89701 775-283-7137 / FAX 887-2107

http://www.carson-city.nv.us/

#### **NOTICE TO CONTRACTORS**

BID #1011-201

North/South Water Transmission Main Project-Phase II Labor Commissioner PWP# CC-2011-177 Public Works Project No. 4.0800 Engineer's Estimate: \$8,440,000.00

March 14, 2011

Addendum No. 1

Please make the following additions/changes to the above referenced project.

#### Make the following changes to the Bid Documents;

- **1.** Replace Engineer's Estimate equal to \$9,500,000.00.
- 2. Replace the title of Special Condition SP 2.2.4 to read the following:

Overexcavate Unsuitable Material and Backfill (Contingent Item)
Excavation and Export (Contingent Item)
Excavation and Fill

- **3.** Add Special Condition SP 2.2.12 to read the following:
  - 2.2.12 Pulverization of Existing Roadbed
  - A. Work under this section shall be completed per Section 200.01.04 "RECYCLED AGGREGATE BASE" of the Standard Specifications for Public Works Construction.

If the pulverization of the existing pavement layer does not meet the criteria of Section 200.01.04, a portion of the pulverized material shall be replaced with approved virgin material to ensure compliance with Section 200.01.04, as directed by the Engineer.

- B. Measurement of this item will be per Square Foot.
- C. Payment for Pulverization to the depth necessary to construct the roadbed modification as shown on the plans will be made in Unit Price named in Proposal Summary, which price shall constitute full compensation for pulverization, grading and compaction of pulverized material to 95% relative density, removal of excess material, removal of material that is 2 inch plus in diameter, and all other labor, tools, equipment, materials and incidentals required to perform the work.

Addendum 1 Page 1 of 2

D. Equipment for pulverizing shall be specifically designed to pulverize pavement to at least 12 inches in depth. The pulverized plantmix bituminous material shall be thoroughly mixed with the underlying aggregate base, to a depth to construct the roadbed modification as shown on the plans.

The Contractor shall limit their daily operation to the extent that a section of roadway can be pulverized, graded and blended, and compacted to the existing grades shown in the sections of improvement. The intent of this limitation is to provide an acceptable driving surface for public traffic during non-working hours.

If the pulverized material is in excess of what is required for construction of finish grade, then remove excess amount at contractor's expense.

- **4.** Replace the last sentence in the second paragraph of Special Condition 2.2.2 Traffic Control for Roadway Improvements to read the following:
  - "Liquated damages are accessed for additional delays, see GC 3.13 as amended in these special conditions."
- **5.** Replace Page BP-16 thru Page BP-18 Bid Proposal with attached sheets.
- **6.** Replace IB-7-A Page ITB-12 Instructions to Bidders first sentence to read the following:

"Carson City requires that qualified MBE's, SBE's and WBE's have the maximum opportunity to participate in the performance of contacts in conjunction with this Project."

#### Make the following changes to the Plans;

- 7. Sheets C3 thru C8, C12 thru C19, C21 thru C23, C27 thru C46, C55 thru C58, C67 and C68 of 96. North/South Water Transmission Main Project Phase 2;
  - A. Replace the above listed sheets with the attached sheets that show added/revised paving limits and typical sections, and a revised sewer lateral.

#### Clarifications:

None

#### End of Addendum No. 1

Addendum 1 Page 2 of 2

### **BID PROPOSAL**

BID # 1011-201

BID TITLE: NORTH/SOUTH WATER TRANSMISSION MAIN PROJECT-PHASE II

NOTICE:

No substitution or revision to this Bid Proposal form will be accepted. Carson City will reject any Bid that is received that has changes or alterations to this document. Although the Prevailing Wages are provided in this bid document, the bidder is responsible to verify with the Labor Commissioner if any addendums have been issued. The successful bidder will be required to provide the current Prevailing Wages used in preparation of their bid within 24 hours of bid submission.

**PRICES** will be valid for sixty (60) calendar days after the bid opening which is indicated in the Notice to Contractors.

<u>A COPY OF CONTRACTOR'S "CERTIFICATE"</u> of eligibility issued by the State of Nevada Contractors' Board as proof of Bidder's compliance with the provisions of N.R.S. 338.147 must be submitted with his/her bid for the preference to be considered. This Statute does not apply to projects expected to cost less than \$250,000.

**COMPLETION** of this project is expected **PURSUANT TO THE BID DOCUMENTS**.

**BIDDER** acknowledges receipt of \_\_\_\_\_ Addendums.

#### SUMMARY

Description		Scheduled Value	Unit	Unit Price	Total Price			
SCHEDULE A: 24-INCH WATER LINE WORK								
BP.1	Mobilization/Demobilization and Cleanup (SP 2.2.1)	1	LS					
BP.2	Clearing and Grubbing (SP 2.2.3)	265,000	SF					
BP.3*	Excavate and Export (SP 2.2.4) (Contingent Item)	4,000	CY					
BP.4	Excavate and Fill (SP 2.2.4)	8,900	CY					
BP.5	15-inch SDR 35 PVC Storm Drain, Complete in Place (SP 2.6.8)	76	LF					
BP.6	15-inch CMP Storm Drain, Complete in Place (SP 2.6.8)	49	LF					
BP.7	15-inch CMP Storm Drain w/ Flared End Sections, Complete in Place (SP 2.6.8)	97	LF					
BP.8	18-inch CMP Storm Drain, Complete in Place (SP 2.6.8)	50	LF					
BP.9	24-inch CMP Storm Drain, Complete in Place (SP 2.6.8)	112	LF					
BP.10	21"x15" CMP Storm Drain w/ Flared End Sections, Complete in Place (SP 2.6.8)	60	LF					
BP.11	15-inch Class III or Class IV RCP Storm Drain, Complete In Place (SP 2.6.8)	390	LF					
BP.12	15-inch Class IV RCP Storm Drain w/ Flared End Sections, Complete in Place (SP 2.6.8)	40	LF					
BP.13	30-inch Class III or Class IV RCP Storm Drain w/ Flared End Section, Complete in Place (SP 2.6.8)	40	LF					
BP.14	Outlet Structure and Appurtenances, Complete in Place (SP 2.6.9)	1	LS					
BP.15	Remove Existing Curb Inlet and Construct Type 4R Catch Basin, Complete in Place (SP 2.5.3)	2	EA					

## **BID PROPOSAL**

Description		Scheduled Value	Unit	Unit Price	Total Price
BP.16	Type 200 Drop Inlet, Complete in Place (SP 2.6.9)	2	EA		
BP.17	24-inch Precast Drop Inlet, Complete in Place (SP 2.6.9)	2	EA		
BP.18	36-inch Precast Drop Inlet, Complete In Place (SP 2.6.9)	4	EA		
BP.19	Type 1 PCC Median Curb, Complete in Place (SP 2.2.6)	234	LF		
BP.20	Type 2 PCC Median Curb, Complete in Place (SP 2.2.6)	1183	LF		
BP.21	PCC Median Paving, Complete in Place (SP 2.2.6)	4,697	SF		
BP.22	Type 1 PCC Curb and Gutter, Complete in Place (SP 2.2.6)	635	LF		
BP.23*	Overexcavate Unsuitable Material and Backfill (SP 2.2.4) (Contingent Item)	4,000	CY		
BP.24	Pulverization of Existing Roadbed, Complete in Place (SP 2.2.12)	531,065	SF		
BP.25	6" Type 2, Class B, Aggregate Base Access Road, Complete in Place (SP 2.2.5)	350	CY		
BP.26	3" Plantmix Bituminous Pavement Type 2 Agg., PG 64-28NV on 6" Aggregate Base, Multi-Use Path, Complete in Place (SP 2.2.7)	64,370	SF		
BP.27	3" Plantmix Bituminous Pavement Type 2 Agg., PG 64-28NV on 6" Pulverized Material, Complete in Place (SP 2.2.7)	392,000	SF		
BP.28	4" Plantmix Bituminous Pavement Type 2 Agg., PG 64-28NV on 8" Pulverized Material, Complete in Place (SP 2.2.7)	139,065	SF		
BP.29	PCC Curb Ramps and Apron, Complete in Place (SP 2.2.6)	3	EA		
BP.30	PCC Sidewalk, 4-inch Thickness, Complete in Place (SP 2.2.6)	411	SF		
BP.31	Street Light Foundation and Appurtenances, Complete In Place (SP 2.2.11)	1	EA		
BP.32	4" SCH 40 PVC Conduit and Appurtenances, Complete in Place (SP 2.6.3)	58,100	LF		
BP.33	#7 Fiber Optic Pull Box, Complete in Place (SP 2.6.3)	27	EA		
BP.34	#9 Fiber Optic Pull Box, Complete in Place (SP 2.6.3)	15	EA		
BP.35	Permanent Pavement Paint (4-Inch Solid White), Complete in Place (SP 2.2.9)	9,083	LF		
BP.36	Permanent Pavement Paint (4-Inch Double Yellow), Complete in Place (SP 2.2.9)	1,790	LF		
BP.37	Permanent Pavement Paint (4-Inch Solid Yellow w/ 4-inch Broken Yellow), Complete in Place (SP 2.2.9)	680	LF		
BP.38	Permanent Pavement Paint (8-Inch Solid White), Complete in Place (SP 2.2.9)	1,700	LF		
BP.39	Permanent Pavement Paint (8-Inch Broken White), Complete in Place (SP 2.2.9)	5,053	LF		

## **BID PROPOSAL**

	Description	Scheduled Value	Unit	Unit Price	Total Price		
BP.40	Permanent Pavement Paint (8-Inch Solid Yellow), Complete in Place (SP 2.2.9)	50	LF				
BP.41	Permanent Pavement Paint (24-Inch Solid White), Complete in Place (SP 2.2.9)	225	LF				
BP.42	Permanent Pavement Paint (Turn Arrow White Symbol), Complete in Place (SP 2.2.9)	15	EA				
BP.43	Permanent Pavement Paint ("ONLY" White Symbol), Complete in Place (SP 2.2.9)	8	EA				
BP.44	Permanent Pavement Paint (Triangle Yield White Symbol), Complete in Place (SP 2.2.9)	5	EA				
BP.45	Permanent Pavement Paint (Merge Arrow White Symbol), Complete in Place (SP 2.2.9)	3	EA				
BP.46	Signage, Complete in Place (SP 2.2.10)	1	LS				
BP.47	Traffic Control, Complete in Place (SP 2.2.2)	1	LS				
BP.48	48-inch Sanitary Sewer Manhole, Complete in Place (SP 2.4.3)	24	EA				
BP.49	4-inch SDR 35 PVC Sewer Lateral, Complete in Place (SP 2.4.5)	65	EA				
BP.50	8-inch SDR 35 PVC Sewer Main, Complete in Place (SP 2.4.4)	6,332	LF				
BP.51	Adjust Existing Valve Box to New Finish Grade (SP 2.2.8)	1	EA				
BP.52	Air Release Valve Assembly (size per plan), Complete in Place (SP 2.3.5)	26	EA				
BP.53	Permanent Flush Valve Assembly (size per plan), Complete in Place (SP 2.3.5)	3	EA				
BP.54	8-inch Gate Valve, Complete in Place (SP 2.3.4)	4	EA				
BP.55	24-inch Butterfly Valve, Complete in Place (SP 2.3.4)	18	EA				
BP.56	18" Flow Meter Station and Appurtenances, Complete in Place (SP 2.3.6)	1	LS				
BP.57	16" Flow Meter Station and Appurtenances, Complete in Place (SP 2.3.6)	1	LS				
BP.58	12" and 16" Flow Control Station and Appurtenances, Complete in Place (SP 2.3.6)	1	LS				
BP.59	8-inch PVC C900 Water Main CL 125 and Appurtenances, Complete in Place (SP 2.3.3)	456	LF				
BP.59A	24-inch PVC C905 Water Main CL 125 and Appurtenances, Complete in Place (SP 2.3.3)	29,000	LF				
BP.59B	Subtotal Schedule A						
BP.59C	BP.59C Total Bid Price						
	Contingent Items						

<sup>\*</sup> Contingent Items

**BP.60** Total Bid Price Written in Words: