

**CARSON CITY PURCHASING AND CONTRACTS**  
**201 North Carson Street, Suite 3**  
**Carson City, NV 89701**  
**775-882-2133 extension 30137/FAX 887-2107**  
**<http://www.carson-city.nv.us/index.aspx?page=998>**

**NOTICE TO CONTRACTORS**

**BID #0910-127**

**Project A-Production Well 4 Remodel and Piping Modifications and Project  
B-Production Well 24 Phase II Upgrades  
Labor Commissioner PWP#CC-2010-104  
Public Works Project No. 4.0621 (Well 4) and 4.0703 (Well 24)  
Engineer's Estimate: \$650,000  
ARRA Funded**

January 12, 2010

Addendum No. 5

Please make the following additions/changes to the above referenced project.

**1. Special Conditions, Time of Performance of the Well #4 Project:**

- A. Due to bid time extension identified in Addendum #4, Well #24 will now be awarded on February 4. The project completion date shall be changed from May 15 to May 29 and the Well #24 project shall be totally complete by August 15, 2010.

**Make the following changes to the Plans;**

**2. Carson City Well #4 Remodel and Piping Modifications;**

- A. **Sheet C1/17.** Change the description of the vault shown in the sidewalk on east side of building from "Electrical Vault" to "Existing 8" Water Meter Vault". This vault, as well as the adjacent meter box, will be removed for installation of the new 12" water line and a new meter vault. Note: Existing flow meter will be returned to Carson City.
- B. **Sheet C4,C5/17.** Material lists and labeling on drawing have been corrected so they match. See revised sheets included with this addendum.

**3. Carson City Well #24 Phase II Upgrades;**

- A. **Sheet C1,C3,C4,C5/C22.** Material lists and labeling on drawing have been corrected so they match. Flush to waste plumbing (8") has been extended downward through the floor, then out to the west side of the building to a new concrete flush to waste structure using the same design as the well #4 flush to waste. The 16" Flush to waste drain pipe has been realigned to connect to the new flush to waste structure. See revised sheets included with this addendum.
- B. **Sheet L4/C22.** Detail 12 Backflow Preventer. A backflow enclosure is not required. The ¾" supply and delivery lines to and from the back flow device can be installed into the same trench as the new 12" water line, but below and off to one side of the new water line.

**Clarifications;**

- 4. A. The only items being provided by Carson City for the Well #4 site are as listed in the Special Conditions, which include one (1) new submersible pump (brand unknown at this time) and three (3) removable bollards.
- B. The only items being provided by Carson City for the Well #24 site are as listed in the Special Conditions, which include one (1) new vertical turbine pump and motor and discharge head assembly (brand is unknown at this time), 220' of 10" steel well column pipe and one (1) stick of 12" prefabricated, epoxy coated steel spool.
- C. All fabricated steel pipe shall be pressure rated to a minimum of 150 PSI.
- D. The existing 18" sewer main on the east side of the Well #4 site can only be plugged for by-pass pumping. Estimated Peak flow in the 18" sewer trunk main is 750 GPM. Contractor shall verify peak flows for any pumping requirements.

End of Addendum No. 5