

**CARSON CITY PURCHASING & CONTRACTS**

**201 North Carson Street Suite 3**

**Carson City, NV 89701**

**775-283-7137/ FAX 887-2107**

**<http://www.carson-city.nv.us/Index.aspx?page=998>**

**BID #0910-181**

**Carson City Municipal Well #50 and 24 Inch Water Line Construction**

**Labor Commissioner PWP# CC-2010-236**

**Public Works Project No. 4.0817**

**Engineer's Estimate: \$900,000.00**

April 16, 2010

**Addendum No. 2**

Please make the following additions/changes to the above referenced project.

**Make the following changes to the Plans;**

**1. Sheet C5/23. Well Head Material List;**

- A. Change Item B to say; "8 Inch check valve with break off plug"
- B. Change Item C to say; "8 Inch Schedule 40 steel well drop pipe and couplings".

**Clarifications;**

- 2. A. Approved Factory-Built, Factory Delivered, underground well Control Meter station, above grade sodium hypochlorite feed unit station and above grade electrical control cabinet Equipment Manufacturers include;

Engineered Fluids, Inc.

- B. All PVC water main pipe required for this project shall **NOT** be provided by JM Eagle.

- C. Electrical wire for new submersible pump and sounding tube shall be attached to the well column pipe every 20 feet with 4 wraps of 10 Mil plastic tape and secured with stainless steel bands.

**End of Addendum 2**