

BID PROPOSAL

BID # 1011-201

BID TITLE: NORTH/SOUTH WATER TRANSMISSION MAIN PROJECT-PHASE II

NOTICE: No substitution or revision to this Bid Proposal form will be accepted. Carson City will reject any Bid that is received that has changes or alterations to this document. Although the Prevailing Wages are provided in this bid document, the bidder is responsible to verify with the Labor Commissioner if any addendums have been issued. The successful bidder will be required to provide the current Prevailing Wages used in preparation of their bid within 24 hours of bid submission.

PRICES will be valid for sixty (60) calendar days after the bid opening which is indicated in the Notice to Contractors.

A COPY OF CONTRACTOR'S "CERTIFICATE" of eligibility issued by the State of Nevada Contractors' Board as proof of Bidder's compliance with the provisions of N.R.S. 338.147 must be submitted with his/her bid for the preference to be considered. This Statute does not apply to projects expected to cost less than \$250,000.

COMPLETION of this project is expected **PURSUANT TO THE BID DOCUMENTS.**

BIDDER acknowledges receipt of _____ Addendums.

SUMMARY

Description		Scheduled Value	Unit	Unit Price	Total Price
SCHEDULE A: 24-INCH WATER LINE WORK					
BP.1	Mobilization/Demobilization and Cleanup (SP 2.2.1)	1	LS		
BP.2	Clearing and Grubbing (SP 2.2.3)	265,000	SF		
BP.3*	Excavate and Export (SP 2.2.4) (Contingent Item)	4,000	CY		
BP.4	Excavate and Fill (SP 2.2.4)	8,900	CY		
BP.5	15-inch SDR 35 PVC Storm Drain, Complete in Place (SP 2.6.8)	76	LF		
BP.6	15-inch CMP Storm Drain, Complete in Place (SP 2.6.8)	49	LF		
BP.7	15-inch CMP Storm Drain w/ Flared End Sections, Complete in Place (SP 2.6.8)	97	LF		
BP.8	18-inch CMP Storm Drain, Complete in Place (SP 2.6.8)	50	LF		
BP.9	24-inch CMP Storm Drain, Complete in Place (SP 2.6.8)	112	LF		
BP.10	21"x15" CMP Storm Drain w/ Flared End Sections, Complete in Place (SP 2.6.8)	60	LF		
BP.11	15-inch Class III or Class IV RCP Storm Drain, Complete In Place (SP 2.6.8)	390	LF		
BP.12	15-inch Class IV RCP Storm Drain w/ Flared End Sections, Complete in Place (SP 2.6.8)	40	LF		
BP.13	30-inch Class III or Class IV RCP Storm Drain w/ Flared End Section, Complete in Place (SP 2.6.8)	40	LF		
BP.14	Outlet Structure and Appurtenances, Complete in Place (SP 2.6.9)	1	LS		
BP.15	Remove Existing Curb Inlet and Construct Type 4R Catch Basin, Complete in Place (SP 2.5.3)	2	EA		
BP.16	Type 200 Drop Inlet, Complete in Place (SP 2.6.9)	2	EA		

BID PROPOSAL

Description		Scheduled Value	Unit	Unit Price	Total Price
BP.17	24-inch Precast Drop Inlet, Complete in Place (SP 2.6.9)	2	EA		
BP.18	36-inch Precast Drop Inlet, Complete In Place (SP 2.6.9)	4	EA		
BP.19	Type 1 PCC Median Curb, Complete in Place (SP 2.2.6)	234	LF		
BP.20	Type 2 PCC Median Curb, Complete in Place (SP 2.2.6)	1183	LF		
BP.21	PCC Median Paving, Complete in Place (SP 2.2.6)	4,697	SF		
BP.22	Type 1 PCC Curb and Gutter, Complete in Place (SP 2.2.6)	635	LF		
BP.23*	Overexcavate Unsuitable Material and Backfill (SP 2.2.4) (Contingent Item)	4,000	CY		
BP.24	Pulverization of Existing Roadbed, Complete in Place (SP 2.2.12)	534,065	SF		
BP.25	6" Type 2, Class B, Aggregate Base Access Road, Complete in Place (SP 2.2.5)	350	CY		
BP.25A*	Type 2, Class B, Aggregate Base, Complete in Place (Contingent Item) (SP 2.2.5)	5,000	CY		
BP.26	3" Plantmix Bituminous Pavement Type 2 Agg., PG 64-28NV on 6" Aggregate Base, Multi-Use Path, Complete in Place (SP 2.2.7)	62,175	SF		
BP.27	3" Plantmix Bituminous Pavement Type 2 Agg., PG 64-28NV on 6" Pulverized Material, Complete in Place (SP 2.2.7)	395,000	SF		
BP.28	4" Plantmix Bituminous Pavement Type 2 Agg., PG 64-28NV on 8" Pulverized Material, Complete in Place (SP 2.2.7)	139,065	SF		
BP.29	PCC Curb Ramps and Apron, Complete in Place (SP 2.2.6)	3	EA		
BP.30	PCC Sidewalk, 4-inch Thickness, Complete in Place (SP 2.2.6)	411	SF		
BP.31	Street Light Foundation and Appurtenances, Complete In Place (SP 2.2.11)	1	EA		
BP.32	4" SCH 40 PVC Conduit and Appurtenances, Complete in Place (SP 2.6.3)	58,100	LF		
BP.33	#7 Fiber Optic Pull Box, Complete in Place (SP 2.6.3)	27	EA		
BP.34	#9 Fiber Optic Pull Box, Complete in Place (SP 2.6.3)	15	EA		
BP.35	Permanent Pavement Paint (4-Inch Solid White), Complete in Place (SP 2.2.9)	9,083	LF		
BP.35A	Permanent Pavement Paint (4-Inch Broken Yellow), Complete in Place (SP 2.2.9)	2,860	LF		
BP.36	Permanent Pavement Paint (4-Inch Double Yellow), Complete in Place (SP 2.2.9)	1,790	LF		
BP.37	Permanent Pavement Paint (4-Inch Solid Yellow w/ 4-inch Broken Yellow), Complete in Place (SP 2.2.9)	680	LF		
BP.38	Permanent Pavement Paint (8-Inch Solid White), Complete in Place (SP 2.2.9)	1,700	LF		
BP.39	Permanent Pavement Paint (8-Inch Broken White), Complete in Place (SP 2.2.9)	240	LF		

BID PROPOSAL

Description		Scheduled Value	Unit	Unit Price	Total Price
BP.40	Permanent Pavement Paint (8-Inch Solid Yellow), Complete in Place (SP 2.2.9)	50	LF		
BP.41	Permanent Pavement Paint (24-Inch Solid White), Complete in Place (SP 2.2.9)	225	LF		
BP.42	Permanent Pavement Paint (Turn Arrow White Symbol), Complete in Place (SP 2.2.9)	15	EA		
BP.43	Permanent Pavement Paint ("ONLY" White Symbol), Complete in Place (SP 2.2.9)	8	EA		
BP.44	Permanent Pavement Paint (Triangle Yield White Symbol), Complete in Place (SP 2.2.9)	5	EA		
BP.45	Permanent Pavement Paint (Merge Arrow White Symbol), Complete in Place (SP 2.2.9)	3	EA		
BP.46	Signage, Complete in Place (SP 2.2.10)	1	LS		
BP.47	Traffic Control, Complete in Place (SP 2.2.2)	1	LS		
BP.48	48-inch Sanitary Sewer Manhole, Complete in Place (SP 2.4.3)	24	EA		
BP.49	4-inch SDR 35 PVC Sewer Lateral, Complete in Place (SP 2.4.5)	65	EA		
BP.50	8-inch SDR 35 PVC Sewer Main, Complete in Place (SP 2.4.4)	6,332	LF		
BP.51	Adjust Existing Valve Box to New Finish Grade (SP 2.2.8)	1	EA		
BP.52	Air Release Valve Assembly (size per plan), Complete in Place (SP 2.3.5)	26	EA		
BP.53	Permanent Flush Valve Assembly (size per plan), Complete in Place (SP 2.3.5)	9	EA		
BP.54	8-inch Gate Valve, Complete in Place (SP 2.3.4)	4	EA		
BP.55	24-inch Butterfly Valve, Complete in Place (SP 2.3.4)	18	EA		
BP.56	18" Flow Meter Station and Appurtenances, Complete in Place (SP 2.3.6)	1	LS		
BP.57	16" Flow Meter Station and Appurtenances, Complete in Place (SP 2.3.6)	1	LS		
BP.58	12" and 16" Flow Control Station and Appurtenances, Complete in Place (SP 2.3.6)	1	LS		
BP.59	8-inch PVC C900 Water Main CL 125 and Appurtenances, Complete in Place (SP 2.3.3)	456	LF		
BP.59A	24-inch PVC C905 Water Main CL 125 and Appurtenances, Complete in Place (SP 2.3.3)	29,000	LF		
BP.59B	Total Bid Price				

* Contingent Items

BP.60 Total Bid Price Written in Words:

