

CARSON CITY PURCHASING AND CONTRACTS
201 North Carson Street, Suite 3
Carson City, NV 89701
775-283-7137/FAX 887-2107
<http://www.carson.org/index.aspx?page=998>

NOTICE TO CONTRACTORS
RFP #1213-184
Carson City Senior Center Floor Replacement Project
PWP# CC-2013-256

May 29, 2013

Addendum No. 2

Please make the following additions/changes to the above referenced project.

In response to questions raised at the pre-bid conference, make the following revisions to the plans:

1. Sheet A1, Detail 2: Revise fastening note to read "FASTEN EX. PLYWOOD W/ #8 X 3" SCREWS, 10d x 3" SCREW-SHANK NAILS, OR 10d X 3" RING-SHANK NAILS @ 6" O.C. EDGES/12" O.C. FIELD. FASTEN NEW PLYWOOD OR OSB WITH GLUE AND FASTENERS AS NOTED ABOVE."
2. Sheet S1, under FLOORING DEMOLITION NOTES, add: "5. WHERE JOISTS RUN PARALLEL TO WALLS, SAWCUT AND REMOVE PLYWOOD OVER JOIST CLOSEST TO WALL SO EDGE IS SUPPORTED. REMOVE FLOORING AND UNDERLAYMENT BETWEEN CUT AND WALL. 6. IN ROOM 101, THE FLOORING NORTH OF A POINT 20' FROM THE SOUTH WALL CONSISTS OF 2 LAYERS OF VCT TILE AND UNDERLAYMENT."
3. Sheet S1, under ROUGH CARPENTRY SPECIFICATIONS, add: "H. Add solid 2x4 blocking to support unsupported edges between joists adjacent to walls running east to west."
4. Sheet S1, Floor Framing Plan, revise note No. 2 in upper right corner to read: "REPLACE REMOVED PLYWOOD WITH MIN. 23/32" OSB OR PLYWOOD (MATCH EXISTING THICKNESS). GLUE TO JOISTS AND FASTEN WITH #8 X 3" SCREWS, 10d x 3" SCREW-SHANK NAILS, OR 10d X 3" RING-SHANK NAILS @ 6" O.C. EDGES/12" O.C. FIELD."

The bid date of June 5, 2013 remains unchanged.

End of Addendum 2