

**CARSON CITY PURCHASING AND CONTRACTS**  
**201 North Carson Street, Suite 3**  
**Carson City, NV 89701**  
**775-283-7137/FAX 887-2107**  
**<http://www.carson.org/index.aspx?page=998>**

**NOTICE TO CONTRACTORS**  
**BID #1314-184**  
**Sugarloaf Communication Site Project**  
**PWP # CC-2014-208**

May 15th, 2014

Addendum No. 1

Please see the responses below to the questions received by 5/14/2014.

1. *Should bidders use the same frequencies on the future microwave antennas as shown on the initial antennas?*

Tower structural design shall be performed based on the antenna size described in the equipment table on sheet C5 not the frequency of the antenna to be installed. Per SC.1 the mounting frames are to be furnished and installed. No antennas are to be furnished/installed under this project.

2. *What appurtenances are to be included with the tower steel such as climbing facilities, waveguide ladders, grounding, etc.?*

See SC – 1, Scope of Work of the contract documents for appurtenances. Paragraph two explains tower appurtenances.

3. *Is this tower 3 or 4 legged?*

4 legged, see SC 4.2.4 of the contract document.

4. *What are the dimensions of the twelve (12) LTE Sector Antennas located at the 70' elevation on the Tower Equipment Schedule?*

CommScope - 698-896 MHz 15.5dBd Dual Polarized Panel Antenna  
LTE antenna  
L= 96.3" x W=11.9" x D=7.1  
Weight 63lbs

End of Addendum 1