

**NOTICE TO CONTRACTORS
CARSON CITY PURCHASING AND CONTRACTS
201 NORTH CARSON STREET, SUITE 3
CARSON CITY, NEVADA 89701
775-283-7137 / FAX 775-887-2107
<http://www.carson.org/Index.aspx?page=998>**



**ADVERTISED BID #1415-171
BID TITLE "Clear Creek Avenue Sanitary Sewer
Extension"
Labor Commissioner PWP# CC-2015-177
Engineer's Estimate: \$950,000**

PLEASE NOTE: Carson City has extensively revised these Contract Documents and all Bidders are advised to read these documents thoroughly before submitting a bid.

SUMMARY

Carson City is accepting sealed bids for all labor, materials, tools and equipment necessary for the Clear Creek Sanitary Sewer Extension Project. The project consists of constructing approximately, 2,500 lineal feet of sewer line, and 1700 lineal feet of storm sewer, 700 lineal feet of water line as well as their associated appurtenances. This project also includes pulverizing the existing road and placing approximately 64,000 square feet of new asphalt, as well as curb and gutter, driveway aprons, spandrel and valley gutter, and pedestrian curb ramps. The project includes all common phases of construction customarily associated with this type of project. Sealed bids must be submitted in accordance with the bid documents, drawings and plans, specifications and special conditions related hereto.

CONTRACTOR'S LICENSE: Carson City has determined that the responsive bidder must possess a minimum of a Class A license with appropriate sub-classifications or subcontractors. All Contractors license shall be in good standing and issued by the Nevada State Contractor's Board at the time of the bid.

BID DOCUMENTS may be obtained as follows and the cost is non-refundable.

You may download this Bid Document, excluding the drawings, and a pdf version of the Bid Bond and Bid Proposal to prepare your bid from the Carson City website <http://www.carson.org/Index.aspx?page=998>.

Downloading this bid document from the website does not put you on the plan holders list, you must click the link at the bottom of the page and provide your information to add your company name to the plan holders list.

You may purchase the drawings separately from the following businesses, please call ahead to place your order.

Nevada Blue, 3246 North Carson Street, Carson City, NV 89706 (775) 883-6011 www.nvblue.com

OSI, Inc., 4750 Longley Lane, Suite 103, Reno, NV 89502 (775) 827-4343 www.osireno.com

Sierra Contractor's Source, 860 Maestro Dr., Suite B, Reno NV 89511 (775) 329-7222
www.scsplanroom.com

INSPECTION OF BID DOCUMENTS: All documents related hereto may be viewed at the following locations:

CARSON CITY PUBLIC WORKS DEPARTMENT, 3505 Butti Way, Carson City, Nevada 89701.

ADDENDA: All addenda are posted on Carson City's website <http://www.carson.org/Index.aspx?page=998>. It is each bidder's responsibility to ensure that they have received all addenda prior to submission of their sealed bid.

INFORMAL PRE-BID CONFERENCE will not be held.

QUESTIONS regarding this bid must be received a minimum of eight (8) days prior to bid opening.

SEALED BIDS must be submitted in a sealed envelope which shall be clearly marked with title and number of this Bid Document to Carson City Purchasing and Contracts Department, 201 North Carson Street, Suite 3, Carson City, Nevada 89701, by not later than 11:00 a.m. on May 27, 2015. Bids received after the date and time set for receipt will be **REJECTED** and returned to the bidder unopened.

BID OPENING will be held publicly at 11:10 a.m. on May 27, 2015, at 201 North Carson Street, Suite 3, Carson City, Nevada 89701. Bidders, their representatives, and all other interested persons may be present during the bid opening.

A tabulation of the **BID PROPOSAL** will be posted on Carson City's website within 48 hours.

AWARD RECOMMENDATION will be made by the Carson City Purchasing and Contracts Department. You are encouraged to visit the City's website for that recommendation or contact Kim Belt at KBelt@carson.org for the recommendation.

NOTICE OF PROTEST OF AWARD OF CONTRACT must be in compliance with NRS 338.142 and submitted in writing to the Carson City Purchasing and Contract Department of the Division of Finance (Department) at City Hall, 201 N. Carson Street, #3, Carson City, NV 89701 within five (5) business days after the date the Director of such Department or the City's Public Works Director, as the City's authorized representative, makes a recommendation to the award the contract.

The notice of protest must include a written statement setting forth with specificity the reasons the person filing the notice believes the applicable provisions of law were violated.

A person filing a notice of protest may be required by the City's Public Works Director or its Purchasing and Contracts Manager, at the time or soon after the notice of protest is filed, to post a bond with a good and solvent surety authorized to do business in this state or submit other security, in a form approved by such authorized representative of the City and the City shall hold the bond or other security until a determination is made on the protest. A bond posted or other security submitted with a notice of protest must be in an amount equal to the lesser of Twenty-five percent of the total value of the bid submitted by the person filing the notice of protest; or Two hundred fifty thousand dollars.

A notice of protest filed under these provisions operates as a stay of action in relation to the awarding of any contract until a determination is made by the City's Board of Supervisors on the protest.

A person who makes an unsuccessful bid may not seek any type of judicial intervention until the City's Board of Supervisors has made a determination on the protest and awarded the contract.

Neither the City's Board of Supervisors nor any authorized representative of the City or such public body is liable for any costs, expenses, attorney's fees, loss of income or other damages sustained by a person who makes a bid, whether or not the person files a notice of protest pursuant hereto.

If the protest is upheld, the bond posted or other security submitted with or soon after the submission of the notice of protest must be returned to the person who posted the bond or submitted the security. If the protest is rejected, a claim may be made against the bond or other security by the City's Board of Supervisors in an amount equal to the expenses incurred by the City or its Board of Supervisors because of the unsuccessful protest. Any money remaining after the claim has been satisfied must be returned to the person who posted the bond or submitted the security.

BID AWARD will be made by the Carson City Board of Supervisors and is scheduled for June 18, 2015 and their decision is final. The Carson City Board of Supervisors meeting will be held in the Sierra Room of the Carson City Community Center, 851 East William Street, Carson City, Nevada 89701 beginning at 8:30 a.m.

PRICES must be quoted FOB Carson City, Nevada and are valid for sixty (60) calendar days after the **BID OPENING**.

Signature in Project File

Kim Belt, CPM
Purchasing and Contracts Manager

Signature in Project File

Darren Schulz, Public Works Director

TABLE OF CONTENTS

SECTIONS	PAGE
Notice to Contractors	NC-1 thru NC- 3
Table of Contents	TOC-1 thru TOC-3
Instructions to Bidders	ITB-1 thru ITB-9
Bid Proposal Forms	BP-1 thru BP-17
Bid Bond	
Bid Proposal Summary	
Contract Award	CA-1 thru CA-5
Sample Contract and Bonds (For Use after Bid Opening)	CO-1 thru CO-16
Sample Contract	
Performance Bond	
Labor and Material Payment Bond	
General Conditions	GC-1 thru GC-9
Section 1.0 Intent, Definitions, Abbreviations	GC-1
GC 1.1 Intent of Contract Documents	GC-1
GC 1.2 Partial Invalidity	GC-1
GC 1.3 Governing Order of Bidding and Contracting Documents	GC-1
GC 1.4 Headings	GC-2
GC 1.5 Definitions	GC-2
GC 1.6 Abbreviations	GC-7
Section 2.0 Contract Administration and Responsibilities: Owner’s Representative, Construction Manager, Design Consultant, and Contractor	GC-10 thru GC-22
GC 2.1 Administration	GC-10
GC 2.2 Owner’s Representative	GC-10
GC 2.3 Construction Manager	GC-10
GC 2.4 Design Consultant	GC-11
GC 2.5 City	GC-12
GC 2.6 Contractor	GC-14
Section 3.0 Progress of Work, Meeting, Schedules	GC-23 thru GC-32
GC 3.1 Beginning of Work	GC-23
GC 3.2 Performance of the Work	GC-23
GC 3.3 Plans and Specifications Furnished by the City	GC-23
GC 3.4 Order of Work	GC-23
GC 3.5 Time of Completion	GC-23
GC 3.6 Means and Methods	GC-23
GC 3.7 City-furnished Materials	GC-24
GC 3.8 Defective and Unauthorized Work	GC-24
GC 3.9 Pre-construction Conference	GC-24
GC 3.10 Progress Meetings	GC-25
GC 3.11 Construction Schedules	GC-25
GC 3.12 Notice of Delays	GC-28
GC 3.13 Liquidated Damages	GC-29
GC 3.14 Rights Beyond Liquidated Damages	GC-29
GC 3.15 Extension of Time	GC-29
GC 3.16 Temporary Suspension of Work	GC-30
GC 3.17 Protection of Antiquities	GC-30
GC 3.18 Contract Termination	GC-31
GC 3.19 City’s Right to Terminate for Convenience	GC-32
GC 3.20 Work During Disputes and Litigation	GC-32
GC 3.21 Lands and Right-of-way	GC-32

TABLE OF CONTENTS

SECTIONS	PAGE
GC 3.22	Waiver of Rights GC-32
Section 4.0	Shop Drawings and Quality Control/inspections GC-33 thru GC-35
GC 4.1	Contractor's Responsibilities GC-33
GC 4.2	Source of Materials GC-33
GC 4.3	Transmittal Procedures GC-33
GC 4.4	Review Procedure GC-34
GC 4.5	Quality Control B General GC-35
Section 5.0	Payment GC-38 thru GC-40
GC 5.1	General GC-38
GC 5.2	Payment for Patents and Patent Infringement GC-38
GC 5.3	Payment of Taxes GC-38
GC 5.4	Payment for Labor and Materials GC-38
GC 5.5	Partial Payments GC-38
GC 5.6	Retention GC-39
GC 5.7	Other Withholds GC-40
Section 6.0	Change Orders GC-41 thru GC-48
GC 6.1	General GC-41
GC 6.2	Differing Site Conditions GC-41
GC 6.3	Resolution of Disputes GC-42
GC 6.4	Modification Procedures GC-43
GC 6.5	Disputes GC-47
GC 6.6	Arbitration GC-47
Section 7.0	Construction Facilities and Temporary Controls GC-49 thru GC-59
GC 7.1	General GC-49
GC 7.2	Temporary Utilities and Construction Facilities GC-49
GC 7.3	Construction Controls GC-50
GC 7.4	Public Safety/convenience and Traffic Controls GC-54
GC 7.5	Project Signs GC-56
GC 7.6	Project Office GC-56
GC 7.7	Storage of Materials GC-56
GC 7.8	Hazardous Materials GC-56
GC 7.9	System Testing GC-57
GC 7.10	Coordination/cooperation with Utilities GC-57
GC 7.11	Contaminated Groundwater And/or Soil GC-58
GC7.12	Dust Control GC-58
GC7.13	By-Pass Pumping of Sanitary Sewer GC-59
Section 8.0	Contract Completion, O& M Manuals GC-60 thru GC-63
GC 8.1	Intermediate Completion GC-60
GC 8.2	Substantial Completion GC-60
GC 8.3	Construction Completion, Final Inspection, Payment, and Acceptance GC-60
GC 8.4	Operation and Maintenance Manuals GC-61
GC 8.5	Equipment Start-up GC-61
GC 8.6	Final Clean up GC-61
GC 8.7	Warranty of Title GC-61
GC 8.8	Record Drawings GC-62
GC 8.9	Warranty GC-62 Warranty Form GC-63
Section 9.0	Prevailing Wage GC-64 thru GC-66
GC 9.1	Prevailing Wage Rates GC-64
GC 9.2	No Extra Compensation GC-66

TABLE OF CONTENTS

SECTIONS	PAGE
Special Conditions	SC-1 thru SC-21
Technical Specifications	TS-1 thru TS-57
Attachment A 2015 Prevailing Wage Rates for Carson City	A-1 thru A-32
Drawing Sheets (23 Sheets)	
No.	Title
G1	Title Sheet
G2	Notes, Legend and Abbreviations
G3	Construction Notes
G4	Horizontal Control Plan and Sheet Index
C1	Sewer Plan and Profile STA 24+00 to STA 30+50
C2	Sewer Plan and Profile STA 30+50 to STA 38+00
C3	Sewer Plan and Profile STA 38+00 to STA 45+50
C4	Sewer Plan and Profile STA 45+50 to STA 48+00
C5	Street Plan – Typical Roadway Sections
C6	Street Plan and Profile STA 24+00 to STA 30+50
C7	Street Plan and Profile STA 30+50 to STA 38+00
C8	Street Plan and Profile STA 38+00 to STA 45+50
C9	Street Plan and Profile STA 45+50 to STA 48+00
C10	Enlarged Plan
C11	Storm Drain Profiles
C12	Constriction Details
C13	Constriction Details
C14	Constriction Details
C15	Storm Drain Details
C16	Paving Details
C17	Paving Details
C18	Signing and Striping Plan
C19	Signing and Striping Plan

INSTRUCTIONS TO BIDDERS

CORRESPONDENCE AND/OR COMMUNICATIONS:

The provisions of this contract shall be approved by the governing body of the City, and the normal lines of communications shall be between the following persons and the authorized representative of the Contractor:

- A. Contract Administrator**
Kim Belt, CPM - Purchasing and Contracts Manager
Carson City Purchasing and Contracts
201 North Carson Street, Suite 3
Carson City, Nevada 89701
775-283-7137
FAX 775-887-2107
KBelt@carson.org

- B. Owner's Representative**
Darren Schulz, Public Works Director
Carson City Public Works Department
3505 Butti Way
Carson City, Nevada 89701
775-887-2355
FAX No. 775-887-2112
DSchulz@carson.org

- C. Construction Manager**
Rick Cooley, Construction Manager
Carson City Public Works Department
3505 Butti Way
Carson City, Nevada 89701
775-887-2355
FAX No. 775-887-2112
rcooley@carson.org

NOTE: The City reserves the right to appoint a substitute designee for these positions at the City's discretion.

END OF DOCUMENT

INSTRUCTIONS TO BIDDERS

B.1 BIDDING PROCEDURES

A. Pre-bid Conference

If required, a Pre-bid Conference will be held at the time and place indicated on the Notice to Contractors. The purpose of this conference is to discuss the Project, prospective Bidders concerns, and key issues of the Project. Attendance is not mandatory unless otherwise indicated.

B. Designated Contacts

The designated contact for questions pertaining to the Contract Documents, Specifications and/or Drawings is the designated Contract Administrator. All questions should be submitted in writing, and will receive a written response from the Contract Administrator.

C. Contract Drawings

The Contract Drawings used for Bidding shall have the following title:

CONTRACT DRAWING TITLE: **“Clear Creek Avenue Sanitary Sewer Extension”**

The Contract Drawings do not purport to show all the details of the Work. They are intended to illustrate the character and extent of the performance desired under the Contract; therefore, they may be supplemented or revised from time to time, as the Work progresses, by the Construction Manager. Drawing revisions and/or additional drawings or sketches will be made and furnished to the Contractor if they are deemed necessary to adequately illustrate the Work.

D. Interpretations and Addenda

Bidder shall take no advantage of any apparent error or omission in this Bid Document. In the event the Bidder discovers such an error or omission, he/she shall immediately notify the City’s Contract Administrator in writing or by email. Carson City will then make such corrections and interpretations as may be deemed necessary for fulfilling the intent of this Bid Document through the issuance of an Addendum. Any Addendum or clarification supplementing this Bid Document, the Drawings, and the Specifications, issued prior to the date and time set for the submittal of Bid Proposal shall be made part of the Contract.

If it becomes necessary to revise any part of this Bid Document, a written addendum will be provided to all plan holders. The City is not bound by any oral representations, clarifications, or changes made by Carson City employees, or representatives, unless such clarification or change is provided to all Bidders in written addendum form.

Addenda shall be sent by fax, e-mail or posted on the City’s website to all who are known by the City to have received a complete set of Bid Documents (plan holders). No Addendum shall be issued by Carson City less than two (2) working days prior to the advertised date and time for Bid submittal. **Note:** Bidders are requested to submit questions four (4) working days prior to the advertised date and time for Bid submittal.

Prior to submission of the Bid Proposal, each Bidder shall ascertain that he/she has received all Addenda issued. The Bidder shall acknowledge receipt of all Addenda by completing the acknowledgment space provided on the Bid Proposal.

E. Bid Preparation and Submission

1. Bid proposals are to be submitted on the Bid Proposal provided and must be manually signed by pen by an officer or authorized agent (with attached power of attorney) of the Bidder. All figures must be written in ink or typewritten. Figures written in pencil or erasures are not acceptable. Any interlineation or alteration must be initialed in ink by a person authorized to bind the Bidder to a Contract. If the person making said interlineation or alteration is not the same person who signs the Bid Proposal, such person must write his/her signature and print his/her name and title on each page of the Bid Proposal where initials appear. Written delegation of signature authority to an agent acting on behalf of the Bidder must accompany the sealed Bid and cannot contain any language which states the Bidder retains final approval of acceptance of any of the terms, conditions, specifications and/or finalized Contract.

INSTRUCTIONS TO BIDDERS

- Each Bid shall be submitted in a sealed envelope and the envelope must be prominently marked on the lower left corner as follows:

SEALED BID

BID NO.: 1415-171

OPENING: May 27, 2015 at 11:10 am

COMPANY NAME:

- Carson City will not consider a Bid that fails to comply with the above stated requirements. Carson City will not be responsible for the premature opening of a Bid not properly addressed or identified. All Bids must be received prior to the date and time specified in the Notice to Contractors at the following address:

**Carson City Purchasing and Contracts Department
201 North Carson Street, Suite 3
Carson City, Nevada 89701**

- If forwarded by mail, the sealed envelope containing the Bid must be enclosed in another envelope addressed as specified. Mailed Bids must be received by the Purchasing and Contracts Department prior to the closing date and time for receipt of Bids in order to receive consideration. Bids submitted by facsimile or email will not be accepted or considered.

F. Documents Necessary for Submittal

The Bid Bond, Bid Proposal Summary, Bidder's Preference Certificate of Eligibility (if applicable) and any other documents required as defined in the Special Conditions all shall be included in the sealed envelope. **Do not return the entire spec book with the Bid.** Carson City will not consider a Bid received if there is an omission of or failure to complete any portion of the required documents at the time of the Bid Opening.

G. Bid Security

- Each Bid Proposal must be accompanied by a Cashier's check, Certified Check, or Bid Bond acceptable to Carson City in an amount equal to at least five percent (5%) of the Bidder's "Base Bid" Proposal. Said Bid Security shall be payable without condition to Carson City as a guarantee that the Bidder, if awarded the Contract, will promptly execute such Contract in accordance with the Bid Proposal and, in the manner and form required by the Bid Document, and will furnish the required PERFORMANCE and PAYMENT bonds. (Refer to Documents # 2151 and 2152). Should the Bidder refuse to enter into such Contract or fail to furnish such bonds, the amount of the Bid Security may be forfeited to the City as liquidated damages, not as penalty. All checks must indicate the Payee as "Carson City, Nevada" and reflect the Bid Title and Number. Failure to enclose a Bid guarantee with the sealed Bid will cause the Bid to be rejected and not considered.
- Surety companies issuing bonds must be licensed to issue surety by the State of Nevada Insurance Division pursuant to NRS 683A.090 and issued by an appointed agent pursuant to NRS 683A.280. Bonds issued by an individual surety are not acceptable to the City.
- The City will have the right to hold the Bid Security of Bidders to whom an award is being considered until either: (a) the Contract has been executed and bonds have been furnished, (b) the specified time has elapsed so that Bids may be withdrawn, or (c) all Bids have been rejected.

H. Quantities

The quantities given in the Bid Document or indicated by the unit Bid items are approximate quantities and are intended to illustrate the Scope of Work. The Bidder shall be responsible for verifying the exact quantities involved each month through the measurement and payment provisions of the Bid Document.

INSTRUCTIONS TO BIDDERS

I. Compensation

The Total Bid Price shall cover all Work required by the Bid Document. All costs in connection with the proper and successful completion of the Work, including furnishing all materials, equipment, supplies, and appurtenances; providing all construction equipment, tools and temporary utilities; and performing all necessary labor and supervision to fully complete the Work, shall be included in the unit and lump sum prices Bid. All work not specifically set forth as a pay item in the Bid Proposal shall be considered a subsidiary obligation of the Bidder, and all costs in connection therewith shall be included in the prices Bid.

J. Schedule of Values

The purpose of the Schedule of Values shall serve the City in two (2) distinct areas:

1. **PRIOR TO AWARD OF BID:** Carson City may request a Schedule of Values for any or all item(s) included in the Bid Proposal for the purpose of determining an unbalanced Bid. The analysis shall be conducted by the City.
2. **AFTER AWARD OF BID** Carson City will request a Schedule of Values for any or all item(s) included in the Bid Proposal for the purpose of making partial payments to the Contractor.

Under no circumstances may any Bid item reflected as LUMP SUM or otherwise be increased or decreased as a result of the Lump Sum Bid breakdown analysis.

All prospective Bidders may be required to prepare a Schedule of Values, and it shall be the Bidder's responsibility to verify the quantities as shown on the Drawings before preparing his/her Bid. The schedule as shown on the Contract Drawings does not constitute a complete outline of the Work to be performed by the Contractor in accordance with the Contract Drawings and Specifications. This list is intended to include all major items, and the Bid computed therefrom will be the maximum compensation for all work and materials furnished by the Contractor in order to comply with the Contract Drawings and Specifications, whether or not indicated in the approximate quantities or pertaining to the items of Work listed therein.

K. Validity of Bid

Carson City reserves the right to withhold award of the Contract for a period of sixty (60) days from the date of the Bid opening. The Bidder acknowledges in submitting his/her Bid that all prices listed in the Bid Proposal are valid for a period of not less than sixty (60) days from the date of the Bid Opening.

L. Bidders Preference

Bidders submitting a proposal to a public body for a Public Work shall bear the responsibility to ascertain the relevancy of the "preference for certain contractors" referenced in NRS 338.147. Bidders claiming preference shall submit with their Bid Proposal the "Certificate of Eligibility" issued by the State of Nevada Contractor's Board as proof of Contractor's compliance with the provisions of NRS 338.147. Failure to submit the Certificate of Eligibility with your Bid shall result in a waiver of any Bidder preference.

Note: Pursuant to Subsection 8 of NRS 338.147, the provisions of Subsection 2 of NRS 338.147 do not apply to any Contract for a Public Work which is expected to cost less than \$250,000.

M. Bidders Representation

Each Bidder by submitting its Bid represents that:

1. The Bidder, signing the Proposal summary and submitting the bid represents that he/she has familiarized himself with the Notice to Contractors, Contract Drawings, Specifications, and Contract Documents and has found them fit and sufficient for the purpose of preparing his/her Bid. By submission of his/her Bid, he/she agrees to all the terms and conditions of the Bid Document and further agrees that no claim will be made against the City, the Construction Manager, or the Design Consultant for any damage that he/she or his/her subcontractors may have suffered due to the inadequacy of his/her Bid on account of any alleged errors, omissions, or other deficiencies in the Notice to Contractors, Drawings, Specifications, or Contract Documents supplied to him/her by the City.

INSTRUCTIONS TO BIDDERS

2. The submission of a Bid shall constitute an acknowledgment upon which the City may rely that the Bidder has thoroughly examined and is familiar with the Bid Documents. The Bidder shall in no way be relieved from any obligation with respect to its proposal or to the Contract. No claim for additional compensation will be allowed which is based upon a lack of knowledge of the Contract Documents.
3. The Bidder has inspected the site(s) of the Work and is satisfied, by personal examination or by other means, of the locations of the proposed Work, of the actual conditions, including subsurface conditions, of and at the site(s) of the Work. If, during the course of its examinations, a Bidder finds facts or conditions which appear to be in conflict with the letter or spirit of the Bid Documents before submitting his/her bid, the Bidder shall request the City, in writing, to provide additional information and explanation.
4. Submission of a Bid by a Bidder shall constitute conclusive evidence that the Bidder has relied on his/her own examination of (1) the site of the Work, (2) access to the site, (3) all other data and matters requisite to the fulfillment of the Work and on its own knowledge of existing facilities on and in the vicinity of the site of the Work to be constructed under the Contract, (4) the conditions to be encountered, (5) the character, quality and scope of the proposed Work, (6) the quality and quantity of the materials to be furnished, and (7) the requirements of the Bid, the Drawings and Specifications. The Bidder is aware that soil classifications do not represent any particular stability or drainability characteristics, and are aware that water table levels can vary.
5. The information provided by the City is not intended to be a substitute for, or a supplement to, the independent verification by the Bidder to the extent such independent investigation of site conditions is deemed necessary or desirable by the Bidder.
6. The Bidder, by signing the Bid Proposal, agrees that all material and workmanship on this Project shall meet or exceed OSHA standards and NOSHA standards.

Bidder must be duly qualified and possess the classification(s) of contractor's license stipulated by the City for this particular Work and issued by the Nevada State Contractor's Board. Nevada Contractor's License type, number, expiration date and dollar limit must be indicated on the Bid Proposal. The Bidders and the successful Contractors and their subcontractors shall comply with all provisions of NRS Chapter 624 and Nevada Administrative Code, Chapter 624. Carson City will not consider any Bid that fails to comply with these requirements.

The successful Bidder must obtain a valid Carson City Business License within ten (10) days after the award of the Contract, or the Contractor will be declared in default of the contract.

N. Fair Employment Practices

Pursuant to NRS 338.125, it is unlawful for any Contractor in connection with the performance of work under a contract with a public body, when payment of the contract price, or any part of such payment, is to be made from public money, to refuse to employ or to discharge from employment any person because of race, creed, color, national origin, sex, sexual preference, or age to discriminate against person with respect to hire, tenure, advancement, compensation or other terms, conditions, privileges of employment because of race, creed, color, national origin, sex, sexual preference or age.

O. Subcontracting

The Bidder agrees that he/she will perform work totaling at least Fifty per cent (50%) of the Bid amount and will not subcontract work totaling more than Fifty per cent (50%) of the Bid amount.

The Bidder shall be bound by and comply with NRS 338.141 to limit the practice of shopping for Bids and shall provide a Subcontractors Listing with the submission of their Bid. The form must have the spaces filled in for each subcontractor who will be paid an amount exceeding five percent (5%) of the Bid amount. Within two (2) hours after the opening of Bids, the bidders who submitted the three lowest Bids must submit a list of names of each subcontractor who will provide labor or a portion of the Work or improvement to the Contractor for which he/she will be paid an amount exceeding one percent (1%) of the Bid amount or Fifty Thousand Dollars (\$50,000), whichever is greater

INSTRUCTIONS TO BIDDERS

The bidder shall verify prior to submitting their Bid that all subcontractors specified are properly licensed. Substitutions of subcontractors specified in the Bid shall comply with the requirements of NRS 338.141.

Bidder agrees that if awarded the Contract, he/she will assume responsibility for acts or omissions of subcontractors and of persons either directly or indirectly employed by them, as they are responsible for the acts or omissions of persons directly employed by the Bidder. Nothing contained in the Bid Document shall create any contractual relationship between any subcontractor and the City.

Each Contractor engaged on a public works project shall report to the Labor Commissioner the name and address of each Subcontractor whom he/she engages for work on the project within ten (10) days after the Subcontractor commences work on the contract.

Substitutions for subcontractors listed in the Bid Proposal shall comply with the requirements of NRS 338.141.

P. Site Information

Where investigations of surface or subsurface conditions have been made by the City, in respect to foundations or other structural design for design purposes only, said information is available only for the convenience of bidders but are not a part of the Bid Documents. The City, Construction Manager, and Design Consultant assume no responsibility whatsoever as to the sufficiency of borings, or of the log of test borings or other investigations, or tests, or of the interpretations thereof; there is no guarantee, warranty, or representation, expressed or implied, that the conditions indicated thereby, in fact, exist or are representative of those existing throughout the work. Such information available to bidders is not to be construed in any way as a waiver of the other provisions of this paragraph and bidders must satisfy themselves through their own investigations as to the surface and subsurface conditions to be encountered at the Site.

IB.2. OPENING OF BIDS

All Bids received at the designated time and place that comply with these requirements will be opened, publicly read aloud at the date, time and place set forth in the Notice to Contractors. Bidders, their representatives, and all other interested persons may be present at the opening and reading of Bids.

Any Bids received after the date and time set for receiving and opening Bids, as set forth in the Notice to Contractors and any Addendum, will not be considered. Any such Bids will be returned unopened to the Bidder.

A. Mistake in Bid

A request for withdrawal of a Bid due to a purported error shall not be considered unless it is given in writing to the Contract Administrator by the Bidder within forty-eight (48) hours after opening of the bid. Any such request shall contain a full explanation of any purported error and shall be supported by the original calculations on which the Bid was computed, together with a certification and notarization thereon that such calculation is the original as prepared by the Bidder or his/her agent.

In the case of a difference between written words and figures, the amount stated in written words shall govern for a Lump Sum Bid.

In the case of a difference between Unit Price and the Extended Price, the Unit Price shall govern.

B. Withdrawal of Bid

1. **Before Bid Opening** - A Bidder may request withdrawal of his/her, sealed Bid prior to the scheduled date and time of the scheduled Bid opening provided the request is submitted to the Contract Administrator's Office in writing or an authorized representative must present himself with proper identification to the Contract Administrator's Office and verbally request that the Bid be withdrawn.
2. **After Bid Opening** - No Bids may be withdrawn for a period of sixty (60) calendar days after the date and time of Bid opening, except as set forth in A above. All responsive and responsible Bids received are considered firm offers for the time period specified above and may be considered for award. The Bidder's offer will expire at the time specified above or upon acceptance by City,

INSTRUCTIONS TO BIDDERS

which occurs when the successful Bidder provides the bonds, insurance, and submits the signed Contract to the City for execution and the City executes the Contract.

IB.3 AWARD OF CONTRACT/REJECTION OF BIDS/DISQUALIFICATION OF BIDDERS

A. Award of Contract

Carson City will award the Contract pursuant to the provisions of Nevada State law including but not limited to:

- (a) Chapter 332 (Purchasing: Local Governments)
- (b) Chapter 338 (Public Works Projects)
- (c) Chapter 339 (Contractor's Bonds on Public Works)
- (d) Chapter 624 (Contractors).

B. Rejection of Bids

The City reserves the right to waive any informality or irregularity in any Bid received, and to reject any or all Bids. In the case of rejection of all Bids, the City reserves the right to advertise for new Bids or to proceed to do the Work otherwise if, in the judgment of the Carson City Board of Supervisors or Carson City Regional Transportation Commission, it is in the best interest of the City.

C. Irregular Bid

A Bid shall be considered irregular for the following reasons, any one or more of which may be cause for rejection:

1. If the Bid Proposal furnished by the City is not used or is altered.
2. If there are unauthorized additions, conditional or alternate Bids, or omissions or irregularities of any kind, which may tend to make the Bid incomplete, indefinite or ambiguous as to its meaning, or give the Bidder submitting the same a competitive advantage over other Bidders.
3. If the Bid submitted contains any erasures, interlineations, or other corrections unless each such correction is prepared and authenticated in acceptance with the provisions of Paragraph IB.1.E (1).

D. Unbalanced Bid

If the Unit Bid Item prices and/or schedule of values of a prospective Bidder's Bid are obviously unbalanced, either in excess or below the reasonable cost analysis values, in the opinion of the Owner's Representative, the Bid may be rejected. All Bids with separately priced line items shall be analyzed to determine if the prices are unbalanced. A bid may be rejected if the City determines that the lack of balance poses an unacceptable risk to the City.

A Bid with unbalanced pricing may increase performance risk and could result in payment of unreasonably high prices. Unbalanced pricing exists when, despite an acceptable total evaluated price, the price of one or more bid items is significantly over or understated as indicated by the application of cost or price analysis techniques. The greatest risks associated with unbalanced pricing occur when:

1. Over pricing of startup work, mobilization, or early items of work (front end loading) would cause a bidder to receive substantial up-front payment;
2. Base quantities and option quantities are separate line items;
3. The quantities as bid are incorrect and the contract cost will be increased when quantities are corrected;
4. On items where the quantities may vary, if the anticipated variation in quantity would result in the lower Bidder not remaining as the low Bidder;

INSTRUCTIONS TO BIDDERS

E. Disqualification of Bidders

Any one or more of the following may be considered as sufficient for the disqualification of a prospective Bidder and the rejection of the Bid:

1. The Bidder is not responsive or responsible;
2. The quality of the services, materials, equipment or labor offered does not conform to the approved Contract Drawings and specifications;
3. Evidence of collusion among prospective Bidders; (Participants in such collusion will receive no recognition as Bidders)
4. Lack of the contractor's license classification stipulated by Carson City for this Work;
5. More than one Bid for the same work from an individual, firm, or corporation under the same or different name;
6. Lack of competency, understanding of the scope of the Work, adequate machinery, plant and/or equipment as revealed by the requested experience or subcontractor information;
7. Unsatisfactory performance record as shown by past work for the City, judged from the standpoint of workmanship, progress, and quality of services/goods provided;
8. Uncompleted work which, in the judgment of the City, might hinder or prevent the prompt completion of additional work, if awarded;
9. Failure to pay or satisfactorily settle all bills due for labor and material on any contract(s);
10. Failure to comply with any requirements of the City;
11. Failure to list, as required, all subcontractors who will be employed by the Bidder;
12. Negative actions against the Contractor's license by any Federal, State or Local department or agency;
13. Any other reason determined, in good faith, to be in the best interest of the City.

IB.4 BID PROTESTS

A Bidder may file a Notice of Protest regarding the awarding of the contract in accordance with NRS 338.142 and the Notice to Contractors (NC) above, under "NOTICE OF PROTEST OF AWARD OF CONTRACT."

IB.5 BID PREPARATION EXPENSES

By accepting the Bid Proposal of the Bidder, the City assumes no obligation to reimburse the Bidder for Bid preparation expenses. No Bidder shall have any right or claim against the City for reimbursement of Bid preparation expenses.

IB.6 COLLUSION, DISCRIMINATION, AND/OR PRICE FIXING

The Bidder certifies that any and all prices which he/she may charge under the terms of the Contract do not, and will not, violate any existing federal, state or municipal laws or regulations concerning discrimination and/or price fixing. The Bidder agrees to indemnify, exonerate and hold Carson City harmless from liability for any such violation now and throughout the term of the Contract.

END OF INSTRUCTIONS TO BIDDERS

BID PROPOSAL

BID BOND

KNOW ALL MEN BY THESE PRESENTS, that I/We _____

as Principal, hereinafter called Contractor, and _____

a corporation duly organized under the laws of the State of Nevada, as Surety, hereinafter called the Surety, are held and firmly bound unto Carson City, Nevada a consolidated municipality of the State of Nevada, hereinafter called City, for the sum of \$ _____ Dollars

(state sum in words) _____

for the payment whereof Contractor and Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, the Principal has submitted a bid, identified as **BID # 1415-171** and titled "**Clear Creek Avenue Sanitary Sewer Extension**".

NOW, THEREFORE if the City shall accept the bid of the Principal and the Principal shall enter into a contract with the City in Accordance with the terms of such bid, and give such bond or bonds as may be specified in the bidding or Bid Documents with good and sufficient surety for the faithful performance of such Contract and for the prompt payment of labor and material furnished in the prosecution thereof, or in the event of the failure of the Principal to enter such Contract and give such bond or bonds, if the Principal shall pay to the City the difference not to exceed the penalty hereof between the amount specified in said bid and such larger amount for which the City may in good faith contract with another party to perform work covered by said bid or an appropriate liquidated amount as specified in the Invitation for Bids then this obligation shall be null and void, otherwise to remain in full force and effect.

Executed on this ____ day of _____ 2015

Signature of Principal: _____

Title: _____

Firm: _____

Address: _____

City/State/Zip Code: _____

Written Name of Principal: _____

ATTEST NAME

Signature of Notary: _____

(Seal)

Subscribed and sworn before me this _____ day of _____ 2015

(printed name of notary) _____ Notary Public for the State of _____

Claims Under this Bond May be Addressed to: Nevada Resident Agent Information
Complete for out of state bonding companies

Name of Surety

Name of Local Agent

Address

Address

City

City

State/Zip Code

State/Zip Code

Name

Agent's Name

Title

Agent's Title

Phone

Agents Phone

Surety's Acknowledgement

NOTICE: No substitution or revision to this bond form will be accepted. Sureties must be authorized to do business in and have an agent for services of process in the State of Nevada. Certified copy of Power of Attorney must be attached.

BID PROPOSAL

BID # 1415-171

BID TITLE: "Clear Creek Avenue Sanitary Sewer Extension"

NOTICE: No substitution or revision to this Bid Proposal form will be accepted. Carson City will reject any Bid that is received that has changes or alterations to this document. Although the Prevailing Wages are provided in this bid document, the bidder is responsible to verify with the Labor Commissioner if any addendums have been issued. The successful bidder will be required to provide the current Prevailing Wages used in preparation of their bid within 24 hours of bid submission.

PRICES will be valid for sixty (60) calendar days after the bid opening which is indicated in the Notice to Contractors.

A COPY OF CONTRACTOR'S "CERTIFICATE" of eligibility issued by the State of Nevada Contractors' Board as proof of Bidder's compliance with the provisions of N.R.S. 338.147 must be submitted with his/her bid for the preference to be considered. This Statute does not apply to projects expected to cost less than \$250,000.

COMPLETION of this project is expected **PURSUANT TO THE BID DOCUMENTS.**

BIDDER acknowledges receipt of _____ Addendums.

SUMMARY

	Description	Scheduled Value	Unit	Unit Price	Total Price
	Schedule A:				
BP. 1	Mobilization, Demobilization and Clean-Up	1	LS		
BP.2	Traffic Control	1	LS		
BP.3	Surveying	1	LS		
BP.4	3/4" PE Water Service Line	20	LF		
BP.5	3/4" Single Pit Setter and Water Meter	2	EA		
BP.6	8" C900 Water Line	700	LF		
BP.7	8" Gate Valve	2	EA		
BP.8	Fire Hydrant Assembly	1	EA		
BP.9	3/4" Air Release Valve Assembly	1	EA		
BP.10	Adjust Existing Valve Can to Grade	8	EA		
BP.11	Reconstruct Existing 48" Diameter Sanitary Sewer Manhole	1	EA		
BP.12	Modify Existing Sanitary Sewer Manhole With Drop Inlet	1	EA		
BP.13	48" Diameter Sanitary Sewer Manhole	10	EA		
BP.14	Adjust Existing Manhole Frame and Cover to Grade	2	EA		
BP.15	4" SDR35 PVC Sanitary Sewer Pipe	370	LF		
BP.16	8" SDR35 PVC Sanitary Sewer Pipe	70	LF		
BP.17	10" SDR35 PVC Sanitary Sewer Pipe	2,000	LF		
BP.18	Type 4R Storm Sewer Inlet	6	EA		
BP.19	48" Dia. Storm Sewer Manhole	3	EA		
BP.20	48" Storm Sewer Drop Inlet	2	EA		
BP.21	15" Class IV RCP Storm Sewer Pipe	65	LF		
BP.22	15" HDPE Storm Sewer Pipe	45	LF		
BP.23	18" HDPE Storm Sewer Pipe	1,110	LF		
BP.24	18" HDPE Storm Sewer Pipe (Perforated)	280	LF		
BP.25	24" HDPE Storm Sewer Pipe	45	LF		
BP.26	24" HDPE Storm Sewer Pipe (Perforated)	160	LF		
BP.27	Pulverize Bituminous Surface, Blend, and	66,817	SF		

BID PROPOSAL

	Remove Excess for an 8" Min. Base Section				
BP.28	Over Excavation of Unsuitable Materials	1,000	CY		
BP.29	4" Plantmix Pavement Type 3 Agg., NV 64-28	75,600	SF		
BP.30	AC Driveway Apron on 6" Ag. Base	1,000	SF		
BP.31	Remove Existing PCC Sidewalk	140	SF		
BP.32	Type A PCC Sidewalk (4" concrete on 4" aggregate base)	12,300	SF		
BP.33	Remove Existing PCC Curb and Gutter	40	LF		
BP.34	Type 1 PCC Curb and Gutter on 6" of Aggregate Base	3,340	LF		
BP.35	Remove Existing PCC Driveway/Apron	2,000	SF		
BP.36	PCC Driveway Apron Type 1 (6" Conc. On 6" Base)	400	SF		
BP.37	Commercial PCC Driveway Apron (6" Conc. On 6" Base)	610	SF		
BP.38	Residential PCC Driveway (6" Conc. On 6" Base)	1,200	SF		
BP.39	PCC Valley Gutter (6" Conc. On 6" Base)	400	SF		
BP.40	PCC Pedestrian Ramp with Detectable Warning Plate (4" Conc. On 4" Base)	680	SF		
BP.41	24" Solid White Stop Bar	58	LF		
BP.42	4" Solid White Pavement Paint	4,000	LF		
BP.43	4" Double Solid Yellow Pavement Paint	1,131	LF		
BP.44	6" White Dotted Line Pavement Paint (2' Stripe, 6' Space)	120	LF		
BP.45	4" White Centerline Skip Stripe Pavement Paint (7' Stripe 21' Space)	1,285	LF		
BP.46	Solid White Bicycle With Arrow Legend Pavement Paint	5	EA		
BP.47	Install New Sign and Post	4	EA		
BP.48	Reinstall Existing Traffic Sign and Post	4	EA		
BP.49	Total Base Bid Price (Schedule A)				

BP.50 Total Base (Schedule (A) Bid Price Written in Words:

BID PROPOSAL

BP.51 BIDDER INFORMATION:

Company Name:

Federal ID No.:
Mailing Address:
City, State, Zip Code:
Complete Telephone Number:
Complete Fax Number:
Fax Number including area code:
E-mail:

Contact Person / Title:

Mailing Address:
City, State, Zip Code:
Complete Telephone Number:
Complete Fax Number:
E-mail Address:

BP.52 LICENSING INFORMATION:

Nevada State Contractor's License Number:
License Classification(s):
Limitation(s) of License:
Date Issued:
Date of Expiration:
Name of Licensee:
Carson City Business License Number:
Date Issued:
Date of Expiration:
Name of Licensee:

BID PROPOSAL

BP.53 DISCLOSURE OF PRINCIPALS:

Individual and/or Partnership:

Owner 1) Name:
Address:
City, State, Zip Code:
Telephone Number:
Owner 2) Name:
Address:
City, State, Zip Code:
Telephone Number:
Other 1) Title:
Name
Other 2) Title:
Name:

Corporation:

State in which Company is Incorporated:
Date Incorporated:
Name of Corporation:
Mailing Address
City, State, Zip Code:
Telephone Number:
President's Name:
Vice-President's Name:
Other 1) Name & Title:

BID PROPOSAL

BP.54 MANAGEMENT AND SUPERVISORY PERSONNEL:

Persons and Positions	Years With Firm
Name 1)	

Title 1)

Name 2)	
---------	--

Title 2)

Name 3)	
---------	--

Title 3)

Name 4)	
---------	--

Title 4)

Name 5)	
---------	--

Title 5)

Name 6)	
---------	--

Title 6)

(If additional space is needed, attach a separate page)

BID PROPOSAL

BP.55 REFERENCES:

Instructions:

List at least three (3) contracts of a similar nature performed by your firm in the last three (3) years. If **NONE**, use your Company's letterhead (and submit with your bid proposal) to list what your qualifications are for this contract. Carson City reserves the right to contact and verify, with any and all references listed, the quality of and the degree of satisfaction for such performance.

Clients: (if additional space is needed attach a separate page)

Company Name 1):
Contract Person:
Mailing Address:
City, State, Zip Code:
Complete Telephone Number:
E-Mail Address:
Project Title:
Amount of Contract:
Scope of Work:
Company Name 2):
Contract Person:
Mailing Address:
City, State, Zip Code:
Complete Telephone Number:
E-Mail Address:
Project Title:
Amount of Contract:
Scope of Work:

BID PROPOSAL

Company Name 3):
Contract Person:
Mailing Address:
City, State, Zip Code:
Complete Telephone Number:
E-Mail Address:
Project Title:
Amount of Contract
Scope of Work:
Company Name 4):
Contract Person:
Mailing Address:
City, State, Zip Code:
Complete Telephone Number:
E-Mail Address:
Project Title:
Amount of Contract:
Scope of Work:

BID PROPOSAL

BP. 56 CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER RESPONSIBILITY MATTERS PRIMARY COVERED TRANSACTIONS

1. The prospective primary participant certifies to the best of its knowledge and belief, that it and its principals:
 - a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded by any Federal, State or Local department or agency.
 - b) Have not within a three-year period preceding this bid been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or Local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property.
 - c) Are not presently indicted for or otherwise criminally or civilly charged by a government entity (Federal, State or Local) with commission of any of the offenses enumerated in paragraph (1)(b) of this certification; and
 - d) Have not within a three-year period preceding this bid had one or more public transactions (Federal, State or Local) terminated for cause or default.
2. Where the prospective primary participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this bid.

Signature of Authorized Certifying Official

Title

Printed Name

Date

I am unable to certify to the above statement. My explanation is attached.

Signature

Date

BIDDER'S SAFETY INFORMATION

Bidder's Safety Factors:

Year	"E-Mod" Factor ¹	OSHA Incident Rate ²
2014		
2013		

¹ E-Mod (Experience Modification) Factors are issued by the Employer's Insurance Company of Nevada.

² OSHA Incident Rate is the number of OSHA Recordable Accidents per 100 employees and is calculated as the number of accidents divided by 208,000.

BID PROPOSAL

SUBCONTRACTORS

BP.57 INSTRUCTIONS: for Subcontractors and **General Contractors who self-perform** in amounts **exceeding five (5) percent of bid amount.** This information must be submitted with your bid proposal. The bidder shall enter **NONE** under **Name of Subcontractor** if not utilizing subcontractors exceeding this amount and **per NRS 338.141 the prime contractor shall list itself on the subcontractor's list if it will be providing any of the work on the project.** (This form must be complete in all respects. If, additional space is needed, attach a separate page).

Name of Subcontractor	Address	
Phone	Nevada Contractor License #	Limit of License
Description of work		
Name of Subcontractor	Address	
Phone	Nevada Contractor License #	Limit of License
Description of work		
Name of Subcontractor	Address	
Phone	Nevada Contractor License #	Limit of License
Description of work		
Name of Subcontractor	Address	
Phone	Nevada Contractor License #	Limit of License
Description of work		
Name of Subcontractor	Address	
Phone	Nevada Contractor License #	Limit of License
Description of work		

BID PROPOSAL

SUBCONTRACTORS

BP.58 INSTRUCTIONS: for Subcontractors **exceeding one (1) percent of bid amount or \$50,000 whichever is greater.** This information must be submitted by the three lowest bidders within two (2) hours after the completion of the opening of the bids. The bidder may elect to submit this information with the bid proposal and, in that case, the bidder will be considered as having submitted this information within the above two hours.

Name of Subcontractor	Address	
Phone	Nevada Contractor License #	Limit of License
Description of work		
Name of Subcontractor	Address	
Phone	Nevada Contractor License #	Limit of License
Description of work		
Name of Subcontractor	Address	
Phone	Nevada Contractor License #	Limit of License
Description of work		
Name of Subcontractor	Address	
Phone	Nevada Contractor License #	Limit of License
Description of work		
Name of Subcontractor	Address	
Phone	Nevada Contractor License #	Limit of License
Description of work		

BID PROPOSAL

SUBCONTRACTORS

BP. 59 INSTRUCTIONS: for all Subcontractors not previously listed on the 5% and 1% pages. This information must be submitted by the three lowest bidders within twenty four (24) hours after the completion of the opening of the bids. The bidder may elect to submit this information with the bid proposal and, in that case, the bidder will be considered as having submitted this information within the above twenty four hours.

Name of Subcontractor	Address	
Phone	Nevada Contractor License #	Limit of License
Description of work		
Name of Subcontractor	Address	
Phone	Nevada Contractor License #	Limit of License
Description of work		
Name of Subcontractor	Address	
Phone	Nevada Contractor License #	Limit of License
Description of work		
Name of Subcontractor	Address	
Phone	Nevada Contractor License #	Limit of License
Description of work		
Name of Subcontractor	Address	
Phone	Nevada Contractor License #	Limit of License
Description of work		

BID PROPOSAL

BP. 60

WORKERS EMPLOYED REPORT INSTRUCTIONS FOR COMPLETION

Effective July 1, 2013, contractors who receive a preference in bidding on a public work must submit an affidavit to the public body certifying that 50 percent of all workers employed on the public work, including any employees of the contractor and of any subcontractor, will hold a valid driver's license or identification card issued by the Nevada Department of Motor Vehicles. Pursuant to NRS 338.070(4), a contractor and each subcontractor engaged on a public work shall keep an accurate record showing, for each worker employed by the contractor or subcontractor in connection with the public work who has a driver's license or identification card, the name of the worker, the driver's license number or identification card number of the worker, and the state or other jurisdiction that issued the license or card. A copy of this record must be received by the public body no later than 15 days after the end of the month. Additionally, the contractor and any subcontractor will maintain and make available for inspection within Nevada his or her records concerning payroll relating to the public work.

- EACH contractor and subcontractor must complete the Workers Employed Report.
- You may make additional copies of the report as necessary.
- A copy of this report must be submitted with the monthly certified payroll report.
- Submit Identification log monthly listing all employees that worked for that month. The Identification log should correspond with the certified payroll reports. If employees are not working in a given month then they should not be listed on said report.

This report is intended to serve as a cumulative list of all workers employed by the contractor and subcontractor over the duration of the project to verify compliance with the minimum requirements of the affidavit.

BID PROPOSAL



WORKERS EMPLOYED REPORT

Project Name: _____ Contract Number : _____
General Contractor:_____ PWP # _____
Subcontractor: _____ Date: _____
Address at which payroll records are maintained:

Contact Person and Phone Number: _____

Employee Name	Driver License Number or ID Card Number	Issuing State or Jurisdiction

BID PROPOSAL

BID PROPOSAL

BP.61 ACKNOWLEDGMENT AND EXECUTION:

STATE OF _____)
) SS
COUNTY OF _____)

I _____ (Name of party signing this Bid Proposal), do depose and say: That I am the Bidder or authorized agent of the Bidder; and that I have read and agree to abide by this Bid which includes, but is not limited to the following documents: Notice to Contractors, Table of Contents, Project Coordination, Instructions to Bidders, Bid Bond, Proposal Summary, Contract Award Instructions and Information, Sample Contract, Sample Performance Bond, Sample Labor and Material Payment Bond, General Conditions, Special Conditions, Standard Specifications, Prevailing Wage Rates, Technical Specifications, Geotechnical Report (if any), Contract Drawings, Permits (if any), and any addenda issued and understands the terms, conditions, and requirements thereof; that if his/her bid is accepted that he/she agrees to furnish and deliver all materials except those specified to be furnished by the City (Owner) and to do and perform all work for the “**Clear Creek Avenue Sanitary Sewer Extension**”, contract number **1415-171**, together with incidental items necessary to complete the work to be constructed in accordance with the Contract Documents, Contract Drawings, and Specifications annexed hereto.

BIDDER:

PRINTED NAME OF BIDDER: _____

TITLE: _____

FIRM: _____

Address: _____

City, State, Zip: _____

Telephone: _____

Fax: _____

E-mail Address: _____

(Signature of Bidder)

DATED: _____

Signed and sworn (or affirmed) before me on this _____ day of _____, 2015, by _____.

(Signature of Notary)

(Notary Stamp)

END OF BID PROPOSAL

CONTRACT AWARD

CA.1 NOTICE TO CONTRACTORS:

The **CONTRACTOR** shall complete a Wage Comparison Worksheet (see SRF Requirement Section for form) and submit it along with the Agreement, Bonds and Insurance after the Notice of Award is issued.

CA.2 METHOD OF AWARD

The Bid, if awarded, will be awarded to the lowest responsive and responsible Bidder based on the Total Base Bid amount, plus or minus any or all Additive or Deductive Alternates, in any combination that is most advantageous to the City. Bidder must bid all items to be responsive and considered for award.

CA.3 TIME OF AWARD

The award, if made, will be within sixty (60) calendar days after the opening of Bids. The City reserves the right to accept or reject any or all Bids received.

CA.4 BONDS

A. Bonds Required

The Contractor agrees that any bonding or guarantee required by this bid shall not be considered as the exclusive remedy of the City for any default in any respect by the Contractor, but such bonding or guarantee shall be considered to be in addition to any right or remedy hereunder or allowed by law, equity, or statute.

A Performance Bond and a Payment Bond, pursuant to the requirements of NRS 339.025, if not otherwise excluded under the threshold stated in NRS 339.025, in the amount of one hundred percent (100%) of the Contract Amount shall be required of the Contractor prior to execution of the Contract and not later than ten (10) calendar days after receipt of the Notice of Award. Said bonds shall remain in full force and effect for a period of not less than one (1) year from the date of Final Acceptance of this Project by the City (Carson City Board of Supervisors or Carson City Regional Transportation Commission). Each of the bonds required must be executed by one or more surety companies authorized to do business in the State of Nevada. Note that individual surety bonds are not acceptable to the City.

B. Bond Forms

The referenced bonds shall be written on the Performance Bond, and Labor and Material Payment Bond forms provided by the City, as shown in the following Construction Contract forms.

The Bidder shall require any resident agent who executes the required bonds on behalf of the surety to affix thereto a certified and current copy of his/her power of attorney.

Any Labor and Material Payment Bond or Performance Bond prepared by a licensed non-resident agent must be countersigned by a resident agent in accordance with the provisions of NRS 680A.300.

The referenced Bonds must be issued by a certified surety listed in the Department of the Treasury, Fiscal Service (Department Circular 570, Current Revision); companies holding certificates of authority as acceptable sureties on federal bonds and as acceptable reinsuring companies.

CA.5 INSURANCE REQUIREMENTS

A. General

Contractor, as an independent contractor and not an employee of the City, must carry policies of insurance in amounts specified and pay all taxes and fees incidental hereto. City shall have no liability except as specified in this Contract.

Contractor shall not commence work before: (1) Contractor has provided the required evidence of insurance to Carson City Purchasing and Contracts, (2) City has approved the insurance policies provided by Contractor, and (3) City has issued the Notice to Proceed.

CONTRACT AWARD

Contractor shall not allow any subcontractors to commence work on its subcontract until all similar insurance required of the subcontractor has been obtained and verified by Contractor.

Prior approval of the insurance policies by City shall be a condition precedent to any payment of consideration under this Contract and City's approval of any changes to insurance coverage during the course of performance shall constitute an ongoing condition subsequent to this Contract. Any failure of City to timely approve shall not constitute a waiver of the condition.

The insurance requirements specified herein do not relieve Contractor of his/her responsibility or limit the amount of his/her liability to the City or other person, and Contractor is encouraged to purchase such additional insurance as he/she deems necessary.

Contractor is responsible for and must remedy all damage or loss to any property, including property of City, caused in whole or in part by Contractor, any subcontractor or anyone employed, directed or supervised by Contractor. Contractor is responsible for initiating, maintaining and supervising all safety precautions and programs in connection with the Work.

City reserves the right to occupy existing facilities under construction or to use or occupy parts of the Work. Insurance policies shall not restrict or limit such use.

Certificate Holder: Each liability insurance policy shall list Carson City c/o Carson City Purchasing and Contracts, 201 North Carson Street, Suite 3, Carson City, Nevada 89701 as a certificate holder.

A. Insurance Coverage

Contractor shall, at Contractor's sole expense, procure, maintain and keep in force for the duration of this Contract the following insurance conforming to the minimum requirements specified below. Unless specifically specified herein or otherwise agreed to by the City, the required insurance shall be in effect prior to the commencement of work by the Contractor and shall continue in force as appropriate until the latter of:

1. Final acceptance by the City of the completion of this Contract; or
2. Such time as the insurance is no longer required by the City under the terms of this Contract
3. Any insurance or self-insured available to the City shall be in excess of and non-contributing with any insurance required from the Contractor. Contractor's insurance policies shall apply on a primary basis. Until such time as the insurance is no longer required by the City, Contractor shall provide the City with renewal or replacement evidence of insurance no less than thirty (30) calendar days before the expiration or replacement of the required insurance. If at any time during the period when insurance is required by this Contract, an insurer or surety fail to comply with the requirements of this Contract, as soon as **CONTRACTOR** has knowledge of any such failure, Contractor shall immediately notify the City and immediately replace such insurance or bond with an insurer meeting the requirements.

B. General Requirements

Certificate Holder: Each liability insurance policy shall list Carson City c/o Carson City Purchasing and Contracts, 201 North Carson Street, Suite 3, Carson City, Nevada 89701, as a certificate holder.

Additionally Insured: By Endorsement to the general liability insurance policy evidence by Contractor, the City and County of Carson City, Nevada, its officers, employees and immune Contractors shall be named as additionally insured's for all liability arising from this contract.

Waiver of Subrogation: Each liability insurance policy shall provide for a waiver of subrogation as to additionally insured's.

CONTRACT AWARD

Cross Liability: All required liability policies shall provide cross-liability coverage as would be achieved under the standard ISO separation of insured's clause.

Deductibles and Self-Insured Retentions: Insurance maintained by the Contractor shall apply on a first dollar basis without application of a deductible or self-insured retention unless otherwise specifically agreed to by the City. Such approval shall not relieve Contractor from the obligation to pay any deductible or self-insured retention. Any deductible or self-insured retention shall not exceed \$5,000.00 per occurrence, unless otherwise approved by the City.

Policy Cancellation: Except for ten (10) calendar days notice for non-payment of premium, each insurance policy shall be endorsed to state that: without thirty (30) calendar days prior written notice to Carson City Purchasing and Contracts, the policy shall not be cancelled, non-renewed or coverage and/or limits reduced or materially altered, and shall provide that notices required by this paragraph shall be sent by certified mail to Carson City Purchasing and Contracts, 201 North Carson Street, Suite 3, Carson City, Nevada 89701.

Approved Insurer: Each insurance policy shall be issued by insurance companies authorized to do business in the State of Nevada or eligible surplus line insurers acceptable to the State and having agents in Nevada upon whom service of process may be made, and currently rated by A.M. Best as "A-VII" or better.

Evidence of Insurance: Prior to commencement of work, the Contractor must provide the following documents to Carson City Purchasing and Contracts, 201 North Carson Street, Suite 3, Carson City, Nevada 89701.

Certificate of Insurance: The Acord 25 Certificate of Insurance form or a form substantially similar must be submitted to Carson City Purchasing and Contracts to evidence the insurance policies and coverages required of Contractor.

Additional Insured Endorsement: An additional Insured Endorsement (CG20 10 or CG 20 26), signed by an authorized insurance company representative, must be submitted to Carson City Purchasing and Contracts to evidence the endorsement of **CITY** as an additional insured.

Schedule of Underlying Insurance Policies: If Umbrellas or Excess policy is evidenced to comply with the minimum limits, a copy of the Underlyer Schedule from the Umbrella or Excess insurance policy may be required.

Review and Approval: Documents specified above must be submitted for review and approval by Carson City Purchasing and Contracts prior to the commencement of work by Contractor. Neither approval by the City nor failure to disapprove the insurance furnished by the Contractor shall relieve Contractor or Contractor's full responsibility to provide the insurance required by this Contract. Compliance with the insurance requirements of this Contract shall not limit the liability of Contractor or its subcontractors, employees or agents to City or others, and shall be in addition to and not in lieu of any other remedy available to the City under this Contract or otherwise. Carson City reserves the right to request and review a copy of any required insurance policy or endorsement to assure compliance with these requirements.

C. Commercial General Liability Insurance

Minimum Limits required:

Two Million Dollars (\$2,000,000.00) – General Aggregate

Two Million Dollars (\$2,000,000.00) – Products and Completed Operations Aggregate

One Million Dollars (\$1,000,000.00) – Each Occurrence

Coverage shall be on an occurrence basis and shall be at least as broad as ISO 1996 form CG 00 01 (or a substitute form providing equivalent coverage); and shall cover liability arising from premises,

CONTRACT AWARD

operations, independent Contractors, completed operations, person injury, products, civil lawsuits, Title VII actions and liability assumed under an insured contract (including the tort liability or another assumed in a business contact).

D. Business Automobile Liability

Minimum Limit required:

On Million Dollars (\$1,000,000.00) per occurrence for bodily injury and property damage

Coverage shall be for "any auto" including owned, non-owned and hired vehicles. The policy shall be written on ISO form CA 00 01 or a substitute providing equivalent liability coverage. If necessary, the policy shall be endorsed to provide contractual liability coverage.

F. Worker's Compensation and Employer's Liability Insurance

CONTRACTOR shall provide workers' compensation insurance as required by Nevada Revised Statutes Chapters 616A through 616D inclusive and Employer's Liability insurance with a minimum limit of \$500,000.00 each employee per accident for bodily injury by accident or disease.

CA.6 PENALTY FOR COLLUSION

If at any time, it is found that the Contractor has, in presenting any bid or bids, colluded with any other party or parties, then the Contract shall be null and void, and the Contractor and its sureties shall be liable for loss or damage which the City may suffer thereby, and the City may advertise for new bids for said Work. The Contractor further certifies that any and all prices which he/she may charge under the terms of the Contract do not, and will not; violate any existing Federal, State or Municipal laws or regulations concerning discrimination and/or price fixing.

CA.7 SUCCESSORS AND ASSIGNS

The performance of the Contract may not be assigned. Consent will not be given to any proposed assignment which would relieve the surety of the original Contractor of their responsibilities under the Contract, nor will the City consent to any assignment of a part of the Work under the Contract.

CA.8 RIGHTS AND REMEDIES

The duties and obligations imposed by the Contract Documents and the rights and remedies available thereunder shall be in addition to, and not a limitation of, any duties, obligations, rights, and remedies otherwise imposed or available by law.

No action or failure to act by the City, the Design Consultant, or the Construction Manager shall constitute a waiver of any right or duty afforded any of them under the Contract, nor shall any such action or failure to act constitute an approval of or acquiescence in any breach thereunder, except as may be specifically agreed in writing.

CA.9 COPELAND ANTI-KICKBACK LAW

The Contractor shall comply with the Copeland Anti-Kickback Act (19 U.S.C. 874) as supplemented in the Department of Labor Regulations (29 CFR Part 3). This act provides that each Contractor or subcontractor shall be prohibited from inducing by any means, any person employed in the construction, completion or repair of public work, to give up any part of the compensation to which he/she is otherwise entitled.

CA.10 NOTICE TO PROCEED

Within ten (10) calendar days of receipt of all required post-bid information, including bonds, insurances, and executed Contract, the City will issue the Notice to Proceed.

CA.11 TIME: COMPLETION OF PROJECT

A. Time

The successful Bidder, upon becoming the Contractor after having entered into a Contract with the City, shall commence the Work to be performed under the Contract on the date set by the City in the written

CONTRACT AWARD

Notice to Proceed, continuing the Work in accordance with the approved schedule and shall complete the entire Work within the number of calendar days stated in the Special Conditions after the date of the Notice to Proceed. Further, separable portions of the Work may be subject to milestone or specific dates as established in the Special Conditions.

The time specified above represents no overtime requirement. Any scheduling of overtime for this Project is solely that of the Contractor, unless specifically directed in writing by the City. The City will not be responsible for any costs related to overtime work performed unless it is specifically directed in writing by the City.

B. Liquidated Damages

In case of failure on the part of the Contractor to complete the Work within the time(s) specified in the Contract, or within such additional time(s) as may be granted by formal action of the City, or the Contractor fails to prosecute the Work, or any separable part thereof, with such diligence as will insure its completion within the time(s) specified in the Contract or any extensions thereof, the Contractor shall pay to the City, as liquidated damages, the sum specified in the Special Conditions for each calendar day for delay until such reasonable time as may be required for final completion of the Work, together with any increased costs incurred by the City in completing the Work.

Time stated for completion shall include the final cleanup and demobilization.

The signing of the Bid Proposal by the Bidder shall be prima facie evidence that the Contractor agrees that the amount of liquidated damages is fair and reasonable.

CA. 12 LIQUIDATED DAMAGES FOR LATE SUBMITTALS AND LAPSE OF INSURANCE

The Contractor shall provide all submittals required by this Contract within fifteen (15) calendar days of the Notice to Proceed. If the Contractor does not provide the submittals on or before the fifteenth (15th) calendar day, he/she will pay to the City the amount of Two Hundred Fifty Dollars (\$250) per day as liquidated damages. If the Contractor does not keep the bonds or insurance policies in effect or allows them to lapse, the Contractor will pay to the City the amount of Two Hundred Fifty Dollars (\$250) per day as liquidated damages, and will be in breach of Contract.

END OF CONTRACT AWARD

SAMPLE CONTRACT

THIS CONTRACT made and entered into this ____ day of _____, 20__, by and between Carson City, a consolidated municipality, a political subdivision of the State of Nevada, hereinafter referred to as "CITY", and _____, hereinafter referred to as "**CONTRACTOR**".

WITNESSETH:

WHEREAS, the Purchasing and Contracts Manager for **CITY** is authorized pursuant to Nevada Revised Statutes 338 and Carson City Purchasing Resolution #1990-R71, to approve and accept this Contract as set forth in and by the following provisions; and

WHEREAS, this Contract involves a "public work," which pursuant to NRS 338.010(17) means any project for the new construction, repair or reconstruction of an applicable project financed in whole or in part from public money; and

WHEREAS, CONTRACTOR'S compensation under this agreement (does ___) (does not ___) utilize in whole or in part money derived from one or more federal grant funding source(s); and

WHEREAS, it is deemed necessary that the services of **CONTRACTOR** for **CONTRACT No.** _____, titled _____ (hereinafter referred to as "Contract") are both necessary and in the best interest of **CITY**; and

NOW, THEREFORE, in consideration of the aforesaid premises, and the following terms, conditions and other valuable consideration, the parties mutually agree as follows:

1. **REQUIRED APPROVAL:**

This Contract shall not become effective until and unless approved by the Carson City Board of Supervisors.

2. **SCOPE OF WORK (Incorporated Contract Documents):**

2.1 The parties agree that the Scope of Work will be specifically described and hereinafter referred to as the "WORK." This Contract incorporates the following attachments, and a **CONTRACTOR'S** attachment shall not contradict or supersede any **CITY** specifications and/or terms or conditions without written evidence of mutual assent to such change appearing in this Contract:

2.1.1 **CONTRACTOR** agrees that the Contract Documents for Bid No. _____ including, but not limited to, the Notice to Contractors, Table of Contents, Project Coordination, Instructions to Bidders, Contract Award Information, General Conditions, Special Conditions, Technical Specification, Prevailing Wages, Contract Drawings, and Addenda, if any, hereinafter all referred to as Exhibit A, are intended to be complete and complementary and are intended to describe a complete WORK. These documents are incorporated herein by reference and made a part of this Contract.

2.1.2 **CONTRACTOR** additionally agrees **CONTRACTOR'S** Bid Bond, Bid Proposal, Proposal Summary, Executed Contract, Performance Bond, Labor and Material Bond, Certificate of Eligibility, Insurance Certificates, Permits, Notice of Award, Notice to Proceed and Executed Change Orders, hereinafter all referred to as Exhibit B, are incorporated herein and made a part of this Contract..

For P&C Use Only
CCBL expires _____
NVCL expires _____
GL expires _____
AL expires _____
WC expires _____

SAMPLE CONTRACT

2.2 The attached incorporated General Conditions (“GC”) document provides in Section GC 1.3 a “Governing Order of Bidding and Contract Documents,” which shall be applicable to this Contract.

1. CONTRACT TERM AND LIQUIDATED DAMAGES:

3.1 **CONTRACTOR** agrees to complete the WORK on or before the date specified in the Notice to Proceed or any executed Change Orders to the entire satisfaction of **CITY** before final payment is made, unless sooner termination by either party as specified in **Section 6** (CONTRACT TERMINATION) and the General Conditions, Section GC 3.18.

3.2 Pursuant to the provisions under Time for Completion and Liquidated Damages in the Contract Documents of said Specifications, **CONTRACTOR** will complete the WORK within the Contract time. Since **CITY** and **CONTRACTOR** agree it is difficult to ascertain the actual amount of damages incurred due to delay of the Project, it is agreed that **CITY** will be paid the liquidated damages as specified in the Contract Special Conditions for each and every calendar day of delay in the completion of the WORK, in addition to any direct charges incurred by **CITY** as a result of delay of the Project, including engineering fees and additional damages due to late construction. **CITY** also reserves the right to deduct any amounts due **CITY** from any monies earned by **CONTRACTOR** under this Contract.

3.3 That in the performance of this Contract, **CONTRACTOR** and any subcontractors, as employers, shall pay 1 ½ times an employee’s regular wage rate whenever an employee who received compensation for employment at a rate less than 1 ½ time the minimum wage who works more than forty (40) hours in any scheduled work week, more than eight (8) hours in a day, unless by mutual agreement the employee works a scheduled ten (10) hours per day for four (4) calendar days within a work week. Employers should refer to NRS 608.018, NRS 338.020 and A.O. 2013-04 for further details on overtime requirements.

2. NOTICE:

4.1 Except the bid and award process where notices may be limited to postings by **CITY** on its Finance Department/Bid Opportunities website (www.carson.org), all notices or other communications required or permitted to be given under this Contract shall be in writing and shall be deemed to have been duly given if delivered personally in hand, by e-mail, by regular mail, by telephonic facsimile with simultaneous regular mail, or by certified mail, return receipt requested, postage prepaid on the date posted, and addressed to the other party at the address specified below.

4.2 Notice to **CONTRACTOR** shall be addressed to:

email: _____

4.3 Notice to **CITY** shall be addressed to:

Carson City Purchasing and Contracts
Kim Belt, Purchasing and Contracts Manager
201 North Carson Street, Suite 3
Carson City, NV 89701
775-283-7137 / FAX 775-887-2107
KBelt@carson.org

1. COMPENSATION:

5.1 The parties agree that **CONTRACTOR** will provide the WORK specified in the Contract for the Contract Amount of _____ Dollars and ___/100 (\$_____).

5.2 **CITY** will pay **CONTRACTOR** progress payments and the final payment computed from the actual quantities of WORK performed and accepted and the materials furnished at the Unit and Lump Sum prices shown on **CONTRACTOR’S** Bid Proposal and any executed Change Orders.

SAMPLE CONTRACT

5.3 Contract Amount represents full and adequate compensation for the complete WORK, and includes the furnishing of all materials, all labor, equipment, tools, transportation, services, appliances, and all expenses, direct or indirect connected with the proper execution of the WORK.

5.4 CITY does not agree to reimburse CONTRACTOR for expenses unless otherwise specified.

1. CONTRACT TERMINATION:

6.1 Termination Without Cause:

6.1.1 Any discretionary or vested right of renewal notwithstanding, this Contract may be terminated upon written notice by mutual consent of both parties or unilaterally by either party without cause.

6.1.2 CITY reserves the right to terminate this Contract for convenience whenever it considers termination, in its sole and unfettered discretion, to be in the public interest. In the event that the Contract is terminated in this manner, payment will be made for WORK actually completed. If termination occurs under this provision, in no event shall CONTRACTOR be entitled to anticipated profits on items of WORK not performed as of the effective date of the termination or compensation for any other item, including but not limited to, unabsorbed overhead. CONTRACTOR shall require that all subcontracts which he/she enters related to this Contract likewise contain a termination for convenience clause which precludes the ability of any subcontractor to make claims against CONTRACTOR for damages, due to breach of contract, of lost profit on items of WORK not performed or of unabsorbed overhead, in the event of a convenience termination.

6.2 Termination for Nonappropriation:

6.2.1 All payments and WORK provided under this Contract are contingent upon the availability of the necessary public funding, which may include various internal and external sources. In the event that Carson City does not acquire and appropriate the funding necessary to perform in accordance with the terms of the Contract, the Contract shall automatically terminate upon CITY'S notice to CONTRACTOR of such nonappropriation, and no claim or cause of action may be based upon any such nonappropriation.

6.3 Cause Termination for Default or Breach:

6.3.1 A default or breach may be declared with or without termination.

6.3.2 This Contract may be terminated by either party upon written notice of default or breach to the other party as follows:

6.3.2.1 If CONTRACTOR fails to provide or satisfactorily perform any of the conditions, WORK, deliverables, goods, or any services called for by this Contract within the time requirements specified in this Contract or within any granted extension of those time requirements; or

6.3.2.2 If any state, county, city or federal license, authorization, waiver, permit, qualification or certification required by statute, ordinance, law, or regulation to be held by CONTRACTOR to provide the goods or WORK or any services required by this Contract is for any reason denied, revoked, debarred, excluded, terminated, suspended, lapsed, or not renewed; or

6.3.2.3 If CONTRACTOR becomes insolvent, subject to receivership, or becomes voluntarily or involuntarily subject to the jurisdiction of the bankruptcy court; or

6.3.2.4 If CITY materially breaches any material duty under this Contract and any such breach impairs CONTRACTOR'S ability to perform; or

6.3.2.5 If it is found by CITY that any quid pro quo or gratuities in the form of money, services, entertainment, gifts, or otherwise were offered or given by CONTRACTOR, or any agent or representative of CONTRACTOR, to any officer or employee of CITY with a view toward securing a contract or securing favorable treatment with respect to awarding, extending, amending, or making any determination with respect to the performing of such contract; or

SAMPLE CONTRACT

6.3.2.6 If it is found by **CITY** that **CONTRACTOR** has failed to disclose any material conflict of interest relative to the performance of this Contract.

6.3.2.7 **CITY** may terminate this Contract if **CONTRACTOR**:

6.3.2.7.1 Fails to maintain bonding, Nevada State Contractors' Board License, State Industrial Insurance requirements or insurance policies for limits as defined in this Contract; or

6.3.2.7.2 Persistently or materially refuses or fails to supply properly skilled workers or proper materials; or

6.3.2.7.3 Fails to make payment to subcontractors for materials or labor in accordance with the respective agreements between **CONTRACTOR** and the subcontractors; or

6.3.2.7.4 Disregards laws, ordinances, or rules, regulations or order of a public authority having jurisdiction; or

6.3.2.7.5 Otherwise makes a material breach of a provision of this Contract; or

6.3.2.7.6 **CONTRACTOR** fails to maintain safe working conditions.

6.3.3 When any of the **Subsection 6.3.2.7.1 through 6.3.2.7.6, inclusive**, cause reasons exist, and without prejudice to any other rights or remedies of **CITY**, **CITY** may terminate this Contract at any time after giving **CONTRACTOR** and **CONTRACTOR'S** Surety seven (7) calendar days written notice of default or breach and intent to terminate and **CONTRACTOR'S** subsequent failure to timely correct as provided below, and subject to any prior rights of the Surety, **CITY** may:

6.3.3.1 Take possession of the site and of all materials, equipment, tools and construction equipment and machinery thereon owned by **CONTRACTOR**;

6.3.3.2 Accept assignment of subcontractors pursuant to this Contract (Contingent Assignment of Subcontracts to Carson City if this Contract is terminated); and

6.3.3.3 Finish the WORK by whatever reasonable method **CITY** may deem expedient.

6.3.4 If **CITY** terminates this Contract for any of the cause reasons stated in **Section 6.3**:

6.3.4.1 **CONTRACTOR** shall not be entitled to receive further payment until the WORK is finished.

6.3.4.2 If the unpaid balance of the Contract Amount exceeds the cost of finishing the WORK including expenses made necessary thereby, such excess shall be paid to **CONTRACTOR**. If the costs of finishing the WORK exceed the unpaid balance, **CONTRACTOR** shall pay the difference to **CITY**. The amount to be paid to **CONTRACTOR** or **CITY**, as the case may be, shall survive termination of this Contract.

6.3.4.3 In the event of such cause termination, all monies due **CONTRACTOR** or retained under the terms of this Contract shall be held by **CITY**, however, such holdings will not release **CONTRACTOR** or its Sureties from liability for failure to fulfill this Contract. Any excess cost over and above the Contract Amount incurred by **CITY** arising from the termination of the operations of this Contract and the completion of the WORK by **CITY** as provided above shall be paid for by any available funds held by **CITY**. **CONTRACTOR** will be so credited with any surplus remaining after all just claims for such completion have been paid.

6.4 If at any time before completion of the WORK under this Contract, the WORK shall be stopped by an injunction of a court of competent jurisdiction or by order of any competent government authority, **CITY** may give immediate notice to **CONTRACTOR** to discontinue the WORK and terminate this Contract. **CONTRACTOR** shall discontinue the WORK in such manner, sequence, and at such times as **CITY** may direct. **CONTRACTOR** shall have no claim for damages for such discontinuance or termination, nor any claim for anticipated profits on the WORK thus dispensed with, nor for any claim for penalty, nor for any other claim such as unabsorbed overhead, except for the WORK actually performed up to the time of discontinuance, including any extra WORK ordered by **CITY** to be done.

SAMPLE CONTRACT

6.5 Time to Correct (Declared Default or Breach):

6.5.1 Termination upon a declared default or breach may be exercised only after providing 7 (seven) calendar days written notice of default or breach, and the subsequent failure of the defaulting or breaching party, within five (5) calendar days of providing that default or breach notice, to provide evidence satisfactory to the aggrieved party demonstrating that the declared default or breach has been corrected. Time to correct shall run concurrently with any notice of default or breach and such time to correct is not subject to any stay with respect to the nonexistence of any Notice of Termination. Untimely correction shall not void the right to termination otherwise properly noticed unless waiver of the noticed default or breach is expressly provided in writing by the aggrieved party. There shall be no time to correct with respect to any notice of termination without cause, termination for nonappropriation or termination due to court injunction or order of a competent government authority.

6.6 Winding Up Affairs Upon Termination:

6.6.1 In the event of termination of this Contract for any reason, the parties agree that the provisions of this **Subsection 6.6** survive termination:

6.6.1.1 The parties shall account for and properly present to each other all claims for fees and expenses and pay those which are undisputed and otherwise not subject to set off under this Contract. Neither party may withhold performance of winding up provisions solely based on nonpayment of fees or expenses accrued up to the time of termination; and

6.6.1.2 **CONTRACTOR** shall satisfactorily complete WORK in progress at the agreed rate (or a pro rata basis if necessary) if so requested by **CITY**; and

6.6.1.3 **CONTRACTOR** shall execute any documents and take any actions necessary to effectuate an assignment of this Contract if so requested by **CITY**; and

6.6.1.4 **CONTRACTOR** shall preserve, protect, and promptly deliver into **CITY** possession all proprietary information in accordance with City Ownership of Proprietary Information.

6.7 Notice of Termination:

6.7.1 Unless otherwise specified in this Contract, termination shall not be effective until seven (7) calendar days after a party has provided written notice of default or breach, or notice of without cause termination. Notice of Termination may be given at the time of notice of default or breach, or notice of without cause termination. Notice of Termination may be provided separately at any time after the running of the 7-day notice period, and such termination shall be effective on the date the Notice of Termination is provided to the party unless a specific effective date is otherwise set forth therein. Any delay in providing a Notice of Termination after the 7-day notice period has run without a timely correction by the defaulting or breaching party shall not constitute any waiver of the right to terminate under the existing notice(s).

7. DAVIS-BACON & RELATED ACTS 29 CFR PARTS 1,3,5,6,&7 AND NRS 338.070(5):

7.1 **CONTRACTOR** shall comply with Davis-Bacon Act and NRS 338.070(5). **CONTRACTOR** and each covered contractor or subcontractor must provide a weekly statement of wages paid to each of its employees engaged in covered WORK. The statement shall be executed by **CONTRACTOR** or subcontractor or by an authorized officer or employee of **CONTRACTOR** or subcontractor who supervised the payment of wages and shall be on the "Statement of Compliance" form. **CONTRACTOR** shall submit a Statement of Compliance that is prescribed by the Nevada Labor Commissioner or contains identical wording. Per NRS 338.070(6) the records maintained pursuant to subsection 5 must be open at all reasonable hours to the inspection of the public body (the **CITY'S** representative) awarding the contract. The **CONTRACTOR** engaged on the public work or

subcontractor engaged on the public work shall ensure that a copy of each record for each calendar month is received by the public body awarding the contract (the **City**) **no later than 15 days after the end of the month**.

7.2 In the event federal funds are used for payment of all or part of this Contract, **CONTRACTOR** shall submit a Statement of Compliance form WH347 or a form with identical wording and a Statement of Compliance prescribed by the Nevada Labor Commissioner **within 7 days after the regular pay date for the**

SAMPLE CONTRACT

pay period. The original Statements shall be delivered to Carson City Public Works, 3505 Butti Way, Carson City, Nevada 89703, attention Davis-Bacon/Federal Funding Compliance.

7.3 CERTIFIED PAYROLLS FOR DAVIS-BACON AND PREVAILING WAGE PROJECTS:

7.3.1 The higher of the Federal or local prevailing wage rates for **CITY**, as established by the Nevada Labor Commission and the Davis-Bacon Act, shall be paid for all classifications of labor on this project WORK. Should a classification be missing from the Davis-Bacon rates the **CONTRACTOR** shall complete a request of authorization for additional classification or rate form SF1444 in its entirety and submit it to the **CITY** for approval and submission to the U.S. Department of Labor. Also, in accordance with NRS 338, the hourly and daily wage rates for the State and Davis-Bacon must be posted at the work site by **CONTRACTOR**. **CONTRACTOR** shall ensure that a copy of **CONTRACTOR'S** and subcontractor's certified payrolls for each calendar week are received by **CITY**.

7.3.2 Per NRS 338.070(5) a **CONTRACTOR** engaged on a public work and each subcontractor engaged on the public work shall keep or cause to be kept:

(a) An accurate record showing, for each worker employed by the contractor or subcontractor in connection with the public work:

- (1) The name of the worker;
- (2) The occupation of the worker;
- (3) The gender of the worker, if the worker voluntarily agreed to specify that information pursuant to subsection 4, or an entry indicating that the worker declined to specify such information;
- (4) The ethnicity of the worker, if the worker voluntarily agreed to specify that information pursuant to subsection 4, or an entry indicating that the worker declined to specify such information;
- (5) If the worker has a driver's license or identification card, an indication of the state or other jurisdiction that issued the license or card; and
- (6) The actual per diem, wages and benefits paid to the worker; and

(b) An additional accurate record showing, for each worker employed by the contractor or subcontractor in connection with the public work who has a driver's license or identification card:

- (1) The name of the worker;
- (2) The driver's license number or identification card number of the worker; and
- (3) The state or other jurisdiction that issued the license or card.

7.3.3 The original payroll records shall be certified and shall be submitted weekly to Carson City Public Works, 3505 Butti Way, Carson City, Nevada 89703, attention Davis-Bacon/Federal Funding Compliance. Submission of such certified payrolls shall be a condition precedent for processing the monthly progress payment. **CONTRACTOR**, as General Contractor, shall collect the wage reports from the subcontractors and ensure the receipt of a certified copy of each weekly payroll for submission to **CITY** as one complete package.

7.3.4 Pursuant to NRS 338.060 and 338.070, **CONTRACTOR** hereby agrees to forfeit, as a penalty to **CITY**, not less than Twenty Dollars (\$20) nor more than Fifty Dollars (\$50) for each calendar day or portion thereof that each worker employed on the Contract is paid less than the designated rate for any WORK done under the Contract, by **CONTRACTOR** or any subcontractor under him/her, or is not reported to **CITY** as required by NRS 338.070.

8. FAIR EMPLOYMENT PRACTICES:

8.1 Pursuant to NRS 338.125, Fair Employment Practices, the following provisions must be included in any contract between **CONTRACTOR** and a public body such as **CITY**:

8.1.1 ***In connection with the performance of work under this Contract, CONTRACTOR agrees not to discriminate against any employee or applicant for employment because of race, creed, color, national origin, sex, sexual orientation, gender identity, or age, including, without limitation, with regard to employment, upgrading, demotion or transfer, recruitment or recruitment advertising, layoff or termination, rates of pay or other forms of compensation, and selection for training, including without limitation, apprenticeship.***

SAMPLE CONTRACT

8.1.2 **CONTRACTOR** further agrees to insert this provision in all subcontracts hereunder, except subcontracts for standard commercial supplies or raw materials.

9. PREFERENTIAL EMPLOYMENT:

9.1 Unless, and except if, this Contract is funded in whole or in part by federal grant funding (see 40 C.F.R. § 31.36(c) *Competition*), pursuant to Nevada Revised Statute 338.130, in all cases where persons are employed in the construction of public works, preference must be given, the qualifications of the applicants being equal: (1) First: To persons who have been honorably discharged from the Army, Navy, Air Force, Marine Corps or Coast Guard of the United States, a reserve component thereof or the National Guard; and are citizens of the State of Nevada. (2) Second: To other citizens of the State of Nevada.

9.2 Unless, and except if, this Contract is funded in whole or in part by federal grant funding (see 40 CFR § 31.36(c) *Competition*), in connection with the performance of WORK under this Contract, **CONTRACTOR** agrees to comply with the provisions of Nevada Revised Statute 338.130 requiring certain preferences to be given to which persons are employed in the construction of a public work. If **CONTRACTOR** fails to comply with the provisions of Nevada Revised Statute 338.130, pursuant to the terms of Nevada Revised Statute 338.130(3), this Contract is void, and any failure or refusal to comply with any of the provisions of this section renders this Contract void.

10. REMEDIES:

Except as otherwise provided for by law or this Contract, the rights and remedies of the parties shall not be exclusive and are in addition to any other rights and remedies provided by law or equity, including, without limitation, actual damages, and to a prevailing party reasonable attorney's fees and costs. The parties agree that, in the event a lawsuit is filed and a party is awarded attorney's fees by the court, for any reason, the amount of recoverable attorney's fees shall not exceed the rate of \$125 per hour. **CITY** may set off consideration against any unpaid obligation of **CONTRACTOR** to **CITY**.

11. LIMITED LIABILITY:

CITY will not waive and intends to assert available Nevada Revised Statutes Chapter 41 liability limitations in all cases. Contract liability of both parties shall not be subject to punitive damages. Liquidated damages shall not apply unless otherwise expressly provided for elsewhere in this Contract. Damages for any **CITY** breach shall never exceed the amount of funds appropriated for payment under this Contract, but not yet paid to **CONTRACTOR**, for the fiscal year budget in existence at the time of the breach. **CONTRACTOR'S** tort liability shall not be limited.

12. FORCE MAJEURE:

Neither party shall be deemed to be in violation of this Contract if it is prevented from performing any of its obligations hereunder due to strikes, failure of public transportation, civil or military authority, act of public enemy, accidents, fires, explosions, or acts of God, including, without limitation, earthquakes, floods, winds, or storms. In such an event the intervening cause must not be through the fault of the party asserting such an excuse, and the excused party is obligated to promptly perform in accordance with the terms of this Contract after the intervening cause ceases.

13. INDEMNIFICATION:

13.1 To the extent permitted by law, including, but not limited to, the provisions of Nevada Revised Statutes Chapter 41, each party shall indemnify, hold harmless and defend, not excluding the other's right to participate, the other party from and against all liability, claims, actions, damages, losses, and

expenses, including but not limited to reasonable attorney's fees and costs, arising out of any alleged negligent or willful acts or omissions of the indemnifying party, its officers, employees and agents. Such obligation shall not be construed to negate, abridge, or otherwise reduce any other right or obligation of the indemnity which would otherwise exist as to any party or person described in this Section.

13.2 Except as otherwise provided in **Subsection 13.4** below, the indemnifying party shall not be obligated to provide a legal defense to the indemnified party, nor reimburse the indemnified party for the same, for any period occurring before the indemnified party provides written notice of the pending claim(s) or cause(s) of action to the indemnifying party, along with:

SAMPLE CONTRACT

13.2.1 a written request for a legal defense for such pending claim(s) or cause(s) of action; and

13.2.2 a detailed explanation of the basis upon which the indemnified party believes that the claim or cause of action asserted against the indemnified party implicates the culpable conduct of the indemnifying party, its officers, employees, and/or agents.

13.3 After the indemnifying party has begun to provide a legal defense for the indemnified party, the indemnifying party shall not be obligated to fund or reimburse any fees or costs provided by any additional counsel for the indemnified party, including counsel through which the indemnified party might voluntarily choose to participate in its defense of the same matter.

13.4 After the indemnifying party has begun to provide a legal defense for the indemnified party, the indemnifying party shall be obligated to reimburse the reasonable attorney's fees and costs incurred by the indemnified party during the initial thirty (30) day period of the claim or cause of action, if any, incurred by separate counsel.

14. **INDEPENDENT CONTRACTOR:**

14.1 **CONTRACTOR**, as an independent contractor, is a natural person, firm or corporation who agrees to perform WORK for a fixed price according to his or its own methods and without subsection to the supervision or control of the **CITY**, except as to the results of the WORK, and not as to the means by which the WORK are accomplished.

14.2 It is mutually agreed that **CONTRACTOR** is associated with **CITY** only for the purposes and to the extent specified in this Contract, and in respect to performance of the contracted WORK pursuant to this Contract. **CONTRACTOR** is and shall be an independent contractor and, subject only to the terms of this Contract, shall have the sole right to supervise, manage, operate, control, and direct performance of the details incident to its duties under this Contract.

14.3 Nothing contained in this Contract shall be deemed or construed to create a partnership or joint venture, to create relationships of an employer-employee or principal-agent, or to otherwise create any liability for **CITY** whatsoever with respect to the indebtedness, liabilities, and obligations of **CONTRACTOR** or any other party.

14.4 **CONTRACTOR**, in addition to **Section 13** (INDEMNIFICATION), shall indemnify and hold **CITY** harmless from, and defend **CITY** against, any and all losses, damages, claims, costs, penalties, liabilities, expenses arising out of or incurred in any way because of, but not limited to, **CONTRACTOR'S** obligations or legal duties regarding any taxes, fees, assessments, benefits, entitlements, notice of benefits, employee's eligibility to work, to any third party, subcontractor, employee, state, local or federal governmental entity.

14.5 Neither **CONTRACTOR** nor its employees, agents, or representatives shall be considered employees, agents, or representatives of **CITY**.

15. **INSURANCE REQUIREMENTS (GENERAL):**

15.1 **NOTICE: The following general insurance requirements shall apply unless these general requirements are altered by the specific requirements set forth in CITY'S solicitation for bid document, the adopted bid or other document incorporated into this Contract by the parties.**

These general insurance requirements do not include terms related to bond(s) required for this Contract, which are set forth in the CITY'S solicitation and below in this Contract following the execution pages.

15.2 **CONTRACTOR**, as an independent contractor and not an employee of **CITY**, must carry policies of insurance in amounts specified and pay all taxes and fees incident hereunto. **CITY** shall have no liability except as specifically provided in this Contract.

15.3 **CONTRACTOR** shall not commence work before: (1) **CONTRACTOR** has provided the required evidence of insurance to **CITY** Purchasing and Contracts, and (2) **CITY** has approved the insurance policies provided by **CONTRACTOR**.

15.4 Prior approval of the insurance policies by **CITY** shall be a condition precedent to any payment of consideration under this Contract and **CITY'S** approval of any changes to insurance coverage during the course of performance shall constitute an ongoing condition subsequent this Contract. Any failure of **CITY** to timely approve shall not constitute a waiver of the condition.

15.5 *Insurance Coverage (15.6 through 15.23):*

15.6 **CONTRACTOR** shall, at **CONTRACTOR'S** sole expense, procure, maintain and keep in force for the duration of this Contract the following insurance conforming to the minimum requirements specified below. Unless

specifically specified herein or otherwise agreed to by **CITY**, the required insurance shall be in effect prior to the commencement of work by **CONTRACTOR** and shall continue in force as appropriate until the latter of:

SAMPLE CONTRACT

15.6.1 Final acceptance by **CITY** of the completion of this Contract; or

15.6.2 Such time as the insurance is no longer required by **CITY** under the terms of this Contract.

15.6.3 Any insurance or self-insurance available to **CITY** under its coverage(s) shall be in excess of and non-contributing with any insurance required from **CONTRACTOR**. **CONTRACTOR'S** insurance policies shall apply

on a primary basis. Until such time as the insurance is no longer required by **CITY**, **CONTRACTOR** shall provide **CITY** with renewal or replacement evidence of insurance no less than thirty (30) calendar days before the expiration or replacement of the required insurance. If at any time during the period when insurance is required by this Contract, an insurer or surety shall fail to comply with the requirements of this Contract, as soon as **CONTRACTOR** has knowledge of any such failure, **CONTRACTOR** shall immediately notify **CITY** and immediately replace such insurance or bond with an insurer meeting the requirements.

15.7 *General Insurance Requirements (15.8 through 15.23):*

15.8 **Certificate Holder:** Each liability insurance policy shall list Carson City c/o Carson City Purchasing and Contracts, 201 N. Carson Street, Suite 3, Carson City, NV 89701 as a certificate holder.

15.9 **Additional Insured:** By endorsement to the general liability insurance policy evidenced by **CONTRACTOR**, The City and County of Carson City, Nevada, its officers, employees and immune contractors shall be named as additional insureds for all liability arising from this Contract.

15.10 **Waiver of Subrogation:** Each liability insurance policy shall provide for a waiver of subrogation as to additional insureds.

15.11 **Cross-Liability:** All required liability policies shall provide cross-liability coverage as would be achieved under the standard ISO separation of insureds clause.

15.12 **Deductibles and Self-Insured Retentions:** Insurance maintained by **CONTRACTOR** shall apply on a first dollar basis without application of a deductible or self-insured retention unless otherwise specifically agreed to by **CITY**. Such approval shall not relieve **CONTRACTOR** from the obligation to pay any deductible or self-insured retention. Any deductible or self-insured retention shall not exceed \$5,000.00 per occurrence, unless otherwise approved by **CITY**.

15.13 **Policy Cancellation:** Except for ten (10) calendar days notice for non-payment of premium, each insurance policy shall be endorsed to state that; without thirty (30) calendar days prior written notice to Carson City Purchasing and Contracts, the policy shall not be canceled, non-renewed or coverage and /or limits reduced or materially altered, and shall provide that notices required by this paragraph shall be sent by mail to Carson City Purchasing and Contracts, 201 N. Carson Street, Suite 3, Carson City, NV 89701.

15.14 **Approved Insurer:** Each insurance policy shall be issued by insurance companies authorized to do business in the State of Nevada or eligible surplus lines insurers acceptable to the State and having agents in Nevada upon whom service of process may be made, and currently rated by A.M. Best as "A-VII" or better.

15.15 **Evidence of Insurance:** Prior to commencement of work, **CONTRACTOR** must provide the following documents to Carson City Purchasing and Contracts, 201 North Carson Street, Suite 3, Carson City, NV 89701:

15.16 **Certificate of Insurance:** The Acord 25 Certificate of Insurance form or a form substantially similar must be submitted to Carson City Purchasing and Contracts to evidence the insurance policies and coverages required of **CONTRACTOR**.

15.17 **Additional Insured Endorsement:** An Additional Insured Endorsement (CG20 10 or C20 26), signed by an authorized insurance company representative, must be submitted to Carson City Purchasing and Contracts to evidence the endorsement of **CITY** as an additional insured per **Subsection 15.9** (Additional Insured).

15.18 **Schedule of Underlying Insurance Policies:** If Umbrella or Excess policy is evidenced to comply with minimum limits, a copy of the Underlyer Schedule from the Umbrella or Excess insurance policy may be required.

15.19 **Review and Approval:** Documents specified above must be submitted for review and approval by **CITY** Purchasing and Contracts prior to the commencement of work by **CONTRACTOR**. Neither approval by **CITY** nor failure to disapprove the insurance furnished by **CONTRACTOR** shall relieve **CONTRACTOR** of **CONTRACTOR'S** full responsibility to provide the insurance required by this Contract. Compliance with the insurance requirements of this Contract shall not limit the liability of **CONTRACTOR** or its sub-contractors, employees or agents to **CITY** or others, and shall be in addition to and not in lieu of any other remedy available to **CITY** under this Contract or otherwise. **CITY** reserves the right to request and review a copy of any required insurance policy or endorsement to assure compliance with these requirements.

15.20 **COMMERCIAL GENERAL LIABILITY INSURANCE:**

15.20.1 *Minimum Limits required:*

15.20.2 Two Million Dollars (\$2,000,000.00) - General Aggregate.

SAMPLE CONTRACT

15.20.3 Two Million Dollars (\$2,000,000.00) - Products & Completed Operations. Aggregate

15.20.4 One Million Dollars (\$1,000,000.00) - Each Occurrence.

15.20.5 Coverage shall be on an occurrence basis and shall be at least as broad as ISO 1996 form CG 00 01 (or a substitute form providing equivalent coverage); and shall cover liability arising from premises, operations, independent contractors, completed operations, personal injury, products, civil lawsuits, Title VII actions and liability assumed under an insured contract (including the tort liability of another assumed in a business contract).

15.21 BUSINESS AUTOMOBILE LIABILITY INSURANCE:

15.21.1 *Minimum Limit required:*

15.21.2 One Million Dollars (\$1,000,000.00) per occurrence for bodily injury and property damage.

15.21.3 Coverage shall be for "any auto", including owned, non-owned and hired vehicles. The policy shall be written on ISO form CA 00 01 or a substitute providing equivalent liability coverage. If necessary, the policy shall be endorsed to provide contractual liability coverage.

15.22 PROFESSIONAL LIABILITY INSURANCE (Architects, Engineers and Land Surveyors)

15.22.1 *Minimum Limit required:*

15.22.2 One Million Dollars (\$1,000,000.00).

15.22.3 Retroactive date: Prior to commencement of the performance of this Contract.

15.22.4 Discovery period: Three (3) years after termination date of this Contract.

15.22.5 A certified copy of this policy may be required.

15.23 WORKERS' COMPENSATION AND EMPLOYER'S LIABILITY INSURANCE:

15.23.1 **CONTRACTOR** shall provide workers' compensation insurance as required by Nevada Revised Statutes Chapters 616A through 616D inclusive and Employer's Liability insurance with a minimum limit of \$500,000.00 each employee per accident for bodily injury by accident or disease.

15.23.2 **CONTRACTOR** may, in lieu of furnishing a certificate of an insurer, provide an affidavit indicating that **CONTRACTOR** is a sole proprietor; that **CONTRACTOR** will not use the services of any employees in the performance of this Contract; that **CONTRACTOR** has elected to not be included in the terms, conditions, and provisions of Nevada Revised Statutes Chapters 616A-616D, inclusive; and that **CONTRACTOR** is otherwise in compliance with the terms, conditions, and provisions of Nevada Revised Statutes Chapters 616A-616D, inclusive.

16. BUSINESS LICENSE:

16.1 **CONTRACTOR** shall not commence work before **CONTRACTOR** has provided a copy of his Carson City business license to Carson City Purchasing and Contracts.

16.2 The Carson City business license shall continue in force until the latter of: (1) final acceptance by **CITY** of the completion of this Contract; or (2) such time as the Carson City business license is no longer required by **CITY** under the terms of this Contract.

17. COMPLIANCE WITH LEGAL OBLIGATIONS:

CONTRACTOR shall procure and maintain for the duration of this Contract any state, county, city, or federal license, authorization, waiver, permit, qualification or certification required by statute, ordinance, law, or regulation to be held by **CONTRACTOR** to provide the goods or WORK or any services of this Contract. **CONTRACTOR** will be responsible to pay all government obligations, including, but not limited to, all taxes, assessments, fees, fines, judgments, premiums, permits, and licenses required or imposed by law or a court. Real property and personal property taxes are the responsibility of **CONTRACTOR** in accordance with Nevada Revised Statutes Chapter 361 generally and NRS 361.157 and 361.159, specifically regarding for profit activity. **CONTRACTOR** agrees to be responsible for payment of any such government obligations not paid by its subcontractors during performance of this Contract. **CITY** may set-off against consideration due any delinquent government obligation.

18. WAIVER OF BREACH:

Failure to declare a breach or the actual waiver of any particular breach of this Contract or its material or nonmaterial terms by either party shall not operate as a waiver by such party of any of its rights or remedies as to any other breach.

SAMPLE CONTRACT

19. SEVERABILITY:

If any provision contained in this Contract is held to be unenforceable by a court of law or equity, this Contract shall be construed as if such provision did not exist and the nonenforceability of such provision shall not be held to render any other provision or provisions of this Contract unenforceable.

20. ASSIGNMENT / DELEGATION:

To the extent that any assignment of any right under this Contract changes the duty of either party, increases the burden or risk involved, impairs the chances of obtaining the performance of this Contract, attempts to operate as a novation, or includes a waiver or abrogation of any defense to payment by **CITY**, such offending portion of the assignment shall be void, and shall be a breach of this Contract. **CONTRACTOR** shall neither assign, transfer nor delegate any rights, obligations or duties under this Contract without the prior written approval of **CITY**. The parties do not intend to benefit any third party beneficiary regarding their respective performance under this Contract.

21. CITY OWNERSHIP OF PROPRIETARY INFORMATION:

21.1 Any files, reports, histories, studies, tests, manuals, instructions, photographs, negatives, blue prints, plans, maps, data, system designs, computer programs, computer codes, and computer records (which are intended to be consideration under this Contract), or any other documents or drawings, prepared or in the course of preparation by **CONTRACTOR** (or its subcontractors) in performance of its obligations under this Contract shall be the exclusive property of **CITY** and all such materials shall be delivered into **CITY** possession by **CONTRACTOR** upon completion, termination, or cancellation of this Contract. **CONTRACTOR** shall not use, willingly allow, or cause to have such materials used for any purpose other than performance of **CONTRACTOR'S** obligations under this Contract without the prior written consent of **CITY**. Notwithstanding the foregoing, **CITY** shall have no proprietary interest in any materials licensed for use by **CITY** that are subject to patent, trademark or copyright protection.

21.2 **CITY** shall be permitted to retain copies, including reproducible copies, of **CONTRACTOR'S** drawings, specifications, and other documents for information and reference in connection with this Contract.

21.3 **CONTRACTOR'S** drawings, specifications and other documents shall not be used by **CITY** or others without expressed permission of **CONTRACTOR**.

22. PUBLIC RECORDS:

Pursuant to Nevada Revised Statute 239.010, information or documents received from **CONTRACTOR** may be open to public inspection and copying. **CITY** will have the duty to disclose unless a particular record is made confidential by law or a common law balancing of interests. **CONTRACTOR** may clearly label specific parts of an individual document as a "trade secret" or "confidential" in accordance with Nevada Revised Statute 332.061, provided that **CONTRACTOR** thereby agrees to indemnify and defend **CITY** for honoring such a designation. The failure to so label any document that is released by **CITY** shall constitute a complete waiver of any and all claims for damages caused by any release of the records.

23. CONFIDENTIALITY:

CONTRACTOR shall keep confidential all information, in whatever form, produced, prepared, observed or received by **CONTRACTOR** to the extent that such information is confidential by law or otherwise required by this Contract.

24. FEDERAL FUNDING:

24.1 *In the event federal grant funds are used for payment of all or part of this Contract.*

24.1.1 **CONTRACTOR** certifies, by signing this Contract, that neither it nor its principals are presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any federal department or agency. This certification is made pursuant to the regulations implementing Executive Order 12549, Debarment and Suspension, 28 C.F.R. pt. 67, § 67.510, as published as pt. VII of the May 26, 1988, Federal Register (pp. 19160-19211), and any relevant program-specific regulations. This provision shall be required of every subcontractor receiving any payment in whole or in part from federal funds.

24.1.2 **CONTRACTOR** and its subcontractors shall comply with all terms, conditions, and requirements of the Americans with Disabilities Act of 1990 (P.L. 101-136), 42 U.S.C. 12101, as amended, and regulations adopted thereunder contained in 28 C.F.R. 26.101-36.999, inclusive, and any relevant program-specific regulations.

24.1.3 **CONTRACTOR** and its subcontractors shall comply with the requirements of the Civil Rights Act of 1964, as amended, the Rehabilitation Act of 1973, P.L. 93-112, as amended, and any relevant program-specific regulations, and Executive Order 11478 (July 21, 2014) and shall not discriminate against any employee or offeror for employment because of race, national origin, creed, color, sex, sexual orientation, gender identity, religion, age, disability or handicap condition (including AIDS and AIDS-related conditions).

SAMPLE CONTRACT

24.1.4 If and when applicable to the particular federal funding and the Scope of Work under this Contract, **CONTRACTOR** and its subcontractors shall comply with: American Iron and Steel (AIS) provisions of P.L. 113-76, Consolidated Appropriations Act, 2014, Section 1605 – Buy American (100% Domestic Content of iron, steel and manufactured goods); Federal Highway Administration (FHWA) 23 U.S.C. § 313 – Buy America, 23 C.F.R. § 635.410 (100% Domestic Content of steel, iron and manufactured products); Federal Transit Administration (FTA) 49 U.S.C. § 5323(j), 49 C.F.R. Part 661 – Buy America Requirements (See 60% Domestic Content for buses and other Rolling Stock).

25. **LOBBYING:**

25.1 The parties agree, whether expressly prohibited by federal law, or otherwise, that no funding associated with this Contract will be used for any purpose associated with or related to lobbying or influencing or attempting to lobby or influence for any purpose the following:

25.1.1 Any federal, state, county or local agency, legislature, commission, council or board;

25.1.2 Any federal, state, county or local legislator, commission member, council member, board member, or other elected official; or

25.1.3 Any officer or employee of any federal, state, county or local agency; legislature, commission, council or board.

26. **GENERAL WARRANTY:**

CONTRACTOR warrants that it will perform all WORK required hereunder in accordance with the prevailing standard of care by exercising the skill and care normally required of individuals performing the same or similar WORK, under the same or similar circumstances, in the State of Nevada.

27. **PROPER AUTHORITY:**

The parties hereto represent and warrant that the person executing this Contract on behalf of each party has full power and authority to enter into this Contract. **CONTRACTOR** acknowledges that this Contract is effective only after approval by the Carson City Board of Supervisors and only for the period of time specified in this Contract. Any WORK performed by **CONTRACTOR** before this Contract is effective or after it ceases to be effective is performed at the sole risk of **CONTRACTOR**.

28. **ALTERNATIVE DISPUTE RESOLUTION (Public Work):**

If the WORK under this Contract involves a “public work” as defined under NRS 338.010(17), then pursuant to NRS 338.150, a public body charged with the drafting of specifications for a public work shall include in the specifications a clause requiring the use of a method of alternative dispute resolution (“ADR”) before initiation of a judicial action if a dispute arising between the public body and the **CONTRACTOR** engaged on the public work cannot otherwise be settled. Therefore, unless ADR is otherwise provided for by the parties in any other incorporated attachment to this Contract, in the event that a dispute arising between **CITY** and **CONTRACTOR** regarding that public work cannot otherwise be settled, **CITY** and **CONTRACTOR** agree that, before judicial action may be initiated, **CITY** and **CONTRACTOR** will submit the dispute to non-binding mediation. **CITY** shall present **CONTRACTOR** with a list of three potential mediators. **CONTRACTOR** shall select one person to serve as the mediator from the list of potential mediators presented by **CITY**. The person selected as mediator shall determine the rules governing the mediation.

29. **GOVERNING LAW / JURISDICTION:**

This Contract and the rights and obligations of the parties hereto shall be governed by, and construed according to, the laws of the State of Nevada, without giving effect to any principle of conflict-of-law that would require the application of the law of any other jurisdiction. **CONTRACTOR** consents and agrees to the jurisdiction of the courts of the State of Nevada located in Carson City, Nevada for enforcement of this Contract.

30. **ENTIRE CONTRACT AND MODIFICATION:**

This Contract and its integrated attachment(s) constitute the entire Contract of the parties and such are intended as a complete and exclusive statement of the promises, representations, negotiations, discussions, and other Contracts that may have been made in connection with the subject matter hereof. Unless an integrated attachment to this Contract specifically displays a mutual intent to amend a particular part of this Contract, general conflicts in language between any such attachment and this Contract shall be construed consistent with the terms of this Contract. Unless otherwise expressly authorized by the terms of this Contract, no modification or amendment to this Contract shall be binding upon the parties unless the same is in writing and signed by the

SAMPLE CONTRACT

respective parties hereto and approved by the Carson City Board of Supervisors. The parties agree that each has had their respective counsel review this Contract which shall be construed as if it was jointly drafted.

31. ACKNOWLEDGMENT AND EXECUTION:

This Contract may be executed in counterparts. The parties hereto have caused this Contract to be signed and intend to be legally bound thereby as follows:

AND ALL SUPPLEMENTAL AGREEMENTS AMENDING OR EXTENDING THE WORK CONTEMPLATED.

SAMPLE CONTRACT

AND ALL SUPPLEMENTAL AGREEMENTS AMENDING OR EXTENDING THE WORK CONTEMPLATED.

ACKNOWLEDGMENT AND EXECUTION:

In witness whereof, the parties hereto have caused this Contract to be signed and intend to be legally bound thereby.

CARSON CITY
Finance Director

Attn: Kim Belt, CPM - Purchasing and Contracts Manager
201 North Carson Street, Suite 3
Carson City, Nevada 89701
Telephone: 775-283-7137
Fax: 775-887-2107
KBelt@carson.org

By: _____
Kim Belt, CPM

Dated _____

CITY'S LEGAL COUNSEL
Carson City District Attorney

I have reviewed this Contract and approve
as to its legal form.

By: _____
Deputy District Attorney

Dated _____

CITY'S ORIGINATING DEPARTMENT

BY: Darren Schulz, Director
Carson City Public Works Department
3505 Butti Way
Carson City, Nevada 89701
Telephone: 775-887-2355
Fax: 775-887-2164
DSchulz@carson.org

By: _____

Dated _____

SAMPLE CONTRACT

"name of signer" deposes and says: That he/she is Contractor or authorized agent of Contractor; the he/she has read the foregoing Contractor; and that he/she understands the terms, conditions and requirements thereof.

CONTRACTOR

BY:

TITLE:

FIRM:

CARSON CITY BUSINESS LICENSE #:

NEVADA CONTRACTOR'S LICENSE #:

Address:

City: State: Zip Code:

Telephone: /Fax:

E-mail Address:

(Signature of Contractor)

DATED _____

STATE OF _____)

)ss

County of _____)

Signed and sworn (or affirmed before me on this _____ day of _____, 2015, by "name of Contractor".

(Signature of Notary)

(Notary Stamp)

SAMPLE CONTRACT

CONTRACT ACCEPTANCE AND EXECUTION:

The Board of Supervisors for Carson City, Nevada at their publicly noticed meeting of June 18, 2015 approved the acceptance of the attached contract hereinbefore identified as **CONTRACT No. 1415-171** and titled " **Clear Creek Avenue Sanitary Sewer Extension**". Further, the Board of Supervisors authorizes the Mayor of Carson City, Nevada to set his hand to this document and record his signature for the execution of this contract in accordance with the action taken.

CARSON CITY, NEVADA

ROBERT L CROWELL, MAYOR

DATED this 18th day of June, 2015.

ATTEST:

SUSAN MERRIWETHER, CLERK-RECORDER

DATED this 18th day of June, 2015

PERFORMANCE BOND

Doc. No. 2151
(Rev. 11-17-99)

KNOW ALL MEN BY THESE PRESENTS, that I/we _____
_____ as Principal, hereinafter called Contractor, and

_____ a corporation duly organized under the laws of the State of Nevada, as Surety, hereinafter called the Surety, are held and firmly bound unto Carson City, Nevada a consolidated municipality of the State of Nevada, hereinafter called City, for the sum of \$ _____ Dollars (state sum in Words) _____

_____ for the payment whereof Contractor and Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, Contractor has by written agreement dated _____, 2015, entered into a contract with the City for **BID # 1415-171** and titled "**Clear Creek Avenue Sanitary Sewer Extension**" in accordance with drawings and specifications prepared by Carson City and which contract is by reference made a part hereof, and is hereinafter referred to as the Contract.

NOW, THEREFORE, THE CONDITION OF THIS OBLIGATION is such that, if Contractor shall promptly and faithfully perform said Contract then this obligation shall be null and void; otherwise it shall remain in full force and effect. The Surety hereby waives notice of any alteration or extension of time made by the City and its obligation is not affected by any such alteration or extension provided the same is within the scope of the contract. Whenever Contractor shall be, and is declared by City to be in default under the Contract, the City having performed City's obligations thereunder, the Surety may promptly remedy the default or shall promptly:

- 1) Complete the Contract in accordance with its terms and conditions; or
- 2) Obtain a bid or bids for completing the Contract in accordance with its terms and conditions, and upon determination by the City and the Surety jointly of the lowest responsive, responsible bidder, arrange for a contract between such bidder and the City, and make available as work progresses (even though there should be a default or a succession of defaults under the contract or contracts of completion arranged under this paragraph) sufficient funds to pay the cost of completion less the balance of the contract price, but not exceeding, including other costs and damages for which the Surety may be liable hereunder, the amount set forth in the first paragraph hereof. The term "balance of the contract price", as used in this paragraph, shall mean the total amount payable by City to Contractor under the Contract and any amendments thereto, less the amount properly paid by City to Contractor. No right of action shall accrue on this bond to or for the use of any person or corporation other than the City or successors of the City.

PERFORMANCE BOND

Continued for **BID # 1415-171** and titled **“Clear Creek Avenue Sanitary Sewer Extension”**

BY:	(Signature of Principal)
TITLE:	
FIRM:	
Address:	L.S.
City, State, Zip	
Phone:	
Printed Name of Principal	
Attest By	(Signature of Notary)
Subscribed and Sworn before me this	,2015
	day of

CLAIMS UNDER THIS BOND MAY BE ADDRESSED TO:	Nevada Resident Agent Information (complete for out of state bonding companies)
Name of Surety	Name of Local Agent
Address	Address
City	City
State/Zip Code	State/Zip Code
Name	Agent's Name
Title	Agent's Title
Telephone	Agent's Telephone
Surety's Acknowledgment:	Nevada Resident Agent's Acknowledgment:
By:	By:

NOTICE:

No substitution or revision to this bond form will be accepted. Sureties must be authorized to do business in and have an agent for service of process in the State of Nevada. Certified copy of Power of Attorney must be attached.

LABOR AND MATERIAL PAYMENT BOND

Doc. No. 2152
(Rev. 11-17-99)

KNOW ALL MEN BY THESE PRESENTS, that I/we _____
_____ as Principal, hereinafter called Contractor, and
_____ a
corporation duly organized under the laws of the State of Nevada, as Surety, hereinafter called the Surety, are
held and firmly bound unto Carson City, Nevada a consolidated municipality of the State of Nevada, hereinafter
called City, for the \$ _____ Dollars (state sum in words) _____
_____ f
or the payment whereof Contractor and Surety bind themselves, their heirs, executors, administrators, successors
and assigns, jointly and severally, firmly by these presents.

WHEREAS, Contractor has by written agreement dated _____, 2015 entered into a
contract with the City for **BID # 1415-171** and titled "**Clear Creek Avenue Sanitary Sewer Extension**" in
accordance with drawings and specifications prepared by Carson City and which contract is by reference made a
part hereof, and is hereinafter referred to as the Contract.

NOW, THEREFORE, THE CONDITION OF THIS OBLIGATION is such that, if Contractor
shall promptly make payment to all claimants as hereinafter defined, for all labor and material used or reasonably
required for use in the performance of the Contract, then this obligation shall be void; otherwise it shall remain in
full force and effect, subject, however, to the following conditions:

- 1) A claimant is defined as one having a direct contract with the Contractor or with a Subcontractor of the Principal for labor, material, or both, used or reasonably required for use in the performance of the Contract, labor and material being construed to include that part of water, gas, power, light, heat, oil, gasoline, telephone service, or rental of equipment directly applicable to the Contract.
- 2) The above-named Principal and Surety hereby jointly and severally agree with the City that every claimant as herein defined, who has not been paid in full before the expiration of a period of ninety (90) days after the date on which the last of such claimant's work or labor was done or performed, or materials were furnished by such claimant, may sue on this bond for the use of such claimant, prosecute the suit to final judgment for such sum or sums as may be justly due claimant, and have execution thereon. The City shall not be liable for the payment of any costs or expenses of any such suit.
- 3) No suit or action shall be commenced hereunder by any claimant:
 - a) Unless claimant, other than one having a direct contract with the Contractor, shall have given written notice to any two of the following: the Contractor, the City, or the Surety above named, within ninety (90) days after such claimant did or performed the last of the work or labor, or furnished the last of the materials for which said claim is made, stating with substantial accuracy the amount claimed and the name of the party to whom the materials were furnished, or for whom the work or labor was done or performed. Such notice shall be personally served or served by mailing the same by registered mail or certified mail, postage prepaid, in an envelope addressed to the Principal at any place the Principal maintains an office or conducts its business.
 - b) After the expiration of one (1) year following the date on which the last of the labor was performed or material was supplied by the party bringing suit.
 - c) Other than in a court of competent jurisdiction for the county or district in which the construction contract was to be performed.

LABOR AND MATERIAL PAYMENT BOND

Continued for **BID #1415-171** and titled "**Clear Creek Avenue Sanitary Sewer Extension**"

- 4) The amount of this bond shall be reduced by and to the extent of any payment or payments made in good faith hereunder, inclusive of the payment by Surety of mechanics' liens which may be filed of record against said improvement, whether or not claim for the amount of such lien be presented under and against this bond.

BY:	(signature of Principal)
TITLE:	
FIRM:	
Address:	L.S.
City, State, Zip	
Phone:	
Printed Name of Principal:	
Attest by:	(signature of notary)
Subscribed and Sworn before me this	, 2015
day of	

CLAIMS UNDER THIS BOND MAY BE ADDRESSED TO:	Nevada Resident Agent Information (complete for out of state bonding companies)
Name of Surety	Name of Local Agent
Address	Address
City	City
State/Zip Code	State/Zip Code
Name	Agent's Name
Title	Agent's Title
Telephone	Agent's Telephone
Surety's Acknowledgment:	Nevada Resident Agent's Acknowledgment:
By:	By:

NOTICE:

No substitution or revision to this bond form will be accepted. Sureties must be authorized to do business in and have an agent for service of process in the State of Nevada. Certified copy of Power of Attorney must be attached.

GENERAL CONDITIONS

SECTION 1.0 INTENT, DEFINITIONS, ABBREVIATIONS

GC 1.1 INTENT OF CONTRACT DOCUMENTS

The intent of the Contract Drawings and Specifications is to describe the details for the construction and completion of the Work which the Contractor undertakes to perform in accordance with the terms of the Contract. Contract Drawings and Specifications are divided into groups for the convenience of the City Engineer, and Construction Manager. These divisions are not for apportioning Work or responsibility for Work among subcontractors, suppliers, and manufacturers. The Contractor shall provide the City with a complete and operable Work or improvement, even though the Contract Drawing and Specifications may not specifically call out all items or items of work required of the Contractor to complete his/her tasks, incidental appurtenances, materials and the like and without additional compensation.

Where the Contract Drawings or Specifications describe portions of the Work in general terms but not in complete detail, it is understood that only the best general practice is to prevail and that only materials and workmanship of the best quality are to be used. The Contractor shall furnish tools, equipment, and incidentals, and do all the Work involved in executing the Contract in a satisfactory and complete manner.

The Instructions to Bidders, General Conditions, Special Conditions, Technical Specifications, Standard Specifications, Drawings and all supplementary documents are intended to be complete and complementary and to prescribe a complete work. If any omissions are made of information necessary to carry out the full intent and meaning of the Contract Documents, the Contractor shall immediately call the matter to the attention of the Engineer for furnishing of detail instructions. If specific lines, grades, and dimensions are not shown on the Drawings, those furnished by the Engineer shall govern.

Anything mentioned in these Specifications and not indicated on the Contract Drawing, or anything indicated on the Contract Drawing and not mentioned in these Specifications, shall be in the same force and effect as if indicated or mentioned in both.

In the event the materials and/or equipment are to be furnished by the City, as designated in the Special Conditions, this shall not relieve the Contractor of the above requirements to furnish all other labor, materials, and equipment to complete the Contract.

GC 1.2 PARTIAL INVALIDITY

If any provision of this Contract is held by a court of competent jurisdiction to be invalid, void or unenforceable, the remaining provisions shall nevertheless continue in full force without being impaired or invalidated in any way.

GC 1.3 GOVERNING ORDER OF BIDDING AND CONTRACT DOCUMENTS

The Bidding and Contract Documents include various divisions, sections, and conditions which are essential parts for the Work to be provided by the successful Bidder. A requirement occurring in one is as binding as though occurring in all. They are intended to be complementary and to describe and provide for a complete Work. In case of discrepancy, the following precedence will govern:

- a. Permits from City Departments and other Agencies as may be required by law
- b. Change Orders
- c. Contract
- d. Addenda
- e. Special Conditions
- f. Technical Specifications
- g. General Conditions
- h. Contract Drawing s
- i. Standard Specifications for Public Works Construction (Orange Book specifications) sponsored and distributed by R.T.C. of Washoe County, Washoe County, City of Sparks, City of Reno, Carson City, and City of Yerington; 1996 Edition with Revision No. 1 dated 12-15-1998, Revision No. 2 dated 5-1-2000, Revision No. 3 dated 11-08-2001, Revision No. 4 dated 2-27-2004, and Revision No. 5 dated 2-14-2007.
- j. Reference Specifications

GENERAL CONDITIONS

With reference to Contract Drawing, the order of precedence is as follows:

- 1) Addenda/Change Order Drawings govern over any other Drawing
- 2) Figures govern over scaled dimensions
- 3) Contract Detail Drawings govern over Contract General Drawings
- 4) Contract Drawing govern over Standard Details

GC 1.4 HEADINGS

Headings to parts, divisions, sections, articles, paragraphs, subparagraphs, and forms are inserted for convenience of reference only and shall not affect the interpretation of the Contract Documents.

GC 1.5 DEFINITIONS

The words directed, required, permitted, ordered, instructed, designated, applicable, appropriate, sufficient, proper, desirable, necessary, prescribed, approved, acceptable, satisfactory or words of like import refer to actions, expressions, and prerogatives of the City, Design Consultant, or Construction Manager.

Each gender work includes the masculine, feminine and neuter genders. References to gender, such as "workman" and "flagman" and the pronouns "he" or "his" referring to such titles, are abstract in the specifications, are used for the sake of brevity, and are intended to refer to persons of either sex and, if applicable, to the neuter gender.

Singular words include the plural and "person" includes firms, companies, and corporations.

Where used in the Contract Documents, the following words and terms shall have the meanings indicated. The meanings shall be applicable to the singular, plural, masculine, and feminine of the words and terms.

Acceptance - The formal action by the Carson City Board of Supervisors or the Carson City Regional Transportation Commissions accepting the work as being complete. See Final Acceptance.

Act of God - An earthquake, flood, cyclone, or other cataclysmic phenomenon of nature. A rain, windstorm, high water, or other natural phenomenon which might reasonably have been anticipated from historical records of the general locality of the Work, shall not be construed as an Act of God.

Addenda - Written or graphic instruments issued prior to the Bid Opening which modify or interpret the Contract Documents, Drawings, and specifications by additions, deletions, clarifications, or corrections. All addenda become part of the Contract Documents.

Additive Alternative Bid - The amount stated in the Bid Schedule - Additive Schedule to be added to the amount of the Base Bid if the corresponding change in the Work, as described in the Bid Documents, is accepted by the City with the Award of the Project, subject to the availability of funds. Bidder must quote all items to be responsive and considered for Award.

Agreement - The written Contract covering the performance of the Work as more fully described in the Contract Documents.

As Shown, As Indicated, As Detailed - Where these words or words of similar import are used, it shall be understood that reference to the Drawings is made unless stated otherwise.

As Directed, As Permitted, As Approved - Where these words or words of similar import are used, it shall be understood that written direction, requirements, permission, approval or acceptance of the Construction Manager is intended unless otherwise stated.

Bid - The offer or proposal of the Bidder submitted on the prescribed forms setting forth the price for the Work to be performed.

GENERAL CONDITIONS

Bidder - Any properly licensed and qualified individual, firm, partnership, corporation, joint venture, or combination thereof, submitting a proposal for the Work contemplated, acting directly or through a duly authorized representative.

Bond(s) - Bid, Performance, or Payment Bonds and Guarantee and other instruments of surety, furnished by the Contractor and Contractor's surety in accordance with the Contract Documents.

Calendar Day - Every day shown on the calendar.

Cardinal Change - A change required by the City which requires the Contractor to build a fundamentally different Project than originally planned.

City - Consolidated City/County of Carson City, Nevada. Under this Contract, the City is usually identified by name.

Change Order - A written order to the Contractor authorizing an addition, deletion, or revision of the work within the general scope of the Contract, or an adjustment in the contract price or time. Also referred to as a Contract Change Order.

Construction Completion or Completion of Work - Construction completion is when all work is complete, including punch list items, final cleanup, demobilization and submittal of final documentation, in accordance with the contract documents.

Construction Conflicts - Conflicts which may occur whenever corrections, alterations, or modifications of the Work under this Contract are ordered and approved by the City and change the character of the Work, the amount of the Work or the period of time in which to complete said Work.

Construction Inspector - The person designated by the City to act as its representative at the construction site, or remote locations, to perform construction inspection services.

Construction Manager - The person designated in writing by the City to act as its representative at the construction site and to perform construction inspection services and administrative functions relating to this Contract. Initial contact by the Contractor with the City shall be through the Construction Manager.

Construction Schedule - A graphic document that is computer generated which utilizes "critical path method" or "bar chart method" for scheduling projects. The construction schedule is supported by reports that can be generated to demonstrate relationships and logic.

Contract - The written agreement between Carson City and the Contractor setting forth the obligations of the parties thereunder, including, but not limited to the performance of the work, the furnishing of labor and materials, and the basis of payment.

Contract Completion Date - The date set forth in the Contract documents for the completion of all Contract work, including all punch list work, final cleanup and demobilization.

Contract Documents - The words "Contract Documents" shall mean any or all of, but not limited to, the following items, as applicable: Notice to Contractors, Instructions to Bidders, Bid Bond, Bid Proposal Summary, Contract Award Instructions, Contract, Performance Bond, Labor and Material Payment Bond, General Conditions, Prevailing Wage Rates, Permits, Special Conditions, Standard Specifications, Technical Specifications, Drawings, Addenda, if any, Executed Change Orders, if any, Notice of Award, and Notice to Proceed

Each of these items is to be considered by reference as part of the Contract Documents. Also referred to as the Contract.

GENERAL CONDITIONS

Contract Price - The total amount payable to the Contractor under the terms and conditions of the Contract based on the price given on the Bid Proposal, with adjustments made in accordance with the Contract. Said total amount shall include all sales, use, and other consumer taxes related to the work. The base amount given in the Bid Proposal shall be either a lump sum Bid or the summation of the unit price Bids multiplied by the estimated quantities set forth in the Bid form. Also referred to as the Contract Amount.

Contract Time - Number of calendar days stated in the Contract Documents for the completion of the Work, including all authorized time adjustments.

Contractor - The person or persons, firms, partnership, corporation, joint venture, or combination thereof, who have entered into the Contract with the City. "Contractor" shall mean the principal Contractor as defined by NRS 624.020 or his/her authorized representative.

Contractor's Plant and Equipment - Equipment, material, supplies, tools and all other items, except labor, brought onto the site by the Contractor to carry out the Work, but not to be incorporated in the Work.

Day(s) - See Calendar Day(s). A twenty-four hour time period beginning at 12 midnight of day one and terminating at 12 midnight of the same day.

Design Consultant - The engineer, architect or other licensed professional designated by the City to have design control over the Work or a specified portion of the Work, acting either directly or through duly authorized representatives. Such representatives shall act within the scope of the particular duties delegated to them.

Drawings - Refers to the Contract Drawing, profiles, cross sections, elevations, details, and other working Drawings and supplementary Drawings, or reproductions thereof, signed by the Design Consultant and bearing the appropriate Professional seal, approved by the City, and are referred to in the Contract Documents. Drawings show the location, character, dimensions, and details of the Work to be performed. The term "plans" has the same meaning as the term Drawings.

Engineer- The City Engineer of Carson City, or other person or firm designated by the City Engineer as his/her duly authorized representative.

Extra Work - An item of work not provided for in the Contract as awarded but found essential by the Engineer to the satisfactory completion of the Contract within its intended scope.

Field Directive - Written documentation of the actions of the City or Construction Manager in directing the Contractor. Also referred to as a Work Directive.

Field Order - A written instruction given to the Contractor by the City or Construction Manager, authorizing Work that is a change to the scope of Work, to be carried out on a time and materials basis, or a negotiated lump sum. Also referred to as a Work Directive.

Final Acceptance - The formal acceptance by the City of the Work for an entire Contract, which has been completed in all respects (including submittal of the operation and maintenance manuals, equipment start-up and testing, warranty of title, and submittal of record drawings, lien and claims releases, and warranty), in accordance with the Contract Documents and any modifications thereof previously approved.

Final Completion - Final completion is when construction is complete, the City has accepted the work, and the Notice of Completion has been recorded in the Office of the County Recorder. This is based on acceptance by the Carson City Board of Supervisors or the Carson City Regional Transportation Commission of the completed work embraced by the Contract.

GENERAL CONDITIONS

Float - Float or "total float" shall be defined as provided in the Associated General Contractors of America "CPM in Construction, A Manual for General Contractors".

General Conditions - Part of the Contract Documents representing the general clauses that establishes how the Contract is to be administered.

Holidays - Legal holidays observed by the City.

Inspector- The authorized representative of the Engineer assigned to observe the work or materials therefor.

Intermediate Completion- Intermediate Completion is the stage in the progress of the work when an element, section, or division of the Work is sufficiently complete in accordance with the contract documents so that the City can occupy or utilize the essential component(s) of the contractually defined element, section or division of the Work for its intended purpose.

Laboratory - The designated materials testing laboratory authorized by the City to test materials and Work involved in the Contract.

Liquidated Damages - Money to be paid to the City or to be deducted from any payments due to the Contractor for each day's delay in completing the whole, any specified portion of the Work beyond the time allowed in the Contract Documents, submitting award documentation, or technical submittals.

Major Bid Item - Any bid item whose unit bid item price extension is 5 percent or more of the total Contract Price.

Notice of Award - A written notice by the City to the Contractor informing it that the Contract has been awarded to the Contractor.

Notice of Completion - The City will cause to be recorded in the Office of the County Recorder, a notice of completion, which is based on acceptance by the Carson City Board of Supervisors or the Carson City Regional Transportation Commission of the completed work embraced in the Contract.

Notice to Proceed - A) The written notice by the City to the Contractor authorizing the Contractor to proceed with the Work and establishing the date of commencement of the Work. B) Material Only Notice to Proceed - Written notice by the City to the Contractor authorizing the Contractor to proceed with ordering materials, preparing shop Drawings, and acquiring permits only.

Owner B Carson City, which has contracted for the performance of the Work.

Owner's Representative - The person designated in writing by the City to act as its agent on specified matters relating to this Contract. The Owner's Representative may or may not be the Engineer, the Construction Manager, or the Design Consultant.

Plans - All drawings or reproductions thereof pertaining to details of the Work and which are made a part of the Contract Documents. The term "Plans" has the same meaning as "Drawings". See Drawings

Project - The undertaking to be performed under the provisions of the Contract.

Provide - Shall be understood to mean furnish and install, complete in place.

Punch List - List of incomplete items of work and of items of work which are not in conformance with the Contract.

Reference Documents - Bulletins, Standards, Rules, Methods of Analysis or Test, Codes and Specifications of public or private agencies, Engineering Societies, or Industrial Associations. Reference

GENERAL CONDITIONS

shall be to the latest edition thereof, including Amendments, which are in effect and published at the time the Invitation for Bids is issued, unless a specific edition is identified, in which case reference shall be to such specific edition.

Right-of-Way - The area provided by the City for use in constructing the work covered by the Contract, including appurtenances thereto. The right-of-way so designated may be either temporary or permanent.

Schedule of Values - A list of all major items, or those requested by the City, including their respective quantities and unit prices for all Work and materials furnished by the Contractor in order to comply with the contract drawings and specifications, whether or not indicated in the approximate quantities or pertaining to the items of work listed therein.

Service Connection - All or any portion of a pipeline including sewer laterals, conduit, wire, cable or duct, including meters between a utility main distribution line and an individual customer or customers when served by a single connection.

Service Provider - A service provider is an organization, company, or business that provides a service for the Work, but does not perform the Work at the Project site.

Shall - Refers to actions by either the Contractor or the City and means the Contractor or City has entered into a covenant with the other party to do or perform the action.

Shop Drawings - All diagrams, drawings, illustrations, brochures, schedules, and all other data or submittals required by the Contract to be furnished by the Contractor illustrating fabrication, installation, dimensions, and other aspects of the Work.

Site - The property as described in the Special Conditions or as shown on the Drawings where the Project is to be constructed. See Work Area.

Special Conditions - Part of the Contract Documents that establishes special requirements peculiar to the Work and supplementary to the General Conditions.

Specifications - That part of the Contract Documents consisting of the General Conditions, Special Conditions, applicable Standard Specifications, Technical Specifications, other named standard specifications.

Standard Plans - The Standard Details for Public Works Construction, (Orange Book Details) sponsored and distributed by RTC of Washoe County, Washoe County, City of Reno, City of Sparks, Carson City and City of Yerington.

Standard Specifications - The Standard Specifications for Public Works Construction, (Orange Book Specifications) sponsored and distributed by RTC of Washoe County, Washoe County, City of Reno, City of Sparks, Carson City and City of Yerington; 1996 Edition with Revision No. 1 dated 12-15-1998, Revision No. 2 dated 5-1-2000, Revision No. 3 dated 11-08-2001, Revision No. 4 dated 2-27-2004, and Revision No. 5 dated 2-14-2007.

Subcontractor - A subcontractor is a person or entity who has a direct Contract with the Contractor to perform Work at the Site. The term subcontractor means a subcontractor or subcontractor's authorized representative.

Submittals - The information which is specified for submission to the Construction Manager in accordance with the specifications.

Substantial Completion - Substantial Completion is the stage in the progress of the Work when all Work is sufficiently complete in accordance with the Contract Documents so the City can occupy or utilize the essential components of the Project for its intended use.

GENERAL CONDITIONS

Sub-subcontractor - A sub-subcontractor is a person or entity who has a Contract with a subcontractor to perform any of the Work at the Site. The term sub-subcontractor means a sub-subcontractor or an authorized representative thereof.

Superintendent - the Contractor's authorized representative in responsible charge of the Work.

Supplier - Any person, firm, corporation, or organization who supplies materials or equipment for the Work, including that fabricated to a special design, and may also be a subcontractor or a sub-subcontractor, also referred to as Vendor.

Surety - The person, firm, corporation, or organization that joins with the Contractor in assuming the liability for the faithful performance of the Work and for the payment of all obligations pertaining to the Work in accordance with the Contract Documents by issuing the Bonds required by the Contract Documents or by law.

Technical Specifications- The specialized directions, provisions, and requirements of the Contract Documents for materials, equipment, construction systems, standards, and workmanship.

Title and Headings - The titles or headings of the section and subsections in the Contract Documents are intended for convenience of reference and shall not be considered as having bearing on their interpretation.

Total Base Bid - The base amount given in the Bid Schedule as either a lump sum bid, or the summation of the unit price bids multiplied by the estimated quantities as set forth in the bid form.

Utility- Public or private fixed improvement for the transportation of fluids, gases, power, signals, or communications and shall be understood to include tracks, overhead and underground wires, cables, pipelines, conduits, ducts, sewers or storm drains.

Work - The labor, materials, equipment, supplies, and other items necessary for the execution, completion, and fulfillment of the Contract.

Work Area - That area which is defined on the Contract Drawings as the City's Right-of-Way and/or temporary easement available to the Contractor for construction purposes. See Site.

Work Directive - A written directive to the Contractor issued after the effective date of the Contract and signed by the City's Construction Manager ordering an addition, deletion or revision in the Work, or responding to differing or unforeseen conditions under which the Work is to be performed, or to emergencies. A Work Directive may not change the Contract Price or Contract Time, but is the basis and evidence that the parties expect that the change directed or documented by the Work Directive will be incorporated in a subsequently issued Change Order following negotiations of the parties as to its effect, if any, on the Contract Price or Contract Time.

Working Day - A calendar day on which weather and other conditions not under the control of the Contractor will permit construction operations to proceed for at least 5 hours of the day with at least seventy-five (75) percent of the normal working force engaged in performing the current critical item(s) of work on the latest favorably reviewed Construction Schedule, exclusive, however, of Saturdays, Sundays, City recognized holidays, and any day that is incumbent upon the Contractor, by means of a Master Labor Agreement, to observe as a holiday. However, if the Contractor elects to work on such days, those days will be considered as a working day.

GC 1.6 ABBREVIATIONS

Whenever the following terms are used, the intent and meaning shall be as follows:

GENERAL CONDITIONS

Abbreviations Stand For

AASHTO	American Association of State Highway and Transportation Officials
ACI	American Concrete Institute
AI	The Asphalt Institute
AIA	American Institute of Architects
AIEE	American Institute of Electrical Engineers
AISC	American Institute of Steel Construction
AISI	American Iron and Steel Institute
AITC	American Institute of Timber Construction
AMCA	Air Moving and Conditioning Association
ANSI	American National Standards Institute (formerly USASI, USAS, ASA)
APA	American Plywood Association
API	American Petroleum Institute
APWA	American Public Works Association
AREA	American Railway Engineers Association
ASCE	American Society of Civil Engineers
ASHRAE	American Society of Heating, Refrigerating and Air Conditioning Engineers
ASLA	American Association of Landscape Architects
ASME	American Society of Mechanical Engineers
ASTM	American Society of Testing and Materials
AWG	American Wire Gauge
AWPA	American Wood-Preserver's Association
AWS	American Welding Society
AWWA	American Water Works Association
CBR	California Bearing Ratio
COE	Department of the Army Corps of Engineers
CRSI	Concrete Reinforcing Steel Institute
DFPA	Douglas Fir Plywood Association
DIPRA	Ductile Iron Pipe Research Association
EIA	Electronic Industries Association
EPA	U.S. Environmental Protection Agency
ETL	Electronic Testing Laboratory
FHWA	Federal Highway Administration
HI	Hydraulic Institute
HMI	Hoist Manufacturers Institute
IAPMO	International Association of Plumbing and Mechanical Officials
ICBO	International Conference of Building Officials
IEEE	Institute of Electrical and Electronic Engineers
IES	Illuminating Engineering Society
IPCE	International Power Cable Engineers Association
ISA	Instrument Society of America
MUTCD	Manual on Uniform Traffic Control Devices
NAAMM	National Association of Architectural Metal Manufacturers
NBFU	National Board of Fire Underwriters
NBS	National Bureau of Standards
NDEP	Nevada Department of Environmental Protection
NDOT	Nevada Department of Transportation
NEC	National Electric Code
NEMA	National Electrical Manufacturers Association
NFPA	National Fire Protection Association
NOSHA	Nevada Occupational Safety and Health Act
NRS	Nevada Revised Statutes
NSF	National Sanitation Foundation
NWMA	National Woodwork Manufacturers Association
OSHA	Occupational Safety and Health Act

GENERAL CONDITIONS

PCA	Portland Cement Association
RTC	Regional Transportation Commission
SMACNA	Sheet Metal and Air Conditioning Contractors National Association
SSPC	Structural Steel Painting Council
TCA	Tile Council of America
UBC	Uniform Building Code
UPC	Uniform Plumbing Code
U/L or UL	Underwriters Laboratories
WCLIB	West Coast Lumber Inspection Bureau

GENERAL CONDITIONS

SECTION 2.0 CONTRACT ADMINISTRATION AND RESPONSIBILITIES: OWNER'S REPRESENTATIVE, CONSTRUCTION MANAGER, DESIGN CONSULTANT AND CONTRACTOR

GC 2.1 ADMINISTRATION

The Owner's Representative, the Construction Manager, and the Design Consultant will provide administration of the Contract as hereinafter discussed. The duties, responsibilities and limitations of authority of the Design Consultant and the Construction Manager as the representatives of the City during construction, as set forth in the Contract Documents, will not be modified or extended without approval of the City.

In case of the termination of the employment of the Design Consultant or the Construction Manager, the City shall appoint a Design Consultant or a Construction Manager whose status under the Contract Documents shall be that of the former Design Consultant or Construction Manager, respectively.

GC 2.2 OWNER'S REPRESENTATIVE

2.2.1 GENERAL

The Owner's Representative has the authority to act on behalf of the City on change orders, progress payments, Contract decisions, acceptability of the Contractor's work, and early possession.

2.2.2 CHANGE ORDERS

The Owner's Representative has the authority to accept or reject change orders and cost proposals submitted by the Contractor or as recommended by the Construction Manager.

2.2.3 PROGRESS PAYMENTS

The Owner's Representative has the authority to accept or reject requests for progress payments which have been submitted by the Contractor and recommended by the Construction Manager.

2.2.4 CONTRACT DECISIONS

Should the Contractor disagree with the Construction Manager's decision with respect to the Contract, the Contractor may appeal to the Owner's Representative in accordance with the provisions of the Contract.

2.2.5 ACCEPTABILITY OF WORK

The Owner's Representative has the authority to make the final determination of the acceptability of the Work. The Owner's Representative also has the authority to accept or reject the Design Consultant's recommendations regarding retention of non-conforming work as provided.

GC 2.3 CONSTRUCTION MANAGER

2.3.1 GENERAL

The Construction Manager is a representative of the City employed to act as advisor and consultant to the City in construction matters related to the Contract.

All instructions to the Contractor and all communications from the Contractor to the City or the Design Consultant shall be forwarded through the Construction Manager. The Construction Manager will have authority to act on behalf of the City only to the extent provided in the Contract Documents. The City has delegated its authority to the Construction Manager to make initial decisions regarding questions which may arise as to the quality or acceptability of materials furnished and work performed, and as to the manner of performance and rate of progress of the Work under the Contract. The Construction Manager shall interpret the intent and meaning of the Contract and shall make initial decisions with respect to the Contractor's fulfillment of the Contract and the Contractor's entitlement to compensation. The Contractor shall look initially to the Construction Manager in matters relating to the Contract.

GENERAL CONDITIONS

2.3.2 REPRESENTATIVE

The Construction Manager will generally be represented at the site by a resident Construction Manager, a resident engineer, or a resident inspector who will observe the progress, quality, and quantity of the Work to determine, in general, if the Work is proceeding in accordance with the intent of the Contract Documents. The

Construction Manager shall not be responsible for the Contractor's construction means, methods, techniques, sequences, or procedures, or for safety precautions and programs in connection with the Work.

In accordance with the provisions detailed elsewhere in these General Conditions, the Construction Manager will make decisions relative to all matters of interpretation or execution of the Contract Documents.

2.3.3 INSPECTION OF CONSTRUCTION

The Construction Manager shall have the authority to reject Work and materials which do not conform to the Contract Documents, and to require special inspection or testing.

The Construction Manager may employ one or more inspectors to observe the Work and to act in matters of construction under this Contract. An inspector is not authorized to revoke, alter, or waive any requirements of the Contract Documents. The inspector is authorized to call to the attention of the Contractor any failure of the Work, materials or workmanship to conform to the Contract Documents. The inspector shall have the authority to reject materials or, in any emergency, suspend the Work. The Contractor may appeal any such issue which it disagrees with to the Construction Manager for decision.

2.3.4 ACCEPTABILITY OF THE WORK

The Construction Manager shall make a recommendation to the City as to the acceptability of the Work.

2.3.5 CHANGE ORDERS

The Construction Manager has the authority to initiate change orders; to reject change orders proposed by the Contractor or Design Consultant; to negotiate and recommend acceptance of change orders; or to order minor changes in the Work at no cost or time extension to the City.

2.3.6 CONSTRUCTION SCHEDULE

The Construction Manager has the authority to review and recommend acceptance of the Progress Schedule submitted by the Contractor at the start of the Work and subsequent revisions for conformance to the specified sequence of work and logic.

2.3.7 PROGRESS PAYMENTS

The Construction Manager has the authority to recommend acceptance or rejection of requests for progress payments which have been submitted by the Contractor.

2.3.8 FINAL ACCEPTANCE

The Construction Manager, with the assistance of the Design Consultant, will conduct inspections to determine substantial completion and final construction completion of the Work, and will receive and forward to the City, for the City's acceptance, written warranties, and related documents required by the Contract and assembled by the Contractor. The Construction Manager will recommend acceptance of the work by the City.

GC 2.4 DESIGN CONSULTANT

2.4.1 GENERAL

The Design Consultant will have the authority to act on behalf of the City to the extent provided in the Contract Documents.

GENERAL CONDITIONS

2.4.2 INTERPRETATIONS

The Design Consultant has the authority to be the initial interpreter of the technical requirements of the Contract Documents. Either party to the Contract may make written request to the Construction Manager for interpretations necessary for the proper execution or progress of the Work. The Construction Manager shall refer such written requests of the Contractor to the Design Consultant, who will render such interpretations. Where the Contractor has requested an interpretation from the Construction Manager, or been notified by the Construction Manager that such interpretation has been requested by the City, any Work done before receipt of such interpretations, if not in accordance with same, is subject to being removed and replaced or adjusted as directed by the Construction Manager without additional expense to the City.

2.4.3 ACCEPTABILITY OF THE WORK

The Design Consultant has the authority to make a recommendation as to the acceptability of the Work. The Design Consultant has the authority to recommend acceptance regarding the retention of defective work.

2.4.4 SITE OBSERVATIONS

The Design Consultant may visit the site at intervals appropriate to the stage of construction to become familiar with the progress and quality of the Work and to determine if the Work is proceeding in accordance with the Contract Documents. However, the Design Consultant will not be required to make extensive or continuous on-site inspections to check the quality or quantity of the Work.

2.4.5 SUBMITTALS

The Design Consultant has the authority to review and take other appropriate action upon the Contractor's submittals of shop drawings, product data, and samples for conformance with the design concept of the Work and the Contract Documents.

GC 2.5 CITY

2.5.1 GENERAL

The City, acting through the Owner's Representative or the Construction Manager, shall have the authority to act as the sole judge of the Work and materials with respect to both quantity and quality as set forth in the Contract.

2.5.2 ATTENTION TO WORK

The City shall notify the Contractor of the name of the individual designated as the Owner's Representative and the name of the individual designated by the Construction Manager to act as the Construction Manager's representative with the City's authority. The Construction Manager's designated representative will regularly be at the site of the Work.

2.5.3 INSPECTION

In addition to the Construction Manager, the City may employ one or more inspectors to observe the Work and to act in matters of construction under this Contract. An inspector is not authorized to revoke, alter, or waive any requirements of the specifications. The inspector is authorized to call to the attention of the Contractor any failure of the Work or materials to conform to the Contract Documents. The inspector shall have the authority to reject materials or, in any emergency, suspend the Work. The Contractor may appeal any such issue which it disagrees with to the Construction Manager for its decision.

Separate and independent from the inspection above, the Project may be inspected by Building Officials or other agency officials (i.e. Fire Officials, Nevada Department of Transportation) for code compliance. Such inspectors shall have the authority provided to them by local jurisdiction.

If upon routine inspection by the City a problem is found that creates a safety hazard for either City employees or the general public and the General Contractor or subcontractor is not on site, the City employees will correct the safety hazard and the General Contractor will be charged for the City's labor, materials and equipment for making the correction plus a fixed penalty fee of \$500 per occurrence.

GENERAL CONDITIONS

2.5.4 CITY'S RIGHT TO CARRY OUT THE WORK

If the Contractor and/or his/her surety defaults or neglects to carry out the Work in accordance with the Contract Documents, and fails within seven (7) days after receipt of written notice from the City to commence correction of such default or neglect with diligence and promptness, the City may make good such deficiencies.

Whenever, in the opinion of the Construction Manager, the Contractor has not taken sufficient precautions for the safety of the public or the protection of the Work to be constructed under this contract, or of adjacent structures or property which may be injured by processes of construction on account of such negligence, and whenever in the opinion of the Construction Manager, an emergency shall arise and immediate action shall be considered necessary in order to protect public or private, personal or property interest, then and in that event the Construction Manager, with or without notice or prior legal process to the Contractor, may provide suitable protection to the said interests by causing such work to be done and such material to be furnished as shall provide such protection as the Construction Manager may consider necessary and adequate.

In either case an appropriate Change Order shall be issued unilaterally deducting from the payments due the Contractor the cost of correcting such deficiencies and/or for performing such work, including compensation for the Design Consultant's, the Construction Manager's, and City's additional services made necessary by such default, neglect, failure or emergency.

The performance of such emergency work under the direction of the Construction Manager shall in no way relieve the Contractor from any damages which may occur during or after such precaution has been taken by the Construction Manager.

2.5.5 CITY'S RIGHT TO USE OR OCCUPY

The City reserves the right to use the sewer, water, reclaimed water, storm drains and roadway systems as well as the right to occupy and use any completed part or parts of the Work, providing these parts and facilities have been approved for use or occupancy by the City. The City anticipates to use the sewer, water, reclaimed water, storm drains and roadway systems throughout the construction contract, with no increase in the contract amount. Use of the systems will not change the contractual obligations of the Contractor regarding security, damage to the Work, insurance, the period for corrections to the Work, and the commencement of Warranties. The exercise of this right shall in no way constitute an acceptance of the total Work of this Contract, or any other part of the Work, nor shall it in any way prejudice the City's rights in the Contract, or any bonds guaranteeing the same. The Contract shall be deemed completed only when all the Work Contracted has been duly and properly performed and accepted by the City.

Prior to such occupancy or use, the City and Contractor shall agree in writing regarding the responsibilities assigned to each of them for payments, security, maintenance, heat, utilities, damage to the Work, insurance, the period for correction of the Work, and the commencement of warranties required by the Contract Documents.

In exercising the right to occupy or use completed parts of the Work, the City shall not make any use which will materially increase the cost to the Contractor without increasing the Contract Amount, nor materially delay the completion of the Contract without extending the time for completion.

The part or parts of the Work, if any, which the City anticipates to use or occupy during construction are generally noted in the Special Conditions. Failure to note a part or parts of the Work for use or occupancy shall not limit the City's right to use or occupy part or parts of the Work not noted.

2.5.6 CITY'S RIGHT TO PERFORM WORK AND TO AWARD SEPARATE CONTRACTS

The City reserves the right to perform the Work related to the Project with the City's own forces, and to award separate Contracts in connection with the Project or other Work on the site under these or similar Conditions of the Contract. If the Contractor claims that delay, damage, or additional cost is involved

GENERAL CONDITIONS

because of such action by the City, the Contractor shall make such claim as provided elsewhere in the Contract Documents.

When separate contracts are awarded for different portions of the Project or other Work on the Site, the term "Contractor" in the Contract Documents in each case shall mean the contractor who executes each separate agreement. The City will provide for the coordination of the Work of the City's own forces and of each separate contractor with the Work of the Contractor, who shall cooperate therewith.

2.5.7 PROPERTY RIGHTS IN MATERIALS

Nothing in this Contract shall be construed as vesting in the Contractor any right of property in the materials used after they have been attached or affixed to the work or the soil, or after payment has been made for materials delivered to the Site of the Work, or stored subject to or under the control of the City. All such materials shall become the property of the City upon being so attached or affixed or upon payment for materials delivered to the Site of the Work or stored subject to or under the control of the City.

Soil, stone, gravel, and other materials found at the Site of the Work and which conform to the plans and specifications for incorporation into the Work may be used in the Work. No other use shall be made of such materials except as may be otherwise described in the plans and specifications.

2.5.8 CITY OBSERVED HOLIDAYS

The following are the legal Holidays observed by the City. The Contractor shall not perform any Work on a City observed Holiday. When the holiday falls on a Saturday, it is observed the prior Friday; when the holiday falls on a Sunday it is observed on the following Monday:

New Years Day - January 1st
Martin Luther King Day - 3rd Monday of January
Presidents Day - 3rd Monday of February
Memorial Day - last Monday of May
Independence Day - July 4th
Labor Day - 1st Monday of September
Nevada day - last Friday of October
Veterans Day - November 11th
Thanksgiving Day - 4th Thursday of November
Family Day - 4th Friday of November
Christmas Day - December 25th

Any other legal holiday declared by the President of the United States, the Governor of Nevada, or the Carson City Board of Supervisors.

2.5.9 AUDIT OF RECORDS

The City, acting through its Internal Auditor or an outside appointed auditor, may audit or direct the audit of any and all records of the Contractor pertaining to this Contract. In case any portion of this Contract is funded through NDOT, FHWA, or other agencies, they, too, shall have the right to audit any and all records of the Contractor pertaining to this Contract. Contractor agrees by entering this Contract to provide access to any and all records of Contractor pertaining to this Contract for a period of three (3) years after Contract acceptance.

2.5.10 ATTORNEY'S FEES

In the event the Contractor files a complaint or writ naming the City as a party and the Contractor fails to obtain all the relief requested in the complaint or writ, the Contractor shall pay the City reasonable attorney fees and the costs for participating in the litigation. It is specifically agreed that reasonable attorney fees shall be \$150.00 per hour for City-employed attorneys or the usual per hour fee charged by any other attorney retained by the City to participate in the litigation.

GENERAL CONDITIONS

GC 2.6 CONTRACTOR

2.6.1 OFFICE

The Contractor's office at the Project Site is hereby designated as the legal address of the Contractor for the receipt of documents, samples, notices, letters, and other articles of communication. Should the Contractor not maintain an office at the Project site, the Contractor shall notify the Construction Manager regarding the Contractor's legal address for its receipt of Project documents.

2.6.2 CONTRACTOR'S REPRESENTATIVE

At the pre-construction conference (see GC 3.9) the Contractor shall notify the City in writing of the name of the person and an alternate, if applicable, who will act as the Contractor's Representative(s) and shall have the authority to act in matters relating to this Contract. Such notification shall include the Representative's list of projects for which he/she held the position of Contractor's Representative for a three (3) year period. The list shall include the type of construction, the cost of construction, and the name of the owner(s) or agency(ies) including telephone numbers of contact persons. The Contractor's Representative shall have at least three (3) years of experience related to similar Work as described in the Contract Documents.

The Engineer and/or the City may reject the request for Contractor's Representative if, in the opinion of the Engineer and/or the City, the Contractor's Representative is not qualified to perform the Work. No additional payment or compensation will be considered for the rejection and subsequent hiring of Contractor's Representative. A replacement Contractor's Representative for a previously approved Contractor's Representative shall meet the same qualifications as listed above. Contractor shall submit the information requested above to demonstrate that the replacement Contractor's Representative meets the qualifications listed above.

The Contractor, acting through its Representative, shall give personal attention to, and shall manage the Work, so that it shall be prosecuted faithfully. The Contractor's Representative shall be an employee of the Contractor. Upon written request of the Contractor, this requirement may be waived by the City.

At all times during the progress of the Work, the Contractor's representative shall be personally present at the Project site, or a designated alternate shall be at the Project site who has the authority to act in matters relating to the Contract. The Contractor's representative or designated alternate shall have the authority to carry out the provisions of the Contract and to supply materials, equipment, tools, and labor without delay for the performance of the Work. If neither the Contractor's representative nor a designated alternate is at the Project site, the City acting through the Construction Manager shall have the authority to suspend the work until such a representative is at the Project site.

Before initial work is begun on the Contract, the Contractor shall file with the Construction Manager, and City, addresses and telephone numbers where the Contractor's and all subcontractors' representatives can be reached for emergency call outs during all hours, including nights and weekends, when work is not in progress.

2.6.3 CONSTRUCTION PROCEDURES

The Contractor will supervise and direct the Work. The Contractor shall determine the means, methods, techniques, sequences, and procedures of construction, except in those instances where the City, to define the quality of an item of work, specifies in the Contract a means, method, technique, sequence, or procedure for construction of that item of Work.

2.6.4 CONTRACTOR'S EMPLOYEES

The Contractor shall be responsible for the safety, adequacy, efficiency, and sufficiency of its employees.

If any person employed by the Contractor or its subcontractors, appear to the Construction Manager to be disorderly, disrespectful, rude, or intoxicated, such person shall be discharged from the site immediately by the Contractor.

GENERAL CONDITIONS

2.6.5 SUBCONTRACTORS

Subcontractors will not have a direct relationship with the City. The persons engaged in the Work, including employees of subcontractors, suppliers and service providers, will be considered employees of the Contractor. The Contractor will be responsible for their work and their work shall be subject to the provisions of the Contract. The Contractor is as fully responsible to the City for the acts and omissions of its subcontractors and of persons either directly or indirectly employed by them as the Contractor is for the acts and omissions of persons directly employed by the Contractor. Nothing contained in the Contract Documents shall create any Contractual relationship between any subcontractor and the City. References in the Contract Document to actions required of subcontractors, manufacturers, suppliers, or any party other than the Contractor, the City, the Construction Manager, or the Design Consultant shall be interpreted as requiring that the Contractor shall require such subcontractor, manufacturer, supplier, or party to perform the specified action, unless the Contract Documents specifically state that the Work is not included in the Contract.

The Contractor shall employ only subcontractors who are properly licensed in accordance with Nevada State Law. Changes to subcontractors listed in the Bid shall be made only with the approval of the City.

2.6.6 CONTRACTOR'S EQUIPMENT AND FACILITIES

The Contractor shall furnish and maintain in good condition all equipment and facilities as required for the proper execution and inspection of the Work. Such equipment and facilities shall meet all requirements of applicable ordinances and laws.

2.6.7 CITY-CONTRACTOR COORDINATION

A. Service of Notice

Notice, order, direction, request, or other communication given by the Construction Manager or City to the Contractor shall be deemed to be well and sufficiently given to the Contractor if delivered to the Contractor's Representative, or to the Contractor's address provided in the Bid Proposal.

B. Suggestions to Contractor

Plans or methods of work suggested by the City, the Construction Manager, or the Design Consultant to the Contractor, but not specified or required, if adopted or followed by the Contractor in whole or in part, shall be used at the risk and responsibility of the Contractor. The City, Construction Manager, or the Design Consultant assume no responsibility therefore, and in no way will be held liable for any defects in the Work which may result from or be caused by use of such suggested plan or method of work.

C. Cooperation

The Contractor shall conduct its operations so as to interfere as little as possible with those of other contractors or subcontractors on or near the Work. It is expressly understood that the City has the right and may award other contracts in connection with the Work so long as it does not unreasonably interfere with the Work under this Contract.

The Contractor shall afford the City, the Construction Manager and separate contractors reasonable opportunity for the introduction and storage of their materials and equipment and the execution of their work, and shall connect and coordinate the Work with the others as required by the Contract Documents.

If any part of the Contractor's Work depends for proper execution or results upon the Work of the City or any separate contractor, the Contractor shall, prior to proceeding with the Work, promptly report to the Construction Manager any apparent discrepancies or defects in such other work that render it unsuitable for such proper execution and results. Failure of the Contractor to so report shall constitute an acceptance of the City's or separate contractor's work as fit and proper to

GENERAL CONDITIONS

receive the Work, except as to latent defects which subsequently become apparent in such work by others.

If requested by the Contractor, the City shall arrange meetings with other contractors performing work on behalf of the City to plan coordination of construction activities. The City shall keep the Contractor informed of the planned activities of other contractors.

Where one contractor's operations are within the limits or adjoin the operations of another contractor, each shall be responsible to the other for any damage, injury, loss, or expense which may be suffered on account of interference of operations, neglect or failure to finish work at the proper time, or of any other cause.

Differences and conflicts arising between the Contractor and other contractors employed by the City or between the Contractor and the workers of the City with regard to their work shall be submitted to the Construction Manager for his/her decision in the matter. If such separate contractor files a claim against the City on account of any delay or damage alleged to have been caused by the Contractor, the City shall notify the Contractor who shall, at the City's election, defend such claims at the Contractor's expense. If any judgment or award against the City arises from any such claim whether defended by City or by Contractor, the Contractor shall pay or satisfy said judgment or award and shall reimburse the City for all fees, including attorneys' fees, and costs which the City has incurred or for which it is liable.

2.6.8 PERMITS

Unless specifically stated in the Special Conditions to be provided by the City, the Contractor shall apply for, obtain, and comply with all terms, conditions and requirements attached to all permits, licenses, and agreements required by federal, state, or local agencies to perform work, construct, erect, test and start up any equipment or facility for this Contract. The City will provide, at no cost to the Contractor, the City "Building Permit" and/or the City "Engineering Permit". Where operating permits are required, the Contractor shall apply for and obtain such operating permits in the name of the City and provide the permit in an appropriate file folder when the City accepts substantial completion of the equipment or facility. The Contractor shall give all notices necessary or incidental to the due and lawful prosecution of the Work.

The Contractor shall apply for and obtain in its name all necessary permits and shall be responsible for satisfying all code requirements, calling for inspections, and obtaining final approvals. Code inspections will be coordinated with the Construction Manager. The Contractor shall comply with all conditions stipulated in the permits. The Contractor shall include in its Bid the fees for any permits and inspections that are required.

The Contractor shall also apply for and obtain all safety permits for excavations, tunneling, trenches, construction (building structure, scaffolding, or false work) and demolition required by OSHA. Any permits, licenses, agreements, and fees therefore required for the performance of work under this Contract and not specifically mentioned herein as having been obtained and paid by the City shall be included in the Contractor's Bid price. The cost of inspections associated with complying with permits, licenses, and agreements are to be included in the bid price. No time extensions shall be granted for time lost due to violations of permits.

The Contractor shall submit copies of all required Permits to the Construction Manager prior to proceeding with the Work covered by the respective Permits. If copies of all required Permits are not submitted to the Construction Manager prior to proceeding with the Work covered by the respective Permits, the Construction Manager may suspend the Work on the entire project, without any additional time or compensation to the Contractor, until the copies of the Permits are received.

2.6.9 CONTRACTOR'S RESPONSIBILITY FOR THE WORK AND MATERIALS

Until final acceptance of the Work, the Contractor shall have the charge and care of the Work and of the materials to be used therein, the Contractor shall bear the risk of injury, loss, or damage to any part

GENERAL CONDITIONS

thereof (regardless of whether partial payments have been made on such damaged portions of the Work) by the action of the elements or from any other cause, whether or not arising from the non-execution of the Work. The Contractor shall rebuild, repair, restore, and make good all injuries, losses, or damages to any portion of the Work or the materials occasioned by any cause, before its completion and acceptance, and shall bear the expense thereof, except for such injuries, losses, or damages as are directly and proximately caused by acts of the City. Where necessary to protect the work or materials from damage, the Contractor shall, at his/her expense, provide suitable drainage and erect such temporary structures as are necessary to protect the work or materials from damage. The suspension of work or the granting of an extension of time from any cause whatever shall not relieve the Contractor of his/her responsibility for the work and materials as herein specified.

In an emergency affecting the safety of life or property, including adjoining property, the Contractor, without special instruction or authorization, is authorized to act at his/her discretion to prevent such threatened loss or injury.

2.6.10 SURVEYS, LINES AND GRADES

The Contractor shall be responsible for all construction surveying and the setting of all construction control stakes. All construction surveying must be performed by the designated Project Surveyor who shall be a Nevada Licensed Professional Land Surveyor, or the Surveyor's subordinates. Contractor shall provide the name, license number and contact information of the Project Surveyor to the Construction Manager prior to the start of Work.

The Contractor shall be responsible for directing the Project Surveyor to establish all the survey control staking to accomplish the Work within the tolerances established in the Technical Specifications and per the requirements of the Nevada Administrative Code, for Construction Surveys, Sections 625.760 through 625.780.

2.6.11 LAWS TO BE OBSERVED

The Contractor shall keep fully informed of existing and pending county, state, and national laws and regulations and all municipal ordinances and regulations of the City which in any manner affect those engaged or employed in the Work and of all such orders and decrees of bodies having any jurisdiction or authority over the same. The Contractor shall protect and indemnify the City and its officers, agents, employees, and volunteers against any claim or liability arising from or based on the violation of any such laws, ordinances, regulations or orders, whether by the Contractor or its employees. If any discrepancy or inconsistency is discovered in the drawings, specifications or Contract for the Work in relation to any such law, ordinance, regulations, order or decree, the Contractor shall immediately report the same to the Construction Manager in writing.

The Contractor shall comply with all Federal, State and local laws relative to conducting business in Carson City including, but not limited to, licensing, labor and health laws, and applicable NRS. The laws of the State of Nevada will govern as to the interpretation, validity and effect of the Bid, its award, and the Contract.

A. Certified Payrolls - If Prevailing Wage Rates are Required

The Contractor and each subcontractor shall keep an accurate payroll record, showing the name, address, work classification, straight time, and overtime hours worked each day and week, and the actual per diem wages paid to each journeyman, apprentice, worker, or other employee employed in connection with the Project.

The payroll records shall be certified and shall be submitted weekly to the Construction Manager. Submission of the certified payrolls shall be a condition precedent for processing the monthly progress payment. The General Contractor shall collect the wage reports from the Sub-Contractors and ensure the receipt of a certified copy of each weekly payroll for submission to the City as one complete package.

GENERAL CONDITIONS

Pursuant to NRS 338.060 and 338.070, the Contractor hereby agrees to forfeit, as a penalty to the City, not less than Twenty Dollars (\$20) nor more than Fifty Dollars (\$50) for each calendar day or portion thereof that each worker employed on the Contract is paid less than the designated rate for any work done under the Contract, by the Contractor or any subcontractor under him/her, or is not reported to the City as required by NRS 338.070.

2.6.12 SAFETY

A. Contractor's Safety Responsibility

The Contractor shall be solely and completely responsible for conditions of the job site, including safety of all persons and property during performance of the Work. This requirement shall apply continuously and not be limited to normal working hours. Safety provisions shall conform to U.S. Department of Labor (OSHA) Standards, the Nevada Occupational Safety and Health Act, and all other applicable Federal, State, County, and local laws, ordinances, codes, the requirements set forth below, and any regulations that may be detailed in other parts of these Contract Documents. Where any of these are in conflict, the more stringent requirement shall be followed.

No provision of the Contract Documents shall act to make the City, the Construction Manager or any party other than the Contractor responsible for safety. The Construction Manager shall not have authority for safety on the Project. The Contractor shall indemnify, defend (not excluding the City's right to participate) and hold harmless the City, Construction Manager, or other authorized representatives of the City, from and against any and all actions, damages, fines, suits, and losses arising from the Contractor's failure to meet all safety requirements and/or provide a safe work site.

If death or serious injuries or serious damages are caused, the accident shall be reported immediately to the Construction Manager, the City and OSHA. In addition, the Contractor must promptly report in writing to the Construction Manager all accidents whatsoever arising out of, or in connection with, the performance of the Work whether on, or adjacent to, the site giving full details and statements of witnesses. The Contractor shall make all reports as are, or may be, required by any authority having jurisdiction, and permit all safety inspections of the Work being performed under this Contract.

If a claim is made by anyone against the Contractor or any subcontractor on account of any accident, the Contractor shall promptly report the facts in writing to the Construction Manager, giving full details of the claim.

B. Safety Program

The Contractor shall establish, implement, and maintain a written injury prevention program. Before beginning the Work, the Contractor shall prepare and submit to the Construction Manager a Safety Program that provides for the implementation of all of the Contractor's safety responsibilities in connection with the Work at the site and the coordination of that program and its associated procedures and precautions with safety precautions and procedures of each of its subcontractors. The Contractor shall be solely responsible for initiating, maintaining, monitoring, coordinating, and supervising all safety programs, precautions, and procedures in connection with the Work and for coordinating its programs, precautions, and procedures of any other prime Contractors and subcontractors performing work at the site.

C. Safety Supervisor

The Contractor shall appoint an employee as Safety Supervisor who is qualified and authorized to supervise and enforce compliance with the Safety Program. The Contractor shall notify the Construction Manager in writing prior to the commencement of work of the name of the person who will act as the Contractor's Safety Supervisor.

GENERAL CONDITIONS

D. Excavation Safety

The Contractor shall submit, in advance of excavation five feet or more in depth, detailed plans showing the design of shoring, bracing, sloping, or other provisions to be made for worker protection from hazard of caving ground during such excavation, and protection to adjacent structures during such excavation. Design calculations and plans must be sealed by a Civil or Structural Engineer registered in the State of Nevada.

Prior to commencing any excavation, the Contractor shall designate in writing to the Construction Manager the "Competent Person(s)" with the authority and responsibilities designated in the Construction Safety Orders.

E. Emergencies

In emergencies affecting the safety or protection of persons, the Work, or property at the site or adjacent thereto, the Contractor, without special instruction or authorization from the Construction Manager, is obligated to act to prevent threatened damage, injury or loss. The Contractor shall give the Construction Manager prompt notice if the Contractor believes that any changes in the Work or variations from the Contract Documents have been caused thereby. The Contractor shall not resume construction during an emergency, or after an emergency until directed to by the Construction Manager.

F. Safety Violations

The City shall have the authority to require the removal from the Project of any employee in responsible charge of the Work where safety violations occur.

2.6.13 FIRE PREVENTION AND CONTROL

Before setting any fires whatsoever, the Contractor shall notify the responsible Federal, State, or local agency having jurisdiction for the area concerned. The Contractor shall abide by such rules and instructions as to fire prevention and control and as to the place for burning as the Federal, State, or local agency having jurisdiction may prescribe. The Contractor shall take all necessary steps to prevent his/her employees from setting fires not required in the prosecution of the work. The Contractor shall be responsible for preventing the escape of fires set in connection with the work and shall under the direction of the appropriate agency, or, in the absence of an officer from any such agency, acting independently, extinguish all fires which may escape the work, whether or not set directly or indirectly as a result of his/her operations.

The Contractor shall be fully responsible for any damage caused to public and/or private property as a result of his/her burning operations, and shall leave no fires unattended at any time during these operations. He/She shall have available at the site at all times when burning is in progress, adequate equipment to extinguish the fires set by him/her, and to control the spread of fire outside of the burning areas. Burning during high wind conditions shall be expressly prohibited in order to prevent fire hazard, regardless of the prevailing season.

2.6.14 ERRORS OR DISCREPANCIES NOTED BY CONTRACTOR

It is the duty of the Contractor to promptly notify the Construction Manager in writing of any design, materials, or specified method that the Contractor believes may prove defective or insufficient. If the Contractor believes that a defect or insufficiency exists in design, materials, or specified method and fails to promptly notify the Construction Manager in writing of this belief, the Contractor waives any right to assert that defect or insufficiency in design, materials, or specified method at any later date in any legal or equitable proceeding against the City, or in any subsequent arbitration or settlement conference between the City and the Contractor.

The Construction Manager, on receipt of any such notice, will promptly investigate the circumstances and give appropriate instructions to the Contractor. Until such instructions are given, any work done by the Contractor after he/she comes to the belief that a defect or insufficiency exists in materials, or specified method which is directly or indirectly affected by such alleged defect or insufficiency in design, materials, or specified method will be at his/her own risk and he/she shall bear all costs arising therefrom.

GENERAL CONDITIONS

If the Contractor, either before commencing work or in the course of the work, finds any discrepancy between the specifications and the plans or between either of them and the physical conditions at the site of the work or finds any error or omission in any of the plans or in any survey, he/she shall promptly notify the Construction Manager of such discrepancy, error, or omission. If the Contractor observes that any plans or specifications are at variance with any applicable law, ordinance, regulation, order, or decree, he/she shall promptly notify the Construction Manager in writing of such conflict. The Construction Manager, on receipt of any such notice, will promptly investigate the circumstances and give appropriate instructions to the Contractor. Until such instructions are given, any work done by the Contractor after his/her discovery of such error, discrepancy, or conflict will be at his/her own risk and he/she shall bear all costs arising therefrom.

2.6.15 INDEMNIFICATION

The Contractor hereby agrees to indemnify, hold harmless, and defend, not excluding the City's right to participate, the Construction Manager, the City and its elected officials, officers, employees, agents, volunteers, other retained consultants and representatives, from and against any and all liability, claims, actions, damages, legal or administrative proceedings, losses and expenses, including without limitations, reasonable attorney's fees and costs (including attorney's fees in establishing indemnification of whatsoever nature), litigation costs, penalties, fines, judgments, or decrees by reason of any death, injury or disability to or of any person and/or damages to any property or business, including loss of use, arising out of any alleged negligent or willful acts, errors or omissions of the Contractor, Contractor's employees, agents, or subcontractors arising out of or suffered, directly or indirectly, by reason of or in connection with the performance of the Work under this Contract.

The Contractor guarantees the payment of all claims for materials, supplies and labor, and all other claims against it or any subcontractor, made in connection with this Agreement.

2.6.16 INSPECTIONS

The right of inspection and acceptance or rejection of contracted work by the City shall not make the Contractor an agent of the City, and the liability of the Contractor for all damages to persons or to public or private property, arising from the Contractor's execution of the work, shall not be lessened because of such inspections.

2.6.17 CONTRACTOR IS AN INDEPENDENT CONTRACTOR

This Contract does not create an employee/employer relationship between the parties. It is the parties' intention that the Contractor will be an independent contractor and not Carson City's employee for all purposes, including but not limited to the application of the Fair Labor Standards Act, the Federal Unemployment Tax Act, the provisions of the Internal Revenue Code, and Nevada State revenue and taxation laws. The Contractor will retain sole and absolute discretion in the judgment of the manner and means of carrying out the Contractor's activities and responsibilities hereunder. The Contractor agrees that it is a separate and independent enterprise from the public employer, that it has full opportunity to find other business, that it has made its own investment in its business and that it will utilize industry standard of care necessary to perform the Work. This Contract shall not be construed as creating any joint employment relationship between the Contractor and the City, and the City will not be liable for any obligation incurred by the Contractor, including but not limited to unpaid minimum wages and/or overtime premiums.

2.6.18 VALUE ENGINEERING PROPOSALS

Value Engineering Proposals (VEP) may be submitted by the Contractor in writing for modifying the plans, specifications or other requirements of the Contract for the purpose of reducing the total cost of construction without reducing design capacity or quality of the finished product. If accepted, net savings resulting from a VEP will be shared by the City and the Contractor on a 50%-50% basis.

GENERAL CONDITIONS

The requirements herein apply to all VEP's initiated and developed by the Contractor and which are identified as such at the time of submission. Nothing herein shall be construed as requiring consideration or approval of a VEP submitted hereunder.

Each VEP shall result in a net savings over the Contract costs without impairing essential functions and characteristics of the item(s) or of any other part of the project, including but not limited to environmental considerations, service life, reliability, economy of operation, ease of maintenance, desired aesthetics and safety.

Submit the following information with each VEP:

- 5) A statement that the proposal is submitted as a VEP;
- 6) A statement concerning the basis for the VEP and benefits to the City together with an itemization of the Contract requirements affected by the VEP;
- 7) A detailed estimate of the cost under the existing Contract and under the VEP;
- 8) Proposed specifications and recommendations as to how such VEP changes are to be accomplished; and
- 9) A statement as to the time by which a Contract Change Order adopting the VEP must be issued so as to obtain the maximum cost effectiveness.

The VEP will be processed in the same manner as prescribed for any other proposal which would necessitate issuance of a Contract Change Order. The City may accept in whole or in part any VEP by issuing a Contract Change Order which will identify the VEP on which it is based. The City will not be liable for failure to accept or act upon any VEP submitted pursuant to these requirements nor for any delays to the work attributable to any such proposal. Until a proposal is effected by Contract Change Order, Contractor remains obligated to perform under the terms and conditions of the Contract. If an executed Contract Change Order has not been issued by the date upon which the proposal specifies that a decision thereon should be made, or such date as the Contractor may have subsequently specified in writing, such proposal shall be deemed rejected.

The Contract Change Order effecting the necessary Contract modification will establish the net savings agreed upon, will provide for adjustment in the Contract prices and will indicate the new savings to be equally divided between the City and the Contractor. Contractor shall absorb all costs incurred in preparing a VEP for submission. All reasonably incurred costs of reviewing and administering the VEP will be borne by the City. The City reserves the right to include in the agreement any conditions it deems appropriate for consideration, approval, and implementation of the proposal. The Contractor's 50% share of the net savings shall constitute full compensation to him/her for effecting all changes pursuant to the agreement.

Acceptance of the VEP and performance of the work thereunder will not change the Contract time limit as a result of the VEP, unless specifically provided for in the Contract Change Order authorizing the VEP.

Proposed changes in the basic design of a bridge or pavement type, traffic control plan, or changes which require different right-of-way limits, will not normally be considered as an acceptable VEP.

The Construction Manager shall be the sole judge of the acceptability of a VEP.

Subject to the provisions contained herein, the City or any other public agency shall have the right to use all or part of any accepted VEP without obligation or compensation of any kind to the Contractor.

GENERAL CONDITIONS

In the event a VEP is accepted by the City, the provisions of General Conditions Section 6.4.4, Unit Price Adjustments Due to Increased or Decreased Quantities, which pertain to adjustment of Contract unit prices due to alterations of Contract quantities, will not apply to items adjusted or deleted as a result of effecting the VEP by Contract Change Order.

SECTION 3.0 PROGRESS OF WORK, MEETINGS, SCHEDULES

GC 3.1 BEGINNING OF WORK

The Contractor shall begin work within ten (10) calendar days of the effective date of the Notice to Proceed and shall diligently prosecute the same to completion within the Contract Time.

GC 3.2 PERFORMANCE OF THE WORK

Unless otherwise specified in the Special Conditions, the Contractor shall furnish all materials, labor, permits, tools, equipment, water, light, power, transportation, superintendence, temporary construction of every nature, and incidentals, including but not limited to, dust and traffic control measures, and to perform all work involved in executing the Contract in a satisfactory and workmanlike manner within the time specified.

GC 3.3 PLANS AND SPECIFICATIONS FURNISHED BY THE CITY

The City will furnish to the Contractor, free of charge, up to five (5) copies of the contract drawing and specifications. Additional sets shall be provided by the City at cost of the City's standard billing rate for labor of reproduction and the cost of reproduction itself. The five (5) sets of plans and specifications shall be available to the Contractor at the time he/she takes out the Carson City permit at the City's One Stop Permit Center located at the Building Department, 2621 Northgate Lane, Suite 6.

The location of the Work, its general nature and extent, and the form and detail of the various features are shown on the Contract Drawings accompanying and made a part of these Contract Documents.

GC 3.4 ORDER OF WORK

When required by the Contract Documents, the Contractor shall follow the sequence of operations as set forth therein. Full compensation for conforming with such requirements will be considered as included in the prices paid for the various Contract items of work and no additional compensation will be allowed therefore.

GC 3.5 TIME OF COMPLETION

Time shall be of the essence of the Contract. The Contractor shall diligently prosecute the Work so that the various portions of the Project shall be complete and ready for use within the time specified. It is expressly understood and agreed by and between the Contractor and the City that the Contract Time for completion of the Work described herein is a reasonable time taking into consideration the average climatic and economic conditions and other factors prevailing in the locality and the nature of the Work.

Failure of the Contractor to perform any covenant or condition contained in the Contract Documents within the time period specified shall constitute a material breach of this Contract entitling the City to terminate the Contract unless the Contractor applies for, and receives, an extension of time in accordance with the procedures set forth in GC 3.15, EXTENSION OF TIME.

Failure of the City to insist upon performance of any covenant or condition within the time period specified in the Contract Documents shall not constitute a waiver of the Contractor's duty to complete the performance within the designated periods unless the City has given a waiver in writing.

The City's agreement to waive a specific time provision or to extend the time for performance shall not constitute a waiver of any other time provision contained in the Contract Documents. Failure of the Contractor to complete the performance promptly within any additional time authorized or in any waiver or extension of time shall constitute a material breach of this Contract entitling the City to terminate.

GC 3.6 MEANS AND METHODS

GENERAL CONDITIONS

It is expressly stipulated that the drawings, specifications, and other contract documents set forth the requirements as to the nature of the completed Work and do not purport to control the method of performing work except in those instances where the nature of the completed Work is dependent upon the method of performance.

Neither the City, Design Consultant, nor the Construction Manager will be responsible for or have control or charge of construction means, methods, techniques, sequences or procedures, or for safety precautions and programs in connection with the Work. Neither the City, Design Consultant nor the Construction Manager will be responsible for or have control or charge over the acts or omissions of the Contractor, or any of their subcontractors, agents or employees, or any other persons performing any of the Work. Any general control of the Work exercised by the City or its authorized representatives shall not make the Contractor an agent of the City, and the liability of the Contractor for all damages to persons and/or to public or private property arising from the Contractor's execution of the Work shall not be lessened because of such general control.

Neither the inspection by the City, Design Consultant, or Construction Manager, nor any order, measurement, approved modification, or payment of monies, nor acceptance of any part or whole of the Work by the City, Design Consultant, Construction Manager, or their agents shall operate as a waiver of any provision of the Contract.

GC 3.7 CITY-FURNISHED MATERIALS

Only materials and equipment specifically indicated in the Contract Documents shall be furnished by the City and such materials and equipment will be made available as designated in the Special Conditions. The Contractor shall be prepared to load or unload and to properly protect all such material and equipment from damage or loss. The cost of loading, unloading, hauling, handling, demurrage and storage, and placing City-furnished materials into the Work shall be considered as included in the price bid for the Contract item involving such City-furnished material.

Contractor shall inspect and assure itself of the amount and soundness of such material or equipment at the time of receiving such materials. Any City-furnished material or equipment lost or damaged from any cause after the Contractor has taken control of said material or equipment, shall be replaced by the Contractor at his/her expense.

GC 3.8 DEFECTIVE AND UNAUTHORIZED WORK

Any materials or workmanship which does not conform to the requirements of the Contract Documents shall be considered defective and shall be remedied or removed and replaced by the Contractor, together with any other work which may be displaced in so doing, and no additional compensation will be allowed to the Contractor for such removal, replacement, or remedial work. All nonconforming materials shall be immediately removed from the Site.

Any work done beyond the limits of work, lines, and grades shown on any approved plans or established by the Construction Manager, or any changes in, additions to, or deductions from the work done without written authority, will be considered as unauthorized and will not be paid. Work so done may be ordered remedied, removed, or replaced at the Contractor's expense.

Upon failure on the part of the Contractor to comply with any order of the Engineer made under the provisions of this Section, the Engineer shall have authority to cause nonconforming materials, rejected work, or unauthorized work to be remedied, removed, or replaced at the Contractor's expense and to deduct the costs from any monies due or to become due the Contractor.

These provisions shall have full effect regardless of the fact that the defective work may have been done or the defective materials used with the full knowledge of the Engineer or his/her representative. The fact that the Engineer may have previously overlooked such defective work shall not constitute an acceptance of any part of it. Nothing stated herein shall be deemed to shorten the term of any statute of limitations applicable to claims which the City may have against the Contractor.

GC 3.9 PRE-CONSTRUCTION CONFERENCE

GENERAL CONDITIONS

The Construction Manager will schedule a Pre-Construction Conference at the Project site or other established location at the time of Notice to Proceed and/or execution of the Contract and prior to commencement of construction activities.

3.9.1 ATTENDEES

The City, Design Consultant, Construction Manager, Contractor and its superintendent, subcontractors, and other concerned parties shall each be represented at the conference by persons familiar with and authorized to conclude matters relating to the Work.

3.9.2 AGENDA

The Construction Manager will prepare an agenda for discussion of significant items relative to Contract requirements, procedures, coordination and construction. Minutes shall be kept by the Construction Manager and distributed to all attendees.

GC 3.10 PROGRESS MEETINGS

The Construction Manager will conduct progress meetings at the Project site or other established location at regularly scheduled intervals which may be as frequent as weekly. Frequency of meetings shall be determined at the Pre-Construction Conference. Meeting minutes will be taken and distributed by the Construction Manager.

3.10.1 ATTENDEES

The City, Design Consultant, Construction Manager, Contractor, and its superintendent may each be represented at these meetings. Attendance by subcontractors, suppliers, utilities and other entities is subject to issues and/or items of the agenda which may require attendance.

3.10.2 AGENDA

Agenda may include, but not necessarily be limited to: review, correct or approve minutes of the previous progress meeting, review of items of significance that could affect progress, review/discuss topics as appropriate to the current and future status and/or needs of the Project, review the progress of the Work in the preceding week and in the subsequent week, coordinate the Work with public agencies and/or other Contractors as required, and allow the Construction Manager to plan his/her activities for testing, inspection, etc.

GC 3.11 CONSTRUCTION SCHEDULES

Construction schedules are required for all Contracts. The type of construction schedule required, that is, Construction Schedule (A) or Construction Schedule (B) will be specified in the Special Conditions. Compensation for the Work under this item will be included within the other bid items.

3.11.1 CONSTRUCTION SCHEDULE (A)

A. General

The schedule shall be submitted at the Pre-Construction Conference and must be favorably reviewed by the Construction Manager and the City before the first partial payment can be made. NOTE: The Construction Schedule must include and account for the total contract time specified in the Contract Documents.

B. Base Schedule

The Contractor shall submit the schedule based on either the bar chart method or the Critical Path Method (CPM). The schedule shall indicate preceding activity relationships and/or restraints where applicable and a controlling path shall be indicated. The schedule shall be time-scaled and shall be drafted to show a continuous flow from left to right. The construction schedule shall clearly show the sequence of construction operations and specifically list:

1. The start and completion dates of primary work items or components.

GENERAL CONDITIONS

2. The dates of submittals, procurement, delivery, installation and completion of each major equipment and material requirement.
3. Progress milestone events or other significant stages of completion.
4. The lead time required for testing, inspection and other procedures required prior to acceptance of the Work.
5. All activities, other than procurement activities, shall be cost-loaded. Activities shall be no longer than 14 calendar days, except for submittals and delivery items. If an activity takes longer, it shall be broken into appropriate segments of work for measurement of progress. This limitation may be waived, upon approval of the Construction Manager, for repetitious activities of longer durations for which progress can be easily monitored.

C. Reports

The Bar Charts or CPM Schedules shall be prepared as follows:

1. Bar Chart: A manually generated report which lists each primary activity description, early start and finish dates, and all preceding and succeeding activities. Report shall indicate all critical activities. A report with the above information shall be provided with each monthly update.
2. CPM Schedule: A CPM network report sorted by I-J or activity number which lists each activity description, early start and finish dates, preceding and succeeding activities and restraints, including lead/lag durations. The report shall show the critical path.
 - § CPM network report sorted by total float.
 - § CPM network report sorted by early start.

3.11.2 CONSTRUCTION SCHEDULE (B)

A. General

The Construction Schedule under this requirement will also be referred to as the CPM Schedule.

The Contractor shall designate, in writing, an authorized representative in its firm who will be responsible for the preparation, revising, and updating of the CPM Schedule. The Contractor's representative shall have direct Project control and complete authority to act on behalf of the Contractor in fulfilling the construction scheduling requirements set forth herein, and such authority will not be interrupted throughout the duration of the Project. The requirements for the CPM Schedule are included to assure adequate planning and execution of the Work and to assist the Construction Manager and the City in appraising the reasonableness of the proposed schedule and evaluating progress of the Work.

Within seven (7) days from award of the Contract, the Contractor shall submit to the Construction Manager demonstration of competence in the use of CPM Scheduling, including evidence of the use of CPM Scheduling on a project of similar value and complexity. In the event of the failure of the Contractor to satisfy the Construction Manager of its CPM Scheduling competence, the Contractor will be required to employ a qualified CPM consultant who regularly performs these services and who in the opinion of the Construction Manager possesses the qualifications required to perform CPM Scheduling for this Project.

B. Preliminary Construction Schedule

GENERAL CONDITIONS

At the Pre-Construction Conference, the Contractor shall submit copies of a Preliminary Construction Schedule in the form of a precedence diagram covering the following Project phases and activities:

1. Procurement and Submittals, including shop drawings, fabrication, and delivery of key and long lead time procurement activities.
 - a. The Contractor's submittal information shall show intended submittal dates and shall be incorporated into the base project schedule.
 - b. The delivery information shall include realistic delivery dates for the procurement activities.
2. The activities planned for the first 90 days in the execution of the Work.
3. The approach to scheduling the remaining activities or phases of the Work. The Work for each phase or activity shall be represented by at least one summary activity and the sum of the summary activities shall equal the Contract Time.
4. Approximate cost and duration for each summary activity representing the Contractor's best estimate for the Work the summary activity represents.
5. Projected monthly cash flow.

C. Base Schedule Submittal

The Contractor shall submit an acceptable Critical Path Method (CPM) Schedule to the Construction Manager within thirty (30) days after the receipt of the Notice to Proceed. Subsequent revisions to said schedule shall be submitted as set forth hereinafter.

The Construction Manager shall review the schedule and provide any comments, its favorable review of the schedule, or request a meeting to review the schedule with the Contractor within fifteen (15) days of receipt of the schedule. If requested, the Contractor shall participate in a review and evaluation of the proposed network diagrams and analysis by the Construction Manager. Any revisions necessary as a result of this review shall be resubmitted for review by the Construction Manager within ten (10) days. When completed, the favorably reviewed schedule shall then be the schedule to be used by the Contractor for planning, organizing, and directing the Work, and for reporting progress. If the Contractor thereafter desires to make significant changes in its method of operating and scheduling, the Contractor shall notify the Construction Manager in writing stating the reasons for the change. Only one progress payment will be made prior to acceptance of the CPM Schedule. Neither the Contractor nor the City shall own the "float".

To the extent that the favorably reviewed initial Construction Schedule, or revisions thereto, indicate anything not jointly agreed upon, it shall be deemed to be not favorably reviewed by the Construction Manager. Any omission of work from the detailed schedule, otherwise required for Contract compliance, will not excuse the Contractor from completing such work within any applicable completion date.

The CPM Schedule shall utilize a (CPM) format using either the precedence or arrow diagramming method. The schedule shall show completion of the Project at the Contract Completion Date or before.

The schedule shall be computer generated utilizing a scheduling program identified in the Special Conditions. The Contractor shall provide a compact disk or other electronic means approved by the Construction Manager for the initial base schedule and all monthly updates with the network

GENERAL CONDITIONS

diagram and mathematical analyses. The program shall be capable of accepting revised completion dates as modified by approved time adjustments and re-computations of all tabulation date and float accordingly. The CPM schedule system shall consist of diagrams and accompanying mathematical analyses network diagram. See Special Conditions for further details regarding scheduling requirements.

D. Cash Flow Projection

A cash flow projection shall be submitted with the Construction Schedule. This cash flow projection shall be revised and resubmitted when revisions of the Construction Schedule will result in significant changes to the projected cash flow.

GC 3.12 NOTICE OF DELAYS

When the Contractor foresees a delay in the prosecution of the Work and, in any event, within seventy-two (72) hours of a delay, the Contractor shall notify the Construction Manager in writing of the probability of the occurrence, the estimated or actual extent of the delay, and its cause. The Contractor shall take immediate steps to prevent, if possible, the occurrence or continuance of the delay. The Contractor agrees that no claim shall be made for delays which are not called to the attention of the Construction Manager within the time specified above.

Except for Standby Time for City utilities as provided for in GC 7.10, COORDINATION/COOPERATION WITH UTILITIES, the Contractor's sole remedy for any delay in the Work, regardless of the alleged cause of the delay, shall be an extension of the contract time; the Contractor shall not be entitled to any delay damages, wage escalation, material escalation, extended job site or home office overhead or supervision, or additional compensation of any kind.

3.12.1 NON-EXCUSABLE DELAYS

Non-excusable delays in the prosecution of the Work shall include delays which could have been avoided by the exercise of care, prudence, foresight, and diligence on the part of the Contractor or its subcontractors, at any tier level, or suppliers. Time lost due to violations of permit requirements shall be non-excusable delays. No time extension or other compensation shall be granted for time lost due to non-excusable delays.

3.12.2 EXCUSABLE DELAYS

Excusable delays in the prosecution or completion of the Work shall include delays which result from causes beyond the control of the Contractor and which could not have been avoided by the exercise of care, prudence, foresight, and diligence on the part of the Contractor or its subcontractors, at any tier level, or suppliers.

Delays caused by acts of God, fire, unusual storms, floods, earthquakes, strikes, labor disputes, freight embargoes, and shortages of materials shall be considered as excusable delays insofar as they prevent the Contractor from proceeding with at least seventy-five (75) percent of the normal labor and equipment force for at least five (5) hours per day toward completion of the current critical activity item(s) on the latest favorably reviewed Construction Schedule.

Excusable delays shall not entitle the Contractor to any additional compensation. The sole remedy of the Contractor shall be to seek an extension of time.

3.12.3 STANDBY TIME

As provided in GC 7.10, COORDINATION/COOPERATION WITH UTILITIES, if the Contractor is delayed due to the City's non-marking, mis-marking or mis-locating the City's main line water mains, reclaimed water mains, sanitary sewer main lines and storm drains, the City will be responsible for repairs, damages and standby time caused the Contractor. Compensation to the Contractor for such repairs, damages or standby time shall be calculated on the basis of GC 6.4.3, FORCE ACCOUNT PAYMENT. Note: this provision does not apply to service laterals/connections.

GENERAL CONDITIONS

Also Note: per NRS 455.082, the approximate location of a subsurface installation marked in response to a request of USA means a strip of land not more than 24 inches on either side of the exterior surface of a subsurface installation.

3.12.4 WEATHER DELAYS

Should inclement weather conditions or the conditions resulting from weather prevent the Contractor from proceeding with seventy-five (75) percent of the normal labor and equipment force engaged in the current critical activity item(s) on the latest favorably reviewed Construction Schedule for a period of at least five (5) hours per day toward completion of such operation or operations, and the crew is dismissed as a result thereof, it shall be a weather delay day. The Contractor may be granted a non-compensable time extension should the critical path activities be affected by the weather delay.

3.12.5 CONCURRENT DELAYS

Concurrent delays are those delay periods when the prosecution of the Work is delayed during the same period of time due to causes from a combination of the delays, City-caused and Contractor-caused. Time extensions will be granted on the basis of a time impact analysis from the CPM Schedule.

GC 3.13 LIQUIDATED DAMAGES

It is agreed by the parties to the Contract that time is of the essence in the completion of this Work, and that in case all the Work called for under the Contract is not completed before or upon the expiration of the time limit as set forth in these Contract Documents, or as modified by extensions of time granted by the City, damage will be sustained by the City. As it may be impracticable to determine the actual delay damage; it is, therefore, agreed that the Contractor shall pay liquidated damages to the City in the amount set forth in the Construction Contract, per calendar day for each and every calendar day's delay beyond the time prescribed to complete the Work. The Contractor agrees to pay such liquidated damages and in case the same are not paid, agrees that the City may deduct the amount thereof from any monies due or that may become due the Contractor under the Contract.

The Contractor shall not be deemed in breach of this Contract nor shall liquidated damages be collected because of any delays in the completion of the Work due to unforeseeable causes beyond the control and without the fault or negligence of the Contractor provided the Contractor requests an extension of time in accordance with the procedures set forth in GC 3.15, EXTENSION OF TIME. Unforeseeable causes of delay beyond the control of the Contractor shall include Acts of God, acts of a public enemy, acts of government, or acts of the City, fires, floods, epidemics, quarantine restrictions, strikes, freight embargoes, and weather, or delays of subcontractors due to such causes, or delays caused by failure of the City or the facilities.

GC 3.14 RIGHTS BEYOND LIQUIDATED DAMAGES

Liquidated damages shall not preclude the City from claiming and collecting damages on account of delay, price changes, loss of other contracts, loss of income, and or any inability of the City to fulfill other obligations, if such damages are direct or consequential arising out of the failure of the Contractor to perform under the terms, conditions and requirements of this Contract.

GC 3.15 EXTENSION OF TIME

The time specified for completion of all of the Work or any part of the Work may be extended only by a written change order executed by the City. The Construction Manager may, at his/her discretion, recommend that the City extend the time for completion of the Work without invalidating any of the provisions of the contract and without releasing the surety.

Extensions of time, when recommended by the Construction Manager, will be based upon the effect of delays to the project as a whole and will not be recommended for non-controlling delays to minor portions of the Work, unless it can be shown that such delays did, in fact, delay progress of the project as a whole. Excusable delays may justify an extension of time.

No extension of time for completion will be allowed for non-excusable delays.

GENERAL CONDITIONS

Written requests for an extension of time must be delivered to the Construction Manager within seventy-two (72) hours following the date of the occurrence which caused the delay. The request must state the cause of the delay, the date of the occurrence causing the delay, and the amount of additional time requested. The delay causing condition must affect an activity on the critical path of the latest favorably reviewed Construction Schedule. Requests for extensions of time shall be supported by all evidence reasonably available or known to the Contractor which would support the extension of time requested. Requests for extension of time failing to include the information specified in this Section, and requests for extensions of time which are not received within the time specified above, shall result in the forfeiture of the Contractor's right to receive any extension of time requested.

If the Contractor is requesting an extension of time because of a weather delay, Contractor shall supply daily reports to the Construction Manager describing such weather and the work which could not be performed that day because of such weather or conditions resulting therefrom and which Contractor otherwise would have performed. The City's acceptance of the daily reports shall not be deemed an admission of the Contractor's right to receive an extension of time or a waiver of the City's right to strictly enforce the time provisions contained in the Contract Documents.

When the Contractor has submitted a request for an extension of time in accordance with the procedures of this Section, the City will ascertain the facts and extent of the delay and extend the time for completing the Work if, in its judgment, the findings of fact justify such an extension, and its findings of fact thereon shall be final and conclusive. An extension of time may be granted by the City after the expiration of the time originally fixed in the Contract or as previously extended, and the extension so granted shall be deemed to commence and be effective from the date of such expiration.

GC 3.16 TEMPORARY SUSPENSION OF WORK

The City may order suspension of all or any part of the Work if:

- (1) Unsuitable weather and such other conditions beyond the control of the Contractor prevent satisfactory and timely performance of the Work; or
- (2) The contractor does not comply with the Contract or the Engineer's orders.

If the Work is suspended for reason (1) above, the period of work stoppage will be counted as non-working days. However, if the Construction Manager believes the Contractor should have completed the suspended work before the suspension, all or part of the suspension period may be counted as working days. The Construction Manager will set the number of non-working days (or parts of days) by deciding how long the suspension delayed the entire project. An extension of time may be granted. Also, the Contractor will be compensated for its actual costs plus the standard markup for overhead and profit for performing all work necessary to provide a safe, smooth, unobstructed passageway through the Site for use by the public, pedestrian and vehicular traffic during the period of such a suspension of work.

If the Work is suspended for reason (2) above, the period of work stoppage will be counted as working days and no extension of time will be granted. The lost work time, however, shall not relieve the Contractor from any contract responsibility.

If the Contractor fails to correct defective work as required, or fails to carry out the Work in accordance with the Contract Documents or any other applicable rules and regulations, the City, in writing, may order the Contractor to stop the Work, or any portion thereof, until the cause for such order has been eliminated; however, this right of the City to stop the Work shall not give rise to any duty on the part of the City to exercise this right for the benefit of the Contractor or any other person or entity. All delays in the Work occasioned by such stoppage shall not relieve the Contractor of any duty to perform the Work or serve to extend the time for the Work completion. Any and all necessary corrective work done in order to comply with the Contract Documents shall be performed at no cost to the City. When ordered by the City to suspend or resume work, the Contractor shall do so immediately. In all cases of suspension of construction operations, the work shall not again be resumed until permitted by written order of the City.

GENERAL CONDITIONS

In the event that a suspension of Work is ordered for reason (2) above, as provided in this Section, the Contractor shall perform all work necessary to provide a safe, smooth, and unobstructed passageway through the Site for use by public, pedestrian and vehicular traffic, during the period of such a suspension. Should the Contractor fail to perform the Work as specified, the City may perform such work and the cost thereof may be deducted from monies due the Contractor under the Contract. The Contractor will be responsible for all damage to the Work that may occur during suspensions of work. The Contractor will not be entitled to any additional compensation nor allowance for overhead or profit incurred in connection with this type of suspension.

GC 3.17 PROTECTION OF ANTIQUITIES

State and Federal laws pertaining to the protection and preservation of sites or objects of archeological, paleontological or historic interest shall be observed by the Contractor performing this Work.

When features of archeological, paleontological or historic interest are encountered or unearthed in material pits, the roadway prism, or other excavation, the Contractor shall stop work in the immediate vicinity of such feature, protect it from damage or disturbance, and report promptly to the State Historic Preservation Office at (775) 684-3448 and the Construction Manager.

Work shall not be resumed in the immediate area until the Contractor is advised by the authorities having jurisdiction that study or removal of the feature or features has been completed. The Contractor may be allowed an appropriate contract extension of time, as provided for in these General Conditions, for construction time lost.

GC 3.18 CONTRACT TERMINATION

If at any time the Contractor is determined to be in material breach of the Contract, notice thereof in writing will be served upon the Contractor and its sureties, and should the Contractor neglect or refuse to promptly provide means for satisfactory compliance with the Contract, within the time specified in such notice, the City in such case shall have the authority to terminate the operation of the Contract.

- A. The City may terminate the Contract if the Contractor:
 - 1. Fails to maintain bonding, Nevada State Contractor's Board License, State Industrial Insurance requirements or insurance policies for limits as defined in the Contract Documents;
 - 2. Persistently or repeatedly refuses or fails to supply properly skilled workers or proper materials;
 - 3. Fails to make payment to subcontractors for materials or labor in accordance with the respective agreements between the Contractor and the subcontractors;
 - 4. Persistently disregards laws, ordinances, or rules, regulations or order of a public authority having jurisdiction;
 - 5. Otherwise makes a material breach of a provision of the Contract Documents; or
 - 6. Contractor fails to maintain safe working conditions.

- B. When any of the above reasons exist, the City may provide, without prejudice to any other rights or remedies of the City and after giving the Contractor and the Contractor's Surety, seven (7) days written notice, terminate employment of the Contractor and may, subject to any prior rights of the surety:
 - 1. Take possession of the site and of all materials, equipment, tools and construction equipment and machinery thereon owned by the Contractor;
 - 2. Accept assignment of subcontractors pursuant to this Contract for Construction (Contingent Assignment of Subcontracts to City if Contract is terminated); and,

GENERAL CONDITIONS

3. Finish the Work by whatever reasonable method the City may deem expedient.
- C. If the City terminates the Contract for one of the reasons stated in Termination by the City for Cause, the Contractor shall not be entitled to receive further payment until the Work is finished.
 - D. If the unpaid balance of the Contract Amount exceeds the cost of finishing the Work including expenses made necessary thereby, such excess shall be paid to the Contractor. If the costs of finishing the Work exceed the unpaid balance, the Contractor shall pay the difference to the City. The amount to be paid to the Contractor or City, as the case may be, shall survive termination of the Contract for Construction.

In the event of such termination, all monies due the Contractor or retained under the terms of this Contract shall be held by the City; however, such holdings will not release the Contractor or its sureties from liability for failure to fulfill the Contract. Any excess cost over and above the Contract Amount incurred by the City arising from the termination of the operations of the Contract and the completion of the Work by the City as provided above shall be paid for by any available funds held by the City. The Contractor will be so credited with any surplus remaining after all just claims for such completion have been paid.

If at any time before completion of the Work under the Contract, the Work shall be stopped by an injunction of a court of competent jurisdiction or by order of any competent authority, the City may give notice to the Contractor to discontinue the Work and terminate the Contract. The Contractor shall discontinue the Work in such manner, sequence, and at such times as the Construction Manager may direct. The Contractor shall have no claim for damages for such discontinuance or termination, nor any claim for anticipated profits on the Work thus dispensed with, nor for any claim for penalty, nor for any other claim such as unabsorbed overhead, except for the work actually performed up to the time of discontinuance, including any extra work ordered by the Construction Manager to be done.

GC 3.19 CITY'S RIGHT TO TERMINATE FOR CONVENIENCE

The City reserves the right to terminate this contract for convenience whenever it considers termination, in its sole and unfettered discretion, to be in the public interest. In the event that the Contract is terminated in this manner, payment will be made for work actually completed. In no event if termination occurs under this provision shall the Contractor be entitled to anticipated profits on items of work not performed as of the effective date of the termination or compensation for any other item, including but not limited to, unabsorbed overhead. The Contractor shall assure that all subcontracts which he/she enters related to this Contract likewise contain a termination for convenience clause which precludes the ability of any subcontractor to make claims against the Contractor for damages, due to breach of contract, of lost profit on items of work not performed or of unabsorbed overhead, in the event of a convenience termination.

GC 3.20 WORK DURING DISPUTES AND LITIGATION

In the event of a dispute between the parties hereto as to performance of the Work, the interpretation of this Contract, or payment or nonpayment for work performed, the parties shall attempt to resolve the dispute. If the dispute is not resolved, Contractor agrees to continue the Work diligently to completion and will neither rescind this Contract nor stop the progress of the Work but will submit such controversy to determination in accordance with the terms of the Contract Documents. In the event any litigation is commenced with respect to this Contract, such litigation shall not serve to suspend Contractor's obligation to continue performance of the Work hereunder.

GC 3.21 LANDS AND RIGHTS-OF-WAY

The lands and rights-of-way for the project to be constructed will be provided by the City. The Contractor shall make his/her own arrangements and pay all expenses for additional area required by him/her outside the limits of the City's land and right-of-way. Work in the public right-of-way shall be done in accordance with the requirements of the permit issued by the public agency in whose right-of-way the work is located in addition to conforming to the plans and specifications.

GC 3.22 WAIVER OF RIGHTS

GENERAL CONDITIONS

Except as otherwise specifically provided in the Contract Documents, no action or failure to act by the City, Owner's Representative, Construction Manager or Contractor shall constitute a waiver of any right or duty afforded any of them under the Contract Documents, nor shall any such action or failure to act constitute an approval of or acquiescence in any breach thereunder.

GENERAL CONDITIONS

SECTION 4.0 SHOP DRAWINGS AND QUALITY CONTROL/INSPECTIONS

GC 4.1 CONTRACTOR'S RESPONSIBILITIES

The Contractor shall submit, at its own expense, submittals and details of structural and reinforcing steel, concrete mix designs, coatings, equipment, material, electrical controls, architectural fabrications, pipe, pipe joints, special pipe sections, and other appurtenances as required in the Technical Specifications and Special Conditions of the Contract Documents. The contract Unit Bid Price for the various items requiring submittals shall include the cost of furnishing all shop drawings, product data, and samples, and the Contractor will be allowed no extra compensation for such drawings, product data or samples.

All submittals and supporting drawings, designs, calculation, data, catalogs, schedules, etc., shall be submitted as the instruments of the Contractor, who shall be responsible for their accuracy, completeness, and coordination. Such responsibility shall not be delegated in whole or part to subcontractors or suppliers. These submittals may be prepared by the Contractor, subcontractors, or suppliers, but the Contractor shall ascertain that submittals meet all of the requirements of the Contract Documents while conforming to structural, space, and access conditions at the point of installation. Designation of work "by others," if shown in submittals, shall mean that the work will be the responsibility of the Contractor rather than the subcontractor or supplier who prepared the submittals. The Contractor shall insure that there is no conflict with other submittals and notify the Construction Manager in each case where its submittal may affect the work of another Contractor or the City. The Contractor shall insure coordination of submittals among the related crafts and subcontractors.

Submittals shall be prepared in such form that data can be identified with the applicable Specification paragraph. The data shall clearly demonstrate compliance with the Contract Drawings and specifications and shall relate to the specific equipment to be furnished. Where manufacturer's standard drawings are employed, they shall be marked clearly to show what portion of the data is applicable to this Project.

GC 4.2 SOURCE OF MATERIALS

Unless otherwise approved in writing by the Construction Manager, only unmanufactured materials produced in the United States, and only manufactured materials made in the United States, shall be used in the performance of this contract.

GC 4.3 TRANSMITTAL PROCEDURES

4.3.1 TRANSMITTAL FORM

A separate transmittal form shall be used for each specific item, class of material, equipment, and items specified in separate, discrete sections for which the submittal is required. Submittal documents common to more than one piece of equipment shall be identified with all the appropriate equipment numbers. Submittals for various items shall be made with a single form when the items taken together constitute a manufacturer's package or are so functionally related that expediency indicates checking or review of the group or package as a whole. The specification section to which the submittal is related shall be indicated on the transmittal form.

A unique number, sequentially assigned, shall be noted on the transmittal form accompanying each item submitted. Original submittal numbers shall have the following format: "XXX"; where "XXX" is the sequential number assigned by the Contractor. Resubmittals shall have the following format: "XXX-Y"; where "XXX" is the originally assigned submittal number and "Y" is a sequential letter assigned for resubmittals, i.e., A, B, or C being the 1st, 2nd, and 3rd resubmittals, respectively. Submittal 25B, for example, is the second resubmittal of submittal 25.

4.3.2 DEVIATIONS FROM THE CONTRACT

If the submittals show any deviations from the Contract requirements, the Contractor shall submit with the submittal submission a written description of such deviations and the reasons therefore. If the City accepts such deviation, the City shall issue an appropriate Contract Change Order, except that, if the deviation is minor, or does not involve a change in price or in time of performance, a Change Order may

GENERAL CONDITIONS

not be issued. If deviations from the Contract requirements are not noted on the submittal by the Contractor, the review of the shop drawing shall not constitute acceptance of such deviations.

4.3.3 SUBMITTAL COMPLETENESS

The Contractor shall check all submittals before submitting them to the Construction Manager and shall certify on the transmittal letter and on each shop drawing that they have been checked, are in compliance with the drawings and specifications, and all deviations from the Contract requirements are noted.

If the Contractor submits an incomplete submittal, the submittal may be returned to the Contractor without review. A complete submittal shall contain sufficient data to demonstrate that the items comply with the specifications, shall meet the minimum requirements for submissions cited in the Technical Specifications, shall include materials and equipment data and certifications where required, and shall include any necessary revisions required for equipment other than first named.

The City reserves the right to deduct monies from payments due the Contractor to cover additional actual costs of review beyond the second submission.

4.3.4 SUBMITTAL PERIOD

All submittals shall be submitted to the Construction Manager within fifteen (15) calendar days after the date of the Notice to Proceed by the City, unless the Construction Manager accepts an alternate schedule for submission of submittals proposed by the Contractor or unless provided for differently in the Special Conditions.

4.3.5 MATERIAL AND EQUIPMENT SUBSTITUTIONS

In preparing these specifications, the Design Consultant has named those products which to its knowledge meet the specifications and are equivalent in construction, functional efficiency, and durability.

Wherever catalog numbers and specific brands or trade names preceded by "similar and equal" or followed by the designation "or equal" are used in conjunction with a designated material, product, installation, or service mentioned in these specifications, they are used to establish the standards of quality and utility required. The Contractor may request, in writing, approval of any material, process or article which he/she believes to be equal. The written request shall state how the material, process, or article proposed for substitution compares with or differs from the designated material, process, or article in composition, size, arrangement, performance, and in addition, the request shall be accompanied by documentary evidence of equality in price and delivery or evidence of difference in price and delivery. Data on price shall be in the form of certified quotations from suppliers of both the designated and proposed material, process or article. If any material, process or article offered by the Contractor is not, in the opinion of the Engineer, equal or better in every respect to that specified, then the Contractor must furnish the material, process or article specified or one that, in the opinion of the Engineer, is the equal or better in every respect. In the event the Contractor furnishes material, process, or article more expensive than that specified, the difference in cost of such material, process, or article so furnished shall be borne by the Contractor. Pursuant to NRS, Chapter 338.140, data substantiating a request for substitution of "an equal" item shall be submitted within seven (7) days after Award of the Contract.

GC 4.4 REVIEW PROCEDURE

Submittals shall be submitted to the Construction Manager for review and will be returned to the Contractor within fifteen (15) working days after receipt, unless otherwise provided for in the Special Conditions. The primary objective of review of submittals by the City is the completion of the Project in full conformance with the Contract, unmarred by field corrections, and within the time provided. In addition to this primary objective, submittal review as a secondary objective will assist the Contractor in its procurement of equipment that will meet all requirements of the Project Drawings and specifications, will fit the structures detailed on the drawings, will be completed with respect to piping, electrical, and control connections, will have the proper functional characteristics, and will become an integral part of a complete operating facility.

After review by the City of each of the Contractor's submissions, the material will be returned to the Contractor with actions defined as follows:

GENERAL CONDITIONS

- A. **No Exceptions Noted (Resubmittal Not Required)**
Accepted subject to its compatibility with future submissions and additional partial submissions for portions of the work not covered in this submission. Does not constitute approval or deletion of specified or required items not shown in the partial submission.
- B. **Make Corrections Noted (Resubmittal Not Required)**
Same as A, except that minor corrections as noted shall be made by the Contractor.
- C. **Make Corrections Noted (Resubmittal)**
Rejected because of inconsistencies or errors which shall be resolved or corrected by the Contractor prior to subsequent review by the City.
- D. **Not Acceptable (Resubmit)**
Submitted material does not conform to drawings and specifications in major respects, i.e.: wrong size, model, capacity, or material.

It shall be the Contractor's responsibility to copy and/or conform reviewed submittals in sufficient numbers for its files, subcontractors, and vendors.

The Contractor shall submit a minimum of six (6) copies for each submittal. The Construction Manager will retain a minimum of four (4) copies for its use and record and return two (2) copies to the Contractor.

The City's favorable review of submittals shall be obtained prior to the fabrication, delivery and construction of items requiring submittal review.

Favorable review of submittals does not constitute a change order to the Contract requirements. The favorable review of all submittals by the City shall apply in general design only and shall in no way relieve the Contractor from responsibility for errors or omissions contained therein. Favorable review by the City shall not relieve the Contractor of its obligation to meet safety requirements and all other requirements of law. Favorable review by the City shall not constitute acceptance by the City of any responsibility for the accuracy, coordination, and completeness of any items or equipment represented on the submittals.

GC 4.5 QUALITY CONTROL - GENERAL

All materials and equipment to be incorporated into the Work, unless otherwise specified, shall be new and of the specified quality and equal to the samples found to be acceptable by the Design Consultant if samples have been submitted. All materials, equipment, and supplies provided shall, without additional charge to the City, fully conform with all applicable state and federal safety laws, rules, regulations, and orders, and it shall be the Contractor's responsibility to provide only such materials, equipment, and supplies. It shall be the duty of the Contractor to call the Construction Manager's attention to apparent errors or omissions and request instructions before proceeding with the Work. The Construction Manager may, by appropriate instructions, correct errors and supply omissions not involving extra cost, which instructions shall be as binding upon the Contractor as though contained in the original Contract Documents.

At the option of the Construction Manager, materials and equipment to be supplied under this Contract will be tested and inspected either at their place of origin, laboratory, or at the site of the Work. The Contractor shall give the Construction Manager written notification at least 30 days prior to the shipment of materials and major equipment to be tested and inspected at point of origin. Prior to shipping any precast concrete products, a meeting shall be held at the manufacturer's site to discuss and agree on uniform acceptability standards for the precast products. Satisfactory tests and inspections at the point of origin shall not be construed as a final acceptance of the materials and equipment, nor shall such tests and inspections preclude retesting or re-inspection at the site of the Work.

Inspection of the Work by the City, Construction Manager and/or Design Consultant shall not relieve the Contractor of its obligations to conduct comprehensive inspections of the Work, to furnish materials and perform acceptable Work, and to provide adequate safety precautions in conformance with the intent of the Contract.

GENERAL CONDITIONS

4.5.1 QUALITY ASSURANCE INSPECTION

All work and materials are subject to the inspection of the Construction Manager. The Contractor shall prosecute work only in the presence of the Construction Manager or a City inspector appointed by the Construction Manager, and any work done in the absence of said Construction Manager or inspector may be subject to rejection. Furthermore, failure to call for the Construction Manager or inspector to inspect as the work progresses shall be considered as a major breach of the Contract and may constitute grounds for the City to terminate. The Contractor shall make a request to the Construction Manager or inspector at least twenty-four (24) hours in advance before inspection services are required for the work. If the specifications, the Construction Manager's instructions, laws, ordinances, or any public authority require any work to be specially tested or approved, the Contractor shall give timely notice of its readiness for inspection. The City, Construction Manager, Design Consultant and authorized agents and their representatives shall at all times be provided safe access to the Work wherever it is in preparation or progress and to all warehouses and storage yards wherein materials and equipment are stored, and the Contractor shall provide facilities for such access and for inspection, including maintenance of temporary and permanent access. Inspection of the Work shall not relieve the Contractor of the obligation to fulfill all conditions of the Contract, and improper work will be subject to rejection. Work and materials not meeting such requirements shall be made good, and unsuitable work or materials may be rejected; notwithstanding that such work or materials have been previously inspected by the Construction Manager or that payment therefore has been included in a progress estimate.

No work or any portion thereof shall be deemed acceptable by reason of the presence of the Engineer. While the Engineer will endeavor to point out to the Contractor any defective work which comes to the Engineer's attention during these observations, the Engineer's failure to do so shall not constitute the basis of any claim, suit, or cause of action by the Contractor or any party against the Engineer or City and shall not excuse nonconforming or defective work by the Contractor.

No portion of any work or installed materials shall be covered or concealed in any manner without first being inspected by the Construction Manager. If any work should be covered up without the approval or consent of the Construction Manager, the Construction Manager shall have the authority to require, at any time before acceptance of the Work, that such work be uncovered for examination. After examination, the Contractor shall restore said portions of the Work to the standards required by the Specifications. Should the work thus exposed or examined prove acceptable, the uncovering or removing of the covering and the replacing of the covering or making good of the parts removed, will be paid for as provided in GC 6.0, CHANGE ORDERS, but should the work so exposed or examined prove unacceptable, the uncovering or removing and the replacing of the covering or making good of the parts removed shall be at the Contractor's expense.

4.5.2 PERMIT AND CODE COMPLIANCE INSPECTIONS

Separate and independent from the inspections above, the Work may require the inspections of Building Officials or other agencies. The Contractor shall make arrangements with the Carson City Building Department to schedule appropriate Building Permit compliance inspections and with other agencies (i.e. Fire Officials, NDOT, NDEP, etc.) to schedule their required permit and code inspections. Such inspectors shall have the authority provided them by their agencies and jurisdictions.

4.5.3 SAMPLES AND TESTS

The source of supply of materials for the Work shall be subject to tests and inspection before the delivery is started and before such materials are used in the Work. Representative preliminary samples of the character and quality prescribed shall be submitted to the Construction Manager by the Contractor in sufficient quantities or amounts for testing or examination.

All tests of materials furnished by the Contractor shall be made in accordance with the commonly recognized standards of national technical organizations, and such special methods and tests as are prescribed in the Technical Specifications. Certificates of Compliance shall be provided by the Contractor as required in the Technical Specifications.

GENERAL CONDITIONS

A. Sampling

The Contractor shall furnish such samples of materials as are requested by the Construction Manager. No material shall be used until the Construction Manager has had the opportunity to test or examine such materials. Samples shall be secured and tested whenever necessary to determine the quality of the material. Samples and test specimens prepared at the site, such as concrete test cylinders, shall be taken or prepared by the Construction Manager in the presence and with the assistance of the Contractor.

B. Testing

All initial testing including, but not limited to, concrete, soils, and asphalt/concrete pavement shall be at no expense to the Contractor and shall be performed in the City's laboratory or in a laboratory designated by the City. When required by the Contract or the Construction Manager, the Contractor shall furnish certificates of tests of materials and equipment made at the point of manufacture by a recognized testing laboratory.

The Contractor is responsible for all system and equipment testing as provided for in these Contract Documents.

C. Retesting Costs

The costs of any retesting required due to failed test or defective material or sample shall be at the Contractor's expense. The City will deduct such retesting costs from the progress payments through a deductive change order.

D. Test Standards

All sampling, specimen preparation, and testing of materials shall be in accordance with the requirements of the Standard Specifications, or any permits, and the standards of nationally recognized technical organizations. The physical characteristics of all materials not particularly specified shall conform to the latest standards published by the American Society for Testing Materials, where applicable.

E. Testing Disputes

In the event that the Contractor disputes the results of the City's materials testing and retains his/her own testing laboratory for comparison testing, only a laboratory and personnel certified under the Nevada Alliance for Quality Transportation Construction (NAQTC) will be considered.

GENERAL CONDITIONS

SECTION 5.0 PAYMENT

GC 5.1 GENERAL

The Contractor shall accept the compensation, as herein provided, as full payment for furnishing all labor, materials, tools, equipment, and incidentals appurtenant to the various items of the Proposal Summary, as further specified herein, necessary for completing the Work, all in accordance with the requirements of the Contract Documents, including all costs of permits and compliance with the regulations of the Occupational Safety and Health Administration of the U. S. Department of Labor (OSHA), and no additional compensation will be allowed therefore. No separate payment will be made for any item that is not specifically set forth in the Proposal Summary, and all costs therefore shall be included in the prices named in the Proposal Summary for the various items of Work. Prior to the City processing the pay estimate, if prevailing wage rates are required, the Contractor shall submit to the City a copy of its certified payroll reports for each week within the pay estimate period.

GC 5.2 PAYMENT FOR PATENTS AND PATENT INFRINGEMENT

All fees or claims for any patented invention, article, or arrangement that may be used upon or in the work, or is in any manner connected with the performance of the Work, shall be included in the price bid for doing the work. The Contractor and its sureties shall defend, protect, and hold the City, the Construction Manager, and Design Consultant, and their officers, agents, employees, and volunteers harmless against liability of any nature or kind for any and all costs, legal expenses, and damages made for such fees or claims and against any and all suits and claims brought or made by the holder of any invention or patent, or on account of any patented or unpatented invention, process, article, or appliance manufactured for or used in the performance of the Contract, including its use by the City. Before final payment is made on the Contract, the Contractor shall furnish an affidavit to the City regarding patent rights for the Project. The affidavit shall state that all fees and payments due as a result of the Work incorporated into the Project or methods utilized during construction have been paid in full. The Contractor shall certify in the affidavit that no other fees or claims exist in this Project.

GC 5.3 PAYMENT OF TAXES

The Contractor shall pay and shall assume exclusive liability for all taxes levied or assessed on or in connection with the Contractor's performance of this Contract, including, but not limited to, state and local sales and use taxes, federal and state payroll taxes or assessments, and excise taxes. No separate allowance will be made therefore, and all costs in connection therewith shall be included in the total amount of the Contract Amount.

GC 5.4 PAYMENT FOR LABOR AND MATERIALS

In accordance with the provision of NRS 338.550, the Contractor shall pay and require its subcontractors to pay all accounts for labor including workers' compensation premiums, state unemployment and federal social security payments and other wage and salary deductions required by law. The Contractor also shall pay and cause its subcontractors to pay all accounts for services, equipment, and materials used by the Contractor and its subcontractors during the performance of Work under this Contract. Such accounts shall be paid as they become due and payable.

GC 5.5 PARTIAL PAYMENTS

In consideration of the faithful performance of the Work prosecuted in accordance with the provisions of the Contract Documents, the City will pay the Contractor for all such work installed on the basis of percentage completion. Amounts earned will be based on the accepted Schedule of Values.

Payments will be made by the City to the Contractor on estimates approved by the Construction Manager, based on the value of equipment installed and tested, labor and materials incorporated into said permanent Work by the Contractor during the preceding month, and acceptable materials and equipment on hand (materials and equipment furnished and delivered to the site by the Contractor and not yet incorporated into the work accompanied by an approved paid invoice) per GC 5.5.1, below.

Partial payments will be made monthly based on work accomplished as of the last day of each calendar month.

The Contractor and Construction Manager shall meet within five (5) days after the end of each calendar month to review and agree on the Work completed within the past month. The Contractor shall then submit its progress

GENERAL CONDITIONS

billing of the Work completed during the prior month and the Work completed to date on the City's approved form corresponding to the accepted Schedule of Values. Upon receipt of Contractor's progress billing, the City shall act in accordance with the following:

- a. The Construction Manager shall review the submitted progress billing to verify that it corresponds with the agreement reached at the above mentioned review meeting. If the progress billing is satisfactory, the Construction Manager will process it for payment.
- b. If the Construction Manager determines that the progress billing is not satisfactory, then pursuant to NRS 338.525, the City shall, within twenty (20) days of receipt of said progress billing, give written notification to the Contractor of any amount that will be withheld and a detailed explanation of the reason for the withholding. The remainder will be processed for payment.

If requested, the Contractor shall provide such additional data as may be reasonably required to support the partial payment request. Payment will be made by the City to the Contractor in accordance with City's normal accounts payable procedures. The City shall retain amounts in accordance with Sections GC 5.6, RETENTION, and GC 5.7, OTHER WITHHOLDS.

Per NRS 338.515, the City shall pay the Contractor within thirty (30) days after receipt of its progress billing.

5.5.1 PARTIAL PAYMENTS - INCLUSION OF MATERIALS ON HAND

Except as otherwise provided in NRS 338.515(1), GC 5.6 "RETENTION", NRS 338.525, and GC 5.7 "OTHER WITHHOLDS", pursuant to NRS 338.515(2), the City will pay or cause to be paid to the Contractor the actual cost of the supplies, materials and equipment that have been identified in the Special Conditions as eligible for such payment. To be eligible for such payment the supplies, materials, or equipment must:

- (A) be identified in the Special Conditions:
- (B) have been delivered and stored at a location, and in the time and manner, specified in this Contract by the Contractor or a subcontractor or supplier for use in the Work; and,
- (C) be in short supply or were made specifically for this Contract.

Materials, as used herein, shall be considered to be those items which are fabricated and manufactured goods and equipment. Only those materials for which the Contractor can transfer clear title to the City will be qualified for partial payment.

To receive payment for materials and equipment delivered to the site, but not incorporated in the Work, it shall be necessary for the Contractor to submit to the Construction Manager a list of such materials at least seven (7) days prior to submitting the monthly progress billing for work completed. At the Construction Manager's discretion, the Construction Manager will approve items for which partial payment is to be made subject to the following:

- a. Only equipment or materials which have received favorable review of shop drawings will qualify.
- b. Eligible equipment or materials must be delivered and properly stored, protected, and maintained at the job site in a manner favorably reviewed by the Construction Manager.
- c. The Contractor's actual net cost for the materials must be supported by paid invoices of suppliers or other documentation requested by the Construction Manager.

GC 5.6 RETENTION

From each progress payment estimate, ten (10) percent of the "total completed to date" sum will be deducted and retained by the City, and the remainder, less the amount of all previous payment, will be paid to the Contractor. After fifty (50) percent of the Work has been completed and if progress on the Work remaining is satisfactory, the

GENERAL CONDITIONS

deduction to be made from the remaining progress payments and from the final payment may be reduced to five (5) percent of the adjusted Contract Price at the discretion of the City.

GC 5.7 OTHER WITHHOLDS

In addition to the amount which the City may otherwise retain under the Contract, the City may withhold a sufficient amount of any payment otherwise due the Contractor, as in its judgment may be necessary to cover:

- a. Defective work not remedied;
- b. A reasonable doubt that the Contract can be completed for the balance then unpaid;
- c. Damage to another contractor, third party, or to property;
- d. Failure to submit, revise, resubmit, or otherwise conform to the requirements herein for preparing and maintaining a construction schedule;
- e. Failure of the Contractor to keep the Work progressing in accordance with its Progress Schedule;
- f. Failure to maintain current "As-Built" record drawings;
- g. Failure of the Contractor to make proper submissions, as herein specified;
- h. Payments due the City from the Contractor;
- i. Reduction of Contract Amount because of modifications; or
- j. The Contractor's neglect or unsatisfactory prosecution of the Work, including failure to clean up.

When the above reasons for withhold amounts are removed, payment will be made to the Contractor for amounts withheld.

GENERAL CONDITIONS

SECTION 6.0 CHANGE ORDERS

GC 6.1 GENERAL

Without invalidating the Contract and without notice to sureties or insurers, the City through the Construction Manager, may at any time order additions, deletions, or revisions in the Work. These will be authorized by Work Directive, Field Order, or Change Order. A Change Order will not be issued for a Work Directive unless the Construction Manager concurs with an appeal by the Contractor that such Work Directive is a change in the scope of the Contract. The Contractor shall comply promptly with the requirements of all Change Orders, Field Orders, or Work Directives. The work involved in Change Orders shall be executed under the applicable conditions and requirements of the Contract Documents. If any Field Order or Work Directive causes an increase or decrease in the Contract Amount or an extension or shortening of the Contract Time, an equitable adjustment will be made by issuing a Change Order. If the Contractor accepts a Change Order that does not include a time extension, the Contractor waives any claim for additional time for the work covered by that Change Order. Additional or extra work performed by the Contractor without written authorization of a Work Directive, Field Order or Change Order will not entitle the Contractor to an increase in the Contract Amount or an extension of the Contract Time.

Extra work shall be that work neither shown on the Contract Drawings nor specified. Such work shall be governed by all applicable provisions of the Contract Documents. In giving instructions, the Construction Manager shall have authority to make minor changes in the Work, not involving extra cost, or extra time, and not inconsistent with the intent of the Work. With the exception of an emergency which would endanger life or property, no extra work or change shall be made unless in pursuance of a written order by the City through the Construction Manager, and no claim for an addition to the total amount or total time of the Contract shall be valid unless so ordered in writing.

In case any change increases or decreases the Work shown, the Contractor shall be paid for the work actually done at a mutually agreed upon adjustment to the Contract Amount.

If the Contractor refuses to accept a Change Order, the City may issue it unilaterally. The Contractor shall comply with the requirements of the Change Order. The City shall provide for an equitable adjustment to the Contract, and compensate the Contractor accordingly. If the Contractor does not agree that the adjustment is equitable, it may submit a claim in accordance with the requirements herein stated.

GC 6.2 DIFFERING SITE CONDITIONS

The Contractor shall promptly, and before such conditions are disturbed, notify the Construction Manager in writing, of any:

- a. Material that the Contractor believes may be hazardous waste that is required to be removed to a Class I, Class II, or Class III disposal site in accordance with provisions of law.
- b. Subsurface or latent physical conditions at the site differing from those indicated.
- c. Unknown physical conditions at the site of any unusual nature, differing materially from those ordinarily encountered and generally recognized as inherent in work of the character provided for in the Contract.

The Construction Manager shall promptly investigate the conditions, and if it finds that the conditions do materially differ, or do involve hazardous waste, and cause an increase or decrease in the Contractor's cost of, or the time required for performance of any part of the Work, the City shall cause to be issued a change order under the procedures provided herein.

In the event that a dispute arises between the City and the Contractor whether the conditions materially differ, or involve hazardous waste, or cause a decrease or increase in the Contractor's cost of, or time required for, performance of any part of the Work, the Contractor shall not be excused from any scheduled completion date provided for by the Contract, but shall proceed with all Work to be performed under the Contract. The Contractor

GENERAL CONDITIONS

shall retain any and all rights provided either by Contract or by law which pertain to the resolution of disputes and protests between the parties.

No claim of the Contractor under this clause shall be allowed unless the Contractor has given the notice required.

GC 6.3 RESOLUTION OF DISPUTES

6.3.1 CONTRACT INTERPRETATION BY THE CONSTRUCTION MANAGER

Questions regarding the meaning and intent of the Contract Documents shall be referred in writing by the Contractor to the Construction Manager. Where practical, the Construction Manager shall respond to the Contractor in writing with a decision within seven (7) working days of receipt of the request.

6.3.2 CLAIMS

A. Notice

If the Contractor disagrees with the Construction Manager's decision, or in any case where the Contractor deems additional compensation or a time extension to the Contract period is due the Contractor for work or materials not covered in the Contract or which the Construction Manager has not recognized as extra work, the Contractor shall notify the Construction Manager, in writing, of its intention to make claim. Claims pertaining to decisions based on Contract interpretation or such other determinations by the Construction Manager shall be filed in writing to the Construction Manager within five (5) days of receipt of such decision. All other claims or notices for extra work shall be filed in writing to the Construction Manager prior to the commencement of such work. Written notice shall use the words "Notice of Potential Claim". Such Notice of Potential Claim shall state the circumstances and all reasons for the claim, but need not state the amount.

It is agreed that unless notice is properly given, the Contractor shall not recover costs incurred by it as a result of the alleged extra work, changed work or other situation which, had proper notice been given, would have given rise to a right for additional compensation. The Contractor should understand that timely Notice of Potential Claim is of great importance to the Construction Manager and City, and is not merely a formality. Such notice allows the City to consider preventative action, to monitor the Contractor's increased costs resulting from the situation, to marshal facts, and to plan its affairs. Such notice by the Contractor, and the fact that the Construction Manager has kept account of the cost as aforesaid, shall not in any way be construed as proving the validity of the claim.

B. Records of Disputed Work

In proceeding with a disputed portion of the Work, the Contractor shall keep accurate and complete records of its costs and shall make available to the Construction Manager a daily summary of the hours and classifications of equipment and labor utilized on the disputed work, as well as a summary of any materials or any specialized services which are used which shall be signed by the Construction Manager and Contractor daily. Such information shall be submitted to the Construction Manager on a weekly or daily basis as determined by the Construction Manager, receipt of which shall not be construed as an authorization for or acceptance of the disputed work.

C. Submission of Claim Costs

Within thirty (30) days after the last cost of work for which the Contractor contends it is due additional compensation is incurred, but if costs are incurred over a span of more than thirty (30) days, then within fifteen (15) days after the thirtieth day and every month thereafter, the Contractor shall submit to the Construction Manager, as best the Contractor is able, its costs incurred for the claimed matter. Claims shall be made in itemized detail. Should the Construction Manager be dissatisfied with format or detail of presentation, and upon request for more or different information, the Contractor will promptly comply to the satisfaction of the Construction Manager. If the additional costs are in any respect not known with certainty, they shall be estimated as best as can be done. In case the claim is found to be just, it shall be allowed and

GENERAL CONDITIONS

paid for as provided in GC 6.4, MODIFICATION PROCEDURES and GC 5.5, PARTIAL PAYMENTS.

D. Claim Meetings

The Construction Manager may call special meetings to discuss outstanding claims. The Contractor shall cooperate and attend such meetings prepared to discuss its claims, making available the personnel necessary for resolution, and all documents which may reasonably be requested by the Construction Manager.

GC 6.4 MODIFICATION PROCEDURES

6.4.1 CHANGES IN CONTRACT PRICE

Whenever corrections, alterations, or modifications of the Work under this Contract are ordered by the Construction Manager, approved by the City, and increase the amount of work to be done, such added work shall be known as extra work. When such corrections, alterations, or modifications decrease the amount of work to be done, such subtracted work shall be known as work omitted.

The difference in cost of the work affected by such change will be added to or deducted from the amount of said Contract Amount, as the case may be, by a fair and reasonable valuation, which shall be determined in one or more of the following ways as directed by the Construction Manager:

- a. By unit prices accepted by the City and stated in the Contract Documents or Schedule of Values;
- b. By unit prices subsequently fixed by agreement between the parties;
- c. By an acceptable lump sum proposal from the Contractor; or
- d. By Force Account (as described in GC 6.4.3, Force Account Payment, when directed and administered by the City or Construction Manager.

When required by the Construction Manager, the Contractor shall submit, in the form prescribed by the Construction Manager, an itemized breakdown with supporting data of the quantities and prices used in computing the value of any change that may be ordered.

The Construction Manager will review the Contractor's proposal for the change and negotiate an equitable adjustment with the Contractor. When there is an agreement, the Construction Manager will prepare and process the Change Order and make a recommendation for action by the City. All Change Orders must be signed by the Contractor and approved by the City unless unilaterally issued per GC 6.1, above.

The prices agreed upon and any agreed upon adjustment in Contract Time shall be incorporated in the written order issued by the City, which shall be written so as to indicate an acceptance on the part of the Contractor as evidenced by its signature. By signature of the Change Order, the Contractor acknowledges that the adjustments to cost and time contained in the Change Order are in full satisfaction and accord, payment in full, and so waives any right to claim any further cost and time impacts at any time during and after completion of the Contract for the changes encompassed by the Change Order.

When any Extra Work is performed by a Subcontractor, the markups established in GC 6.4.2 and GC 6.4.3 shall be applied to the Subcontractor's costs as determined under GC 6.4.2 and GC 6.4.3. The Contractor's markup on subcontracted work shall be limited to five percent (5%) of the total of the Subcontractor's costs, which amount shall constitute the markup for all overhead and profit for the Contractor on work by the Subcontractor. On any item(s) of Extra Work, there shall only be one markup allowed to the Subcontractor even if there are multiple tiers of subcontractors, and only one markup allowed to the Contractor for subcontracted work.

GENERAL CONDITIONS

6.4.2 NEGOTIATED CHANGE ORDERS

Under the methods described in GC 6.4.1.b and 6.4.1.c above, the Contractor shall submit substantiating documentation with an itemized breakdown of Contractor and subcontractor direct costs, including labor, material, equipment, rentals, and approved services pertaining to such ordered work in the form and detail acceptable to the Construction Manager. The direct costs shall include only the payroll cost for workers and foremen including wages, fringe benefits as established by negotiated labor agreements or state prevailing wages, workers' compensation and labor insurance, and labor taxes as established by law. No other fixed labor burdens will be considered. The cost of materials used and equipment delivered and installed in the Work shall be as substantiated by appropriate documents. The cost of construction machinery and equipment shall be based on fair rental or ownership values acceptable to the Construction Manager as described in GC 6.4.3, Force Account Payment, and the cost of incidentals directly related to such work. The direct costs shall not include any labor or office costs pertaining to the Contractor's managers or superintendents, its office and office facilities, or anyone not directly employed on such work, nor the cost of small tools, as all such indirect costs form a part of the Contractor's overhead expense.

Under the method described in GC 6.4.1.b and 6.4.1.c, the maximum percentage which will be allowed for the Contractor's combined overhead and profit will be:

Direct Labor	fifteen percent (15%)
Materials	fifteen percent (15%)
Equipment (owned or rented)	fifteen percent (15%)

The above fees represent the maximum limits which will be allowed, and they include the Contractor's indirect home office expenses and all costs for cost proposal preparation.

The amount of credit to be allowed by the Contractor to the City for any such change which results in a decrease in cost will be the amount of the actual net decrease plus a credit in accordance with the markups allowed above.

The Contractor shall not claim for anticipated profits on work that may be omitted unless the deleted amount of work is determined to constitute a cardinal change to the Project.

6.4.3 FORCE ACCOUNT PAYMENT

If either the amount of Work or payment for a Change Order cannot be determined or agreed upon beforehand, the City may direct by written Change Order, Work Directive, or Field Order that the Work be done on a force account basis. The term "force account" shall be understood to mean that payment for the Work will be done on a time and expense basis, that is, on an accounting of the Contractor's forces, materials, equipment, and other items of cost as required and actually used to do the work. In order to have a valid claim for Force Account payment, the Contractor must submit on a daily basis the City's Daily Extra Work Report signed by both the Contractor's representative and the City's Construction Manager or inspector. For the work performed, payment will be made for the documented actual cost of the following:

- a. Direct labor cost for workers, including foremen, who are directly assigned to the force account Work. Direct labor cost is the actual payroll cost including wages, fringe benefits as established by negotiated labor agreements or state prevailing wages, workers' compensation and labor insurance, and labor taxes as established by law. No other fixed labor burdens will be considered.
- b. Material delivered and used on the designated work, including sales tax, if paid for by the Contractor or its subcontractor. Material wasted or disposed of in a manor not called for under the contract, material not unloaded from the transporting vehicle, material placed outside the limits indicated or given plans; or material remaining on hand after completion of the work will not be paid for except as otherwise provided.

GENERAL CONDITIONS

- a. Equipment rental: For any machinery or equipment, the use of which has been authorized by the Construction Manager, the Contractor will be paid for the use of such machinery or equipment in the manner hereinafter specified, regardless of ownership and any rental or other agreement, if such may exist, for the use of such equipment entered into by the contractor.

Rental rates will be determined as follows:

- 1.1 The base rates shall be those established in publications and revisions thereto entitled "Rental Rate Blue Book for Construction Equipment" or the "Rental Rate Blue Book for Older Construction Equipment" available from Equipment Watch, 1735 Technology Drive, Suite 410, San Jose, CA 95110-1313, phone (408) 467-6700.

The hourly rate to be paid shall be the monthly rate divided by 176, multiplied by the regional adjustment factor, and multiplied by the appropriate rate adjustment factor, then plus the estimated operating cost per hour shown therein, and then rounded to the nearest \$0.10.

2. Attachments (e.g. tractor with ripper and dozer or tractor with loader and backhoe) will be included in the hourly rental rate only when deemed essential to the work as determined by the Construction Manager. When multiple attachments are approved for use and are being used interchangeably, the attachment having the highest rental rate shall be the only one included for payment.
3. No direct payment will be made for necessary accessories (including replenishing blades, augers, teeth, hoses, bits, etc.) if not listed in the Rental Rate Blue Book.
4. No compensation will be allowed for shop tools having a daily rental rate of less than \$10 as set forth in Section 18 of the Rental Rate Book.

If ordered to use equipment not listed in the aforementioned publications, a suitable rental rate for such equipment will be established. Contractor shall furnish any cost data which might assist in the establishment of such rental rate.

Except as provided below, payment will be made for the actual time that such equipment is in operation on the work. Time will be measured in 0.5 hours increments of actual working time and necessary traveling time of the equipment within the limits of the project.

Authorized standby time for idle equipment will be paid for at 50% of the "monthly rate divided by 176, multiplied by the regional adjustment factor, and multiplied by the rate adjustment factor", and rounded to the nearest \$0.10. No operating cost, markup, overhead or profit will be added.

The rental rates paid as above provided shall include the cost of fuel, oil, lubrication, supplies, small tools, necessary attachments, repairs and maintenance of any kind, depreciating, storage, insurance and all incidentals.

When special equipment has been ordered in connection with force account work, travel time and transportation to the project will be measured as hereinafter outlined. For the use of special equipment moved in on the work and used exclusively for extra work paid for on a force account basis, the rental rates as determined above and the cost of transporting the equipment to the location of the work and its return to its original location will be paid, all according to the following provisions:

GENERAL CONDITIONS

- (a) The original location of the equipment to be hauled to the location of the work will be agreed to in advance.
- (b) The City will pay the costs of loading and unloading such equipment.
- (c) The cost of transporting equipment on low bed trailers shall not exceed the hourly rates charged by established haulers.
- (d) The rental period shall begin at the time the equipment is unloaded at the site of the extra work, shall include each day that the equipment is at the site of the extra work, excluding Saturdays, Sundays and legal holidays unless the extra work is performed on such days, and shall terminate at the end of the day on which the Construction Manager directs the Contractor to discontinue the use of such equipment.
- (e) Should the Contractor desire the return of the equipment to a location other than its original location, the City will pay the cost of transportation by the above provisions, provided such payment shall not exceed the cost of moving the equipment to the work.
- (f) Payment for transporting and loading and unloading equipment as above provided will not be made if the equipment is used on the work in any other way than upon extra work paid for on a force account basis. _

To the preceding costs, there shall be added the following fees as the combined overhead and profit for the Contractor:

- a. A fixed fee not-to-exceed fifteen (15) percent of the costs of Item a, labor, above.
- b. A fixed fee not-to-exceed fifteen (15) percent of the costs of Item b, materials, above.
- c. A fixed fee not-to-exceed fifteen (15) percent of the costs of Item c, equipment, above.

The added fixed fees shall be considered to be full compensation covering the cost of general supervision, overhead, profit, and all other expenses. The above fixed fees represent the maximum limits which will be allowed, and they include the Contractor's indirect home office expenses and all costs for cost proposal preparation and record keeping.

6.4.4 UNIT PRICE ADJUSTMENTS DUE TO INCREASED OR DECREASED QUANTITIES

The unit prices as stated in the Bid and as negotiated in Change Orders shall apply to one hundred (100) percent of the quantity indicated to be estimated quantity for the Bid item, plus or minus twenty-five (25) percent. Either party to the Contract will be entitled to an equitable adjustment in unit prices for that portion of the actual quantity less than seventy-five (75) percent or more than one hundred twenty-five (125) percent of the original Bid quantity. Such equitable adjustment shall be determined in one or more of the following ways:

- A. If the parties are able to agree, the price will be determined by using:
 - 1. Unit prices; or
 - 2. Other agreed upon prices.
- B. If the parties cannot agree, the price will be determined by the Engineer using:
 - 1. Unit prices, or
 - 2. Other means to establish costs.

GENERAL CONDITIONS

The following limitations shall apply in determining the amount of the equitable adjustment:

- A. No claim for loss of anticipated profits on deleted or uncompleted work or consequential damages of any kind will be allowed.
- B. If the actual quantity of work performed is less than seventy-five (75) percent of the original Bid quantity, the total payment for the item will be limited to not more than seventy-five (75) percent of the amount originally Bid.
- C. No payment will be made for extended or unabsorbed home office overhead and field overhead expenses to the extent that there is an unbalanced allocation of such expenses among the contract Bid items.
- D. No adjustment in the unit contract bid price will be made for any item unless the increase or decrease in quantity results in a change of \$10,000 or more as measured by the original bid quantity and unit price for the item.

The City will not adjust for increases or decreases if the City has entered the amount for the Bid item in the proposal form only to provide a common basis for bidders.

6.4.5 TIME EXTENSIONS FOR CHANGE ORDERS

If the Contractor requests a time extension for the extra work necessitated by a proposed Change Order, the request must be accompanied by a time impact analysis, based on the latest Construction Schedule update, or other method acceptable to the Construction Manager.

GC 6.5 DISPUTES

Any dispute relating to this Contract after award shall be resolved through good faith efforts by the Contractor and City. The Contractor shall have the right to appeal any decision by any inspector to the Construction Manager; and, by the Construction Manager to the Owner's Representative. Initial notice of any dispute must be filed with the Construction Manager per GC 6.3.2.A, Claims - Notice.

If the Contractor considers the determination of the Construction Manager to be unfair he/she shall, within ten (10) days after receipt of the Construction Managers decision, file a written protest with the Owner's Representative stating clearly and in detail his/her objections and the reasons therefore. The Owner's Representative shall review the issue in dispute and shall promptly advise the Contractor in writing of his/her final decision. At all times, the Contractor shall carry on the Work and maintain its Construction Schedule in accordance with the requirements of the Contract and the determination of the City, pending resolution of any dispute.

If review by the Owner's Representative does not result in a resolution of the dispute, the parties shall proceed to non-binding mediation. Non-binding mediation shall be conducted under the auspices of the American Arbitration Association acting under its Construction Industry Mediation Procedures. Mediation conducted in accordance with this provision shall take place in Carson City, Nevada. Mediation shall be conducted by a single mediator, approved by both the City and the Contractor from a list provided by the American Arbitration Association. Each party shall pay one-half of the mediator's compensation and the administration fees. Each party shall bear its own expenses associated with the mediation, including but not limited to its own attorney and expert consultant fees. Each party shall have at least one individual attend the mediation proceeding who has full authority to settle the dispute on their behalf, provided however, that any agreement reached will have to be put before the Carson City Board of Supervisors or Carson City Regional Transportation Commission for final approval.

GC 6.6 ARBITRATION

Any controversy or claim arising out of or relating to the performance of these Contract Documents, which cannot be resolved by mutual agreement or mediation, shall be submitted to binding arbitration by the claiming party by filing a Notice of Intent to Arbitrate (demand) within fifteen (15) days of the conclusion of mediation, specified above in GC 6.5, DISPUTES, with the other party and three (3) copies to the American Arbitration Association or the Nevada Arbitration Association. Either party to the Contract Documents may request that any dispute or difference be arbitrated by filing a demand to arbitrate. Said demand shall contain a statement of the disputes,

GENERAL CONDITIONS

the amount involved, if any, and the remedy sought. Through written mutual consent, the parties may agree to combine all disputes for a single arbitration proceeding during or after substantial completion of the Project. Such arbitration shall be conducted in accordance with the Construction Industry Arbitration Rules (which can be found at www.adr.org) administered by the American Arbitration Association or the Nevada Arbitration Association. Failure to give such notice in the time specified shall preclude the party desiring arbitration from subsequently arbitrating that particular claim, dispute, or other matter. Judgment on the award rendered by the arbitrators may be entered in the First Judicial District Court of the State of Nevada.

In the event that any controversy or claim arising out of or relating to the performance of this Contract becomes the subject of arbitration, Carson City shall have the right to join or bring an additional party to the arbitration proceeding, and the Contractor hereby irrevocably consents and agrees to such joinder.

In the event that Carson City is named as a party to any arbitration action arising out of, or resulting from the design or construction of the Project, the Contractor hereby agrees, at the request of Carson City, to be joined as a party to that arbitration proceeding and to be bound by any decision resulting from arbitration.

In the event of arbitration, it is agreed by the parties that all means of discovery, including but not limited to depositions and interrogatories, will be afforded to the parties involved in the arbitration, and the appointed arbitrator shall have all authority to impose sanctions against either party for failing to comply with the rules for discovery provided under the Nevada Rules of Civil Procedure.

Any arbitration carried out under the provisions of GC 6.6, ARBITRATION, shall be heard and determined by a three (3) member panel. From a list of arbitrators provided by the American Arbitration Association, Carson City shall select one (1) member of the panel and the Contractor shall select one (1) member of the panel. The third member of the panel shall be selected from said list by the first two (2) members and shall be approved by both Carson City and the Contractor. The third (3rd) member shall function as the Chairperson of the arbitration panel.

The Contractor shall carry on the Work and maintain progress during any arbitration or any other disputes unless otherwise mutually agreed upon in writing.

Arbitration conducted in accordance with this provision shall take place in Carson City, Nevada.

GENERAL CONDITIONS

SECTION 7.0 CONSTRUCTION FACILITIES AND TEMPORARY CONTROLS

GC 7.1 GENERAL

The Contractor shall provide all temporary facilities and utilities required for prosecution of the Work, protection of employees and the public, protection of the Work from damage by fire, weather or vandalism, and such other facilities as may be specified or required by any legally applicable law, ordinance, rule, or regulation.

GC 7.2 TEMPORARY UTILITIES AND CONSTRUCTION FACILITIES

7.2.1 ELECTRICAL SERVICE

The Contractor shall arrange with the local utility to provide adequate temporary electrical service at a mutually agreeable location. The Contractor shall then provide adequate jobsite distribution facilities conforming to applicable codes and safety regulations. The Contractor shall provide, at its own cost, all electric power required for construction, testing, general and security lighting, and all other purposes whether supplied through temporary or permanent facilities.

7.2.2 WATER

The Contractor shall pay for and shall provide for all facilities necessary to furnish water for its use during construction. Water used for human consumption shall be kept free from contamination and shall conform to the requirements of the state and local authorities for potable water. The Contractor shall pay for all water used for the Contractor's operations prior to final acceptance. The Contractor shall be responsible for obtaining a City water meter and paying all associated charges, including monthly water usage.

The Contractor is hereby informed that Carson City does not allow use of potable water for dust control on unpaved areas and/or earthwork compaction except for health safety concerns as determined by NDEP. The Contractor must obtain a "Treated Wastewater Effluent for Construction Purposes Permit" from the Carson City Wastewater Treatment Plant located at 3320 E. Fifth Street, Carson City. Special arrangements must be made with the Carson City Water Utility located at 3505 Butti Way, Carson City, for use of potable water for dust control on paved areas.

7.2.3 TEMPORARY LIGHTING

The Contractor shall provide temporary lighting in all work areas sufficient to maintain a lighting level during working hours not less than the lighting level required by OSHA standards. As permanent lighting facilities are completed they may be used in lieu of temporary facilities, provided however, that bulbs, lamps, or tubes of such facilities used by the Contractor shall be replaced prior to final acceptance of the Work.

7.2.4 HEATING AND VENTILATION

The Contractor shall provide means for heating and ventilating all work areas as may be required to protect the Work from damage by freezing, high temperatures, weather, or to provide a safe environment for workers. Unvented direct fired heaters shall not be used in areas where freshly placed concrete will be exposed to the combustion gases until at least two hours after the concrete has attained its initial set.

7.2.5 SANITARY CONVENIENCES

The Contractor shall provide suitable and adequate sanitary conveniences for the use of all persons at the site of the Work. Such conveniences shall include chemical toilets or water closets and shall be located at an appropriate location at the site of the Work. All sanitary conveniences shall conform to the regulations of the public authority having jurisdiction over such matters. At the completion of the Work, all such sanitary conveniences shall be removed and the site left in a sanitary condition.

7.2.6 COMMUNICATIONS

The Contractor shall provide, at its own cost, telephone communications to the Project Site either through ground lines or cellular equipment.

GENERAL CONDITIONS

7.2.7 CONSTRUCTION FACILITIES

Construction hoists, elevators, scaffolds, stages, shoring, and similar temporary facilities shall be of ample size and capacity to adequately support and move the loads to which they will be subjected. Railings, enclosures, safety devices, and controls required by law or for adequate protection of life and property shall be provided.

A. Staging and Falsework

Temporary supports shall be designed by a professional registered engineer with an adequate safety factor to assure adequate load bearing capability. If requested by the Construction Manager, the Contractor shall submit design calculations for staging and shoring prior to application of loads.

Excavation support shall be in accordance with GC 2.6.12 (D), Excavation Safety.

B. Temporary Enclosures

When sandblasting, spray painting, spraying of insulation, or other activities inconvenient or dangerous to property or the health of employees or the public are in progress, the area of activity shall be enclosed adequately to contain the dust, over-spray, or other hazard. In the event there are no permanent enclosures of the area, or such enclosures are incomplete or inadequate, the Contractor shall provide suitable temporary enclosures.

C. Warning Devices and Barricades

The Contractor shall adequately identify and guard all hazardous areas and conditions by visual warning devices and, where necessary, physical barriers. Such devices shall, as a minimum, conform to the requirements of OSHA and MUTCD.

D. Use of Explosives

All persons engaged in the activities of receiving, storing, using, handling or transporting any explosives must obtain a permit from the Carson City Fire Department; and all work shall be governed by Title 14, Fire, of the Carson City Municipal Code. The Contractor must notify the Construction Manager at least 14 days prior to the use of explosives.

GC 7.3 CONSTRUCTION CONTROLS

7.3.1 PROTECTION AND RESTORATION OF EXISTING IMPROVEMENTS

The Contractor shall not trespass upon private property and shall be responsible for the protection of public and private property at and adjacent to the Work and shall exercise due caution to avoid damage to such property.

The Contractor shall not infringe upon wetland areas at the Site, whether identified or not, without the written approval of the Construction Manager. Infringement on wetlands will give cause for suspension of all work being conducted on or adjacent to the wetland area.

In addition to any requirements imposed by law, the Contractor shall shore up, brace, underpin, and protect as may be necessary, all foundations and other parts of all existing structures adjacent to and adjoining the Site of the Work which are in any way affected by the excavations or other operations connected with the performance of the Work. Whenever any notice is required to be given to any adjacent or adjoining landowner or other party before commencement of any work, such notice shall be given in writing by the Contractor.

The Contractor shall repair or replace all existing improvements which are not designated for removal (e.g., curbs, sidewalks, survey points, fences, walls, signs, utility installations, pavements, structures, irrigation lines and facilities, etc.) and are damaged or removed as a result of its operations. Repairs and replacements shall be at least equal to existing improvements and shall match them in finish and dimension.

GENERAL CONDITIONS

Land survey monuments and property marks shall not be moved or otherwise disturbed by the Contractor until the Contractor arranges for a Nevada licensed Land Surveyor to witness or otherwise reference their locations in accordance with the requirements of the agency having jurisdiction. Any survey monument or property mark so moved or disturbed must be re-established and re-set by a Nevada licensed Land Surveyor in accordance with the requirements of the agency having jurisdiction.

Trees, lawns, and shrubbery that are not to be removed shall be protected from damage or injury. If damaged or removed because of the Contractor's operations, they shall be restored or replaced in as nearly the original conditions and location as is reasonably possible or better. Where existing turf areas are damaged, they must be replaced with fresh sod of matching grass.

The Contractor shall give reasonable notice, as determined by the Construction Manager, to occupants or owners of adjacent property to permit them to salvage or relocate plants, trees, fences, sprinklers, and other improvements within the right-of-way which are designated for removal or would be destroyed because of the Work.

A. Flood Protection

During the construction period, the Contractor shall be responsible for any damage which may result from flooding, including any earthwork re-excavation or replacement that may be a result of flooding. The Contractor shall submit to the Construction Manager a flood control plan for trenching operations associated with the Work. The flood control plan shall describe the Contractor's plan for control and diversion of surface runoff and flood flows around trench and structure excavations, and the Contractor's action plan for protection of the work and Contractor's plant and equipment during flood events.

7.3.2 PROJECT SECURITY

The Contractor shall make adequate provision for the protection of the Work area against fire, theft, and vandalism, and for the protection of the public against exposure to injury. Contractor shall call the Carson City Sheriff's Department at 887-2008 or call 911 in the event of any public harassment or violence to any of the Contractor's or subcontractor's employees.

A. Fire Extinguisher

Sufficient number of fire extinguishers of the type and capacity required to protect the Work and ancillary facilities, shall be provided and maintained in readily accessible locations.

B. Temporary Fences

The Contractor shall enclose the site of the Work other than roadways with a fence or barricades adequate to protect the Work and temporary facilities against acts of theft, violence, or vandalism. Work within the roadway right-of-way shall be protected as provided for in the "Manual on Uniform Traffic Control Devices."

In the event all or a part of the site is to be permanently fenced, this permanent fence or a portion thereof may be built to serve for protection of the Work site, provided however, that any portions damaged or defaced shall be replaced prior to final acceptance.

Temporary openings in existing fences shall be protected to prevent intrusion by unauthorized persons. During night hours, weekends, holidays, and other times when no work is performed at the site, the Contractor shall provide temporary closures or guard service to protect such openings. Temporary openings shall be fenced when no longer necessary.

C. Graffiti Removal

The Contractor shall at all times keep all equipment, traffic control devices, materials, office trailers, storage facilities, the Work and the site free from graffiti. The Contractor shall remove all graffiti within 24 hours of notification by the Construction Manager. All expenses associated with graffiti removal shall be the responsibility of the Contractor.

GENERAL CONDITIONS

7.3.3 ACCESS ROADS

Access roads shall be maintained to all storage areas and other areas to which frequent access is required. Similar roads shall be maintained to all existing facilities on the site of the Work to provide access for delivery of material and for maintenance and operation. Where such temporary roads cross buried utilities that might be injured by the loads likely to be imposed, such utilities shall be adequately protected by steel plates or wood planking, or bridges shall be provided so that no loads shall discharge on such buried utilities.

7.3.4 NOISE ABATEMENT

Operations at the site shall be performed to minimize unnecessary noise. Special measures shall be taken to suppress noise during night hours. Noise levels due to construction activity shall not exceed the following levels:

Allowable Daytime Noise Levels as measured at the exterior of any given site shall be a noise level of not more than 75 dba Leq from the hours of 7:00 AM to 8:00 PM daily.

Allowable Nighttime Noise Levels as measured at the exterior of any site shall be a noise level of not more than 55 dba Leq from the hours of 8:00 PM to 7:00 AM daily.

Internal combustion engines used on the Work shall be equipped with a muffler of a type recommended by the manufacturer. No internal combustion engine shall be operated without said muffler.

7.3.5 WORKING HOURS

Construction shall be allowed only between the hours of seven (7:00) AM and four (4:00) PM Monday thru Friday (Normal Working Hours) unless otherwise specified in the Special Conditions.

The starting, fueling, maintenance of equipment, and delivery of equipment and materials, and placement or removal of traffic control devices is considered Construction and shall not be allowed outside of the Normal Working Hours. Requests for exceptions to these limitations shall be made in writing to the Construction Manager for consideration in non-sensitive, non-residential areas.

The Contractor may request to work outside the Normal Working Hours by submitting a written request to the Construction Manager at least seventy-two (72) hours in advance of the start of work outside the Normal Working Hours. Permission may or may not be granted by the Construction Manager, with hours noted by the Construction Manager. The Contractor shall be responsible for the costs of any inspection, testing, and additional administration incurred by the City, or its agents and representatives, for work by the Contractor outside the Normal Working Hours defined above, on weekdays in excess of eight (8) hours, or any work on weekends or holidays recognized by the City. Such costs shall be withheld from the succeeding monthly progress payment. Any work specifically required to be performed outside the Normal Working Hours as may be indicated in the Special Conditions, or work required by the Construction Manager, in writing, to be performed outside the Normal Working Hours, is excluded from withholding of payment.

7.3.6 DRAINAGE CONTROL / STORM WATER POLLUTION PREVENTION PLAN

In all construction operations, care shall be taken not to disturb existing drainage patterns whenever possible. Particular care shall be taken not to direct drainage water onto private property. Drainage water shall not be diverted to streets or drainage ways inadequate for the increased flow. Drainage means shall be provided to protect the Work and adjacent facilities from damage due to water from the site or due to altered drainage patterns from construction operations. Temporary provisions shall be made by the Contractor to insure the proper functioning of gutters, storm drain inlets, drainage ditches, culverts, irrigation ditches, and natural water courses. The Contractor shall provide water quality and erosion controls in accordance with the NDEP "Handbook of Best Management Practices" to prevent sedimentation runoff from the Site.

GENERAL CONDITIONS

The Contractor shall comply with the National Pollutant Discharge Elimination System (NPDES) regulations for storm water discharges from a construction site and the Stormwater General Permit NVR100000, State of Nevada, Division of Environmental Protection, General Permit. Preparation of a Storm Water Pollution Prevention Plan (SWPPP) and compliance with the permitting requirements shall be the Contractor's responsibility. The Contractor shall submit the required Notice of Intent (NOI) to the NDEP and comply with the SWPPP referenced above. The Contractor shall obtain any required Temporary Permits prior to any discharges. The Contractor shall submit any required Notification of Termination to the NDEP upon completion of construction and final site stabilization, and shall submit to the City copies of all records associated with the permitting requirements. Contractor must submit a copy of the SWPPP permit and plan to the Construction Manager prior to the start of work.

The Contractor shall be responsible for all costs associated with complying with the permit requirements, submitting any required NOI, preparing and complying with the SWPPP, revising the SWPPP, any required submittal of the Notification of Termination, any required discharge permit and any other related costs.

7.3.7 CONSTRUCTION CLEANING

The Contractor shall, at all times, keep property on which work is in progress and the adjacent property free from accumulations of waste material, rubbish, caused by his/her operations. All surplus material shall be removed from the site immediately after completion of the work causing the surplus materials. Spillage resulting from hauling operations along or across existing streets or roads shall be removed immediately by the Contractor. All gutters and roadside ditches shall be kept clean and free from obstructions. Daily cleanup of trash, paper, and small debris subject to movement with winds shall be required. **The Contractor shall reasonably clean the immediate Work Area on a daily basis to reduce risk of personal injury as well as fire hazard.**

7.3.8 DISPOSAL OF MATERIAL

Unless otherwise specified in the Special Conditions, the Contractor shall make his/her own arrangements for disposing of construction waste materials outside the Project Site and the Contractor shall pay any and all dump fees required, except as provided below. If the Contractor arranges to dispose of construction waste materials on private property, he/she shall first obtain written permission from the property owner on whose property the disposal is to be made in which the City is absolved from any and all liability and responsibility in connection with the disposal of such material on said property. A copy of said written permission must be delivered to the Construction Manager prior to starting disposal operations. When construction waste material is disposed of as above provided, the Contractor shall conform to all required codes and permits pertaining to grading, hauling, and filling of earth or other materials. The Contractor shall contact the City's Community Development Department and the Health Department concerning such codes and permits.

Disposal of all construction waste including but not limited to all pipe, concrete, manholes, pavement, building and excavated materials, and all other appurtenances shall be disposed of in a manner consistent with all local, State and Federal laws and guidelines. Any hazardous waste shall be disposed of at hazardous waste disposal sites that are permitted to accept such wastes. All disposal site locations shall be approved in writing by the Construction Manager. A copy of the disposal plans and any required permits must be delivered to the Construction Manager prior to starting disposal operations.

Asbestos Cement Pipe (ACP) removed from the Project shall be separated from other material, manifested and delivered to the Carson City Landfill. For manifest and disposal requirements prior to removal of any ACP the Contractor shall contact:

Mr. David Bruketta
Operations Manager- Environmental
Cellular phone at (775) 230-2782

ACP Manifests are valid for ten (10) days from date of issuance.

GENERAL CONDITIONS

Construction waste including but not limited to all pipe, concrete, manholes, pavement, building and excavated material, and all other appurtenances removed from the Project may be accepted free of charge at the Carson City Landfill if approved under the direction of the Construction Manager. A Landfill Disposal Form will be provided by the Carson City Inspector upon request by the Contractor. The Contractor or Contractor's agent will provide a Landfill Disposal Form, which must be signed, dated and timed by a Carson City Inspector, to the Landfill Attendant for a waiver of disposal fees for each separate load. The Contractor will pay the full disposal fee if no Landfill Disposal Form from Carson City is presented to the Landfill Attendant. Carson City will not reimburse the Contractor for disposal fees due to failure to comply with these conditions.

7.3.9 PARKING AND STORAGE AREAS

All stockpiled materials and parked equipment at the job site shall be located to avoid interference with private property and to prevent hazards to the public. Locations of stockpiles, parking areas, and equipment storage must be approved by the Construction Manager. Material and equipment may not be stored in public right-of-way unless prior approval by the Construction Manager.

GC 7.4 PUBLIC SAFETY/CONVENIENCE AND TRAFFIC CONTROL

The Contractor shall so conduct his/her operations as to offer the least possible obstruction and inconvenience to the general public, including the residents, businesses and any other contractors working in the vicinity of the Work, and he/she shall have under construction no greater length or amount of work than he/she can prosecute properly with due regard to the rights of the public. Convenient access to driveways, houses, and buildings along the line of work shall be maintained and temporary crossings shall be provided and maintained in good condition. Traffic shall not be prevented from accessing business. Maintain a minimum of one (1) access to each business property at all times. Business Access signs shall be used to direct business traffic. Not more than one (1) crossing or intersecting street or road shall be closed at any one time. Safe access must be maintained for pedestrian traffic through or around the work area at all times.

Inconvenience caused by digging across driveways and sidewalks shall be kept to a minimum by restoring the serviceability of the driveway or sidewalk as soon as possible. Contractor shall provide and identify to the Construction Manager a person to act as a community liaison person, who must be fluent in English with good communication skills, to personally contact each resident and business at least three (3) working days prior to performing any Work which effects their sewer or water service, restricts on street parking, restricts access to their property, or blocks a driveway or sidewalk. Said community liaison person shall provide written notices, pre-approved by the Construction Manager, to all such residents and businesses and must be available and able to answer their questions. Copies of notices to all properties other than single family residences provided to the Construction Manager shall include a name and signature of the person accepting the notice for those properties. The Contractor shall make every effort to provide alternate access to the property during such closure, if at all possible. The Contractor shall replace or repair any damage done to driveways or sidewalks and shall provide temporary relief in the form of steel plates and supports of adequate strength over the excavation. Access to properties must be restored during all non-working hours.

Direct access shall be provided at all times to fire stations, fire hydrants, hospitals, police stations and at all other agencies or services where emergencies may require immediate access to same.

Temporary paving replacement in front of business establishments shall be placed immediately following backfill and shall remain in place until the condition of the backfill is suitable for permanent pavement replacement.

No streets or roads shall be blocked or made inaccessible, due to the Contractor's work, without approval of the City. No open excavations shall be allowed during non-working hours. Excavations shall be backfilled to grade and, if in a pavement area, temporarily paved level with adjacent pavement or, with the prior approval of the Construction Manager, covered with steel plates during non-working hours. If temporary paving and/or maintenance of temporary paving of all disturbed streets, driveways and sidewalks is not completed prior to the end of each work day, the Construction Manager may suspend the Work on the entire project, without any additional costs to the City, until the temporary paving is completed and/or properly maintained. The Construction Manager shall be the judge of proper maintenance of the temporary paving.

GENERAL CONDITIONS

If needed, the City will provide the Contractor with "Temporary No Parking" signs to be posted in the construction area by the Contractor to accommodate each day's work. The Contractor must post the "Temporary No Parking" signs in the construction area no less than seventy-two (72) hours prior to the effective start of such parking restrictions. Temporary No Parking hours are to conform to the Contractor's Working hours, but in no instance shall they exceed the Working Hours as specified in GC 7.3.5 or as amended in the Special Conditions. Contractor must keep a log of day, date, time and location that the signs are posted. If, when work starts, vehicles are parked in violation of the posted restrictions, the Contractor shall call the Carson City Sheriff's Office Dispatch Center at 887-2008 to request that the violating vehicle(s) be towed. Contractor shall identify expected no parking areas on the Traffic Control Plan and shall notify the Construction Manager at least one (1) week prior to the need for the "Temporary No Parking" signs.

7.4.1 HAUL ROUTES

Prior to hauling, the Contractor shall submit for approval the proposed route(s) for all construction traffic on the Project. This shall include any designated routes, if any, shown on the Contract Drawings. Upon approval, the Contractor shall adhere to approved routes only.

7.4.2 TRAFFIC CONTROL

During construction within traffic roadways the Contractor shall maintain no less than one (1) lane of traffic during working hours and two (2) lanes at all other times. When one-way traffic is in effect, the Contractor shall employ no less than two (2) flaggers to facilitate the safe flow of traffic. No streets or roads shall be blocked, closed or made inaccessible due to the Contractor's work, without the prior approval of the Construction Manager.

The Contractor shall provide and maintain traffic control devices such as signs, warning lights, reflectors, barriers, fences, flaggers, steel plates, barricades, light signs and other necessary safety devices and measures on all sides of the construction zone, the number, size, message and spacing of which shall be governed by the Traffic Control Plans, local ordinance, or permit requirements. Traffic control shall be in accordance with the MUTCD. Any Traffic Control for work within NDOT right-of-way shall be in accordance with the NDOT permit requirements. The Contractor shall submit for approval by the City and any other applicable agency, its traffic control plans at least two (2) weeks prior to beginning work on public streets in accordance with GC 4.0, SHOP DRAWINGS AND QUALITY CONTROL.

The Contractor shall designate a Traffic Control Supervisor who shall be responsible for preparing and signing all Traffic Control Plans, and for installing and maintaining all traffic control devices as shown on the approved Traffic Control Plans. Said Traffic Control Plans must be per the provisions of the MUTCD and any Special Conditions. The Traffic Control Supervisor shall be available to be contacted by the Construction Manager twenty-four (24) hours per day for the duration of the Contract. The Traffic Control supervisor must be certified as a worksite traffic supervisor by ATSSA. As a minimum, the Traffic Control Supervisor shall check all traffic control devices at the start, mid-day, and end of each work day and at least once on every non-working day.

In addition to the flaggers required above, the Contractor shall employ flaggers at places designated by the Construction Manager for the safe movement of the public through the Work area. Flaggers shall possess a valid flagger card attesting that they have satisfactorily completed an instructional course in flagger procedures conducted by NDOT or some other approved course given by another entity of government within the State of Nevada.

No material or equipment shall be stored or parked where it will interfere with the free and safe passage of public traffic, and at the end of each day's work, and at other times when construction operations are suspended for any reason, the Contractor shall remove all materials, equipment and other obstructions from the public right-of-way. With the prior approval of the Construction Manager, the Contractor may shield the public traffic from materials or equipment within the public right-of-way by the use of temporary concrete or water filled barrier rails.

The Contractor shall notify the Carson City Fire Department and Sheriff Department dispatch center at (775) 887-2008 at least twenty-four (24) hours in advance of rerouting public traffic when traffic patterns

GENERAL CONDITIONS

are to be altered due to construction operations. Said notification shall set forth the specific traffic patterns to be provided in lieu of the normal routing and the estimated duration of such change(s).

Should the Contractor appear to be negligent in furnishing or maintaining warning and protective measures, as above provided, the Construction Manager may direct attention to the existence of the hazard, and the necessary warning and protective measures shall be immediately furnished and installed by the Contractor at its expense. Failure to do so will be cause to suspend the Work until the deficiency is corrected. If the Contractor does not correct a Traffic Control deficiency by the end of the work day and the Construction Manager determines that the public safety is endangered, then the Construction Manager may take the necessary action to correct the deficiency pursuant to GC 2.5.4, City's Right to Carry Out the Work.

7.4.3 TRAFFIC DETOURS

Detouring traffic to private streets shall not be allowed. Advance warning/detour signs shall be used to direct through-traffic, and shall be placed to notify traffic to avoid all possible situations that require individual motorists to turn around to avoid the closure. The advanced warning signs shall be placed in accordance with the approved Traffic Control Plan. No detour or street closure signing shall be placed on any street prior to the start of Work hours and shall be removed prior to the end of Work hours unless otherwise provided in the approved Traffic Control Plan.

7.4.4 PEDESTRIAN AND BICYCLE DETOURS

Advanced warning/detour signs shall be placed to notify pedestrian and bicycle traffic of any closure and to avoid all possible situations that may require individuals to turn around to avoid the closure.

GC 7.5 PROJECT SIGNS

If required by Contract Special Conditions, the Contractor shall provide, install and maintain for the duration of the Project, Project sign(s). Two (2) signs shall be required for pipeline projects. The sign(s) shall be installed within fifteen (15) days of the Notice to Proceed and shall be installed where directed by the Construction Manager. The Project Sign(s) shall conform to the requirements listed in the Special Conditions.

GC 7.6 PROJECT OFFICE

Unless the Contractor has an office in the Carson City/Reno/Sparks area, the Contractor shall maintain a suitable office on the Project site. The Contractor shall maintain at the Project site copies of the Contract Documents, record drawings, Project schedule, submittals, permits, Material Safety Data Sheets, approved Traffic Control Plans, and other relevant documents which shall be accessible to the Construction Manager and other City representatives during normal working hours. Said site office shall be the headquarters of the Contractor's representative authorized to receive Drawings, instructions, or other communications or articles from the City or its agents unless the Contractor notifies the City otherwise per GC 2.6.1, Office.

GC 7.7 STORAGE OF MATERIALS

Materials shall be stored in such a manner as to ensure the preservation of their quality and fitness for the Work. When required by the Construction Manager, materials shall be placed on platforms or other hard, clean surfaces and covered.

Materials shall be stored so as to facilitate inspection. Storage areas shall be suitably fenced if necessary to protect the public or the material.

Locations and arrangements for storage sites for materials and equipment outside the limits of work, shall be selected and maintained by the Contractor at the Contractor's expense. Prior to occupying a storage site on private property, the Contractor shall submit a letter or agreement signed by the private property owner that authorizes the Contractor to occupy the private property. The City shall be specifically exempted in any agreement from any liability incurred from the use of private property for construction purposes. Use of portions of the City's area at the site for materials and equipment storage shall be permitted upon the approval of the Construction Manager.

GENERAL CONDITIONS

GC 7.8 HAZARDOUS MATERIALS

The storage and handling of potential pollution-causing and hazardous materials, including but not necessarily limited to: gasoline, oil, and paint shall be in accordance with all local, state, and federal requirements. All hazardous materials shall be stored and handled in accordance with the Material Safety Data Sheets for the products. Material Safety Data Sheets shall be submitted to the Construction Manager prior to the delivery of materials to the Project site. Copies of the Material Safety Data Sheets shall be maintained at the Project Site in a readily accessible location.

GC 7.9 SYSTEM TESTING

The Contractor shall test the facilities as specified in the Technical Specifications. The Contractor shall provide all other necessary facilities for conducting the tests including but not limited to: personnel, power, water, equipment, and chemicals. The Contractor shall provide a minimum of forty-eight (48) hours notice to the Construction Manager of its readiness and intent prior to each test.

GC 7.10 COORDINATION/COOPERATION WITH UTILITIES

Within the construction limits of this Project may be various utility systems including water, reclaimed water, sanitary sewers, storm drains, gas, telephone, cable television, and electric power. The approximate location of known main line utilities, as taken from existing records, is shown on the Drawings. The service connections to these facilities may not be shown on the Drawings, however, the Contractor shall field locate and protect all service connections from damage during the course of the Work. The full costs for locating and protecting such service connections shall be included in the various items of work and no additional compensation shall be allowed. Where underground main utility distribution lines are shown on the plans or marked in the field, the Contractor shall assume that every property parcel is served by service connections for each type of utility. The City and Engineer do not guarantee that all existing utilities and facilities are shown on the Drawings or that they are shown in their actual position. The Contractor shall consider it normal and expected that the elevation and alignment of said utilities may vary from that shown on the Drawings, and also that utilities may be encountered that are not shown on the Drawings. Also consider it normal and expected that utilities will prove to be an impediment to the operations and that use of other than the usual equipment and construction methods in accomplishing the necessary work over, around or under such utility installations may be necessary. Should a discrepancy be found on the Drawings, it shall not be construed to relieve the Contractor from his/her responsibility to protect any such utility or facility.

The City has notified all utility companies, all pipeline owners, or other parties known to be affected by the Project and has endeavored to have all necessary adjustments of their facilities and other appurtenances made as soon as possible to eliminate conflicts within or adjacent to the limits of construction. The Contractor shall be responsible to protect and/or support all utilities which do not have to be relocated, but which do affect the Work. Where the City has made arrangements with utility owners to relocate or adjust their facilities, the City's responsibility for such adjustments are shown on and called out at the specific locations on the plans.

Any delays to the Contractor's operations performing the current critical item(s) of work on the latest favorably reviewed Construction Schedules as a direct result of utility or other facilities not being rearranged as herein provided (other than delays in connection with rearrangements made to facilitate Contractor's construction operations) will be considered excusable delays within the meaning of GC 3.12.2, Excusable Delays.

It shall be the Contractor's full responsibility to call Underground Service Alert (USA) at (1-800-227-2600) not less than two (2) working days, but not more than fourteen (14) calendar days, prior to performing any excavation, for location mark-out of any underground utilities and obtaining an inquiry identification number. Contractor must comply with all instructions received from USA.

Note: Per NRS 455.082, the approximate location of a subsurface installation marked in response to a notice to USA means a strip of land not more than twenty-four (24) inches on either side of the exterior surface of a subsurface installation.

If a private underground utility such as gas, electric, telephone or cable television facility must be located or adjusted for construction operations and its location differs by more than twenty-four (24) inches on either side of the exterior surface of the subsurface facility from that shown on the plans or marked in the field, the City shall

GENERAL CONDITIONS

reimburse the Contractor, as extra work, for the difference between the costs incurred in finding the actual location of the facility and the costs of finding the reputed location of the facility.

Contractor shall pothole all indicated, shown, or marked utilities and points of connection to verify their exact location. The Contractor shall have the proposed Work laid out in the filed by a Nevada Licensed Professional Land Surveyor or the Surveyor's subordinates prior to commencing with the potholing. The Contractor shall then pothole prior to performing any other Work including saw cutting for the work. The Contractor shall obtain data (on a form provided by the Construction Manager) to include type, size, and dimensions, material, location and elevation of the underground utilities, referenced to the Surveyor's lay out stakes for each pothole. The Contractor shall provide to the Construction Manager, all data, and shall identify to the Construction Manager any facilities which conflict with the Work on the day the pothole is performed. Carson City will not be responsible for any damages, delays or standby time caused by the Contractor's failure to perform potholing prior to commencement of the Work, failure to provide the data or identify the conflicts when specified, or failure to locate services, laterals or points of connections.

Carson City will be responsible for repairs, damages and standby time caused the Contractor due to non-marking, mis-marking or mis-locating, as defined in NRS 455.082, of the City's main line water mains, reclaimed water mains, sanitary sewer main lines and storm drains. Compensation to the Contractor for such repairs, damages or standby time shall be calculated on the basis of GC 6.4.3, Force Account Payment. NOTE: This provision does not apply to service laterals/connections unless the Contractor can show he/she used diligence in trying to locate each service.

The Contractor shall not interrupt the service function or disturb the support of any utility without authority from the utility owner. All valves, switches, manholes, vaults, and meters shall be maintained readily accessible for emergency shutoff or access. In case it should be necessary to move or temporarily maintain the property of any utility, the cost of which is not required to be borne by the owner thereof, the Contractor shall bear all time required and all expenses incidental to the removal or temporary maintenance of such property in a manner satisfactory to the owner thereof. The work necessary to the raising, lowering, or relocating of a utility may be done by the owner of the utility or by the Contractor, at the option of the utility owner. All work shall be in accordance with the utility owner's standards, and shall be at the Contractor's time and expense unless otherwise expressly provided for in the Special Conditions.

The Contractor shall repair or replace all utilities damaged or destroyed due to his/her operations, even in the event such damage or destruction occurs after backfilling or is not discovered until after completion of backfilling. The Contractor shall resolve all crossing and clearance problems with the utility company concerned and the Construction Manager. The right is reserved to the State, County, City, and owners of private utilities and franchises to enter at any time upon any street, alley, right-of-way, or easement for the purpose of making changes in their property made necessary by the Work and for the purpose of maintaining and making repairs to their property.

In cases where water or sewer mains, or service connections thereto, are accidentally broken or, with the prior approval of the Construction Manager, are intentionally cut by the Contractor, they shall be fully repaired to City specifications and returned to service within four (4) hours, or sooner if deemed necessary by the Construction Manager. The Contractor is to make these repairs a priority over other portions of the Work.

At all times allow the Fire Department access to fire hydrants. Do not place materials or other obstructions closer to a fire hydrant than permitted by ordinance, rules, or regulations or within fifteen (15) feet of the fire hydrant in the absence of such ordinances, rules, or regulations.

GC 7.11 CONTAMINATED GROUNDWATER and/or SOIL

Contaminated groundwater and/or soil may exist anywhere within the Project limits. If contaminated groundwater and/or soil are encountered during construction, the Contractor must act in accordance with all applicable Federal, State, and local laws and Nevada Administrative Code 445A.347, which requires the Nevada Department of Environmental Protection be notified within twenty-four (24) hours of the encounter at (775) 687-4670.

GENERAL CONDITIONS

GC 7.12 DUST CONTROL

The Contractor is responsible for the control of dust originating from any and all of the Contractor's construction operations either within or outside of the Work Area at all times in accordance with Federal, State and local laws, at the Contractor's expense. In areas where fugitive dust is a nuisance, the Contractor shall, as often as necessary, wet down the area to prevent dusty conditions. This includes weekends and holidays. The Contractor shall contact NDEP to determine if a Ground Disturbance Permit is required.

GC 7.13 BY-PASS PUMPING OF SANITARY SEWER

The Contractor shall prepare and submit to the Construction Manager a plan for by-pass pumping of sanitary sewers which will provide for adequate size pumps and hoses to carry the flows from one manhole to another. Hoses must be rated for traffic if traffic is allowed on the roadway where the hose is placed. Provide a backup pump, replacement hose sections and a backup power source at the work site prior to commencing any by-pass pumping operations. Contractor must test the by-pass pumping system, including the backup pump, in the presence of the Construction Manager or his/her representative prior to effecting the flow in the existing sanitary sewer to be diverted. Contractor must identify and have available during pumping operations a person capable and qualified to make emergency repairs in case of a failure of any part of the by-pass pumping operation. The Contractor shall ensure that no spillage of raw sewage will occur on or in the ground. The by-pass pumping plan shall also address how an accidental spill of raw sewage would be contained and mitigated.

GENERAL CONDITIONS

SECTION 8.0 CONTRACT COMPLETION, O&M MANUALS

GC 8.1 INTERMEDIATE COMPLETION

When an intermediate milestone is specified in the Contract Documents, and the Contractor considers that a Work element, section, or division has met the intermediate completion stage requirements, the Contractor shall notify the Construction Manager in writing. Upon receipt of the notification, the Construction Manager and the City will make inspection to determine if the Work element, section or division is sufficiently complete in accordance with the Contract Documents to determine its acceptability for Intermediate Completion and for determination of any other items which do not meet the terms of the Contract so the City can occupy or utilize the Work for its intended use. Upon verification that the Work element, section, or division meets the contractual requirements for Intermediate Completion, the Construction Manager shall prepare a Notice of Intermediate Completion letter for the City's signature. The notice shall establish the date of Intermediate Completion, the responsibilities of the City and Contractor for maintenance, utilities, and damage to the subject Work. If items are found which prevent such use or occupancy, the Construction Manager shall notify the Contractor of such items.

Upon the completion of such corrective work, the Contractor shall so notify the Construction Manager in writing. The Contractor agrees to pay the City's actual costs including, but not limited to, charges for engineering, inspection and administration incurred due to the Contractor's failure to complete the punch list work within the time period specified.

Unless otherwise specified under Special Conditions, no partial acceptance of any portion of the Work will be made and no acceptance other than the final acceptance of the overall completed Project will be made. No review pertaining to specific parts of the Project shall be construed as final acceptance of any part until the overall final acceptance by the City is made. Final payment for completed portions of Work will not be made until final acceptance of the total Work.

GC 8.2 SUBSTANTIAL COMPLETION

When the Contractor considers that all Work required by this Contract including equipment start-up and testing is substantially complete, the Contractor shall notify the Construction Manager in writing. Upon receipt of the notification, the Construction Manager and the City will make inspection to determine if the Work is sufficiently complete in accordance with the Contract Documents to determine its acceptability for Substantial Completion and for determination of any other items which do not meet the terms of the Contract so the City can occupy or utilize the Work for its intended use. If items are found which prevent such use or occupancy, the Construction Manager shall notify the Contractor of such items. Upon verification that the Project is substantially complete, the Construction Manager shall prepare a Notice of Substantial Completion letter for the City's signature. The notice shall establish the date of Substantial Completion and the responsibilities of the City and Contractor for maintenance, utilities, and damage to the Work.

GC 8.3 CONSTRUCTION COMPLETION, FINAL INSPECTION, PAYMENT, AND ACCEPTANCE

When the Contractor considers that all Work including record drawings, operation and maintenance manuals, and cleanup has been completed in accordance with the terms of the Contract, the Contractor shall notify the Construction Manager. Upon notification, the Construction Manager and the City will make the pre-final inspection to determine the actual status of the Work in accordance with the terms of the Contract. If materials, equipment, or workmanship are found which do not meet the terms of the Contract, the Construction Manager shall prepare a final punch list of such items and submit it to the Contractor. Following completion by the Contractor of the corrective work, required by the punch list, the Construction Manager shall notify the City that the Work has been completed in accordance with the Contract. A final inspection will be made to determine the acceptability of the Work. After completion of the Work, but prior to its acceptance by the City, the last partial payment will be made to the Contractor.

After receipt of the last partial payment, but prior to acceptance of the Work by the Carson City Board of Supervisors or Carson City Regional Transportation Commission, the Contractor shall send a letter to the Construction Manager submitting lien releases for all material, or labor for any work covered by this Contract. The letter shall state that acceptance of the final payment described below shall operate as and shall be, a release to the City, the Construction Manager, the Design Consultant, and their duly authorized agents, from all claims

GENERAL CONDITIONS

and/or liability to the Contract arising by virtue of the Contract related to those amounts. Disputed Contract claims in stated amounts previously filed as provided in GC 6.3.2, Claims, may be specifically excluded by the Contractor from the operation of the release.

Following receipt of all required submittals, the Construction Manager's written statement that construction is complete, and recommendation from the City's representative to accept the Project, the Construction Manager shall prepare an agenda item for the Carson City Board of Supervisor's or Carson City Regional Transportation Commission's acceptance of the completed Work and a Notice of Completion.

Following the acceptance by the Carson City Board of Supervisors or the Carson City Regional Transportation Commission of the completed Work embraced in the Contract, the City will cause to be recorded in the office of the County Recorder a Notice of Completion.

Thirty (30) days after recording the Notice of Completion of the Work involved in the Contract, the City will pay the Contractor such sums of money as may be due the Contractor including all sums retained but excluding such sums as have previously been paid the Contractor. This payment will constitute the final payment to the Contractor under this Contract.

GC 8.4 OPERATION AND MAINTENANCE MANUALS

Prior to the delivery and installation of any item of machinery or equipment, the Contractor shall submit one (1) copy of the Operation and Maintenance Manual(s) as required by the Technical Specifications. The manual(s) will be reviewed by the Construction Manager and/or Design Consultant for content and the Construction Manager will advise the Contractor within five (5) working days of receipt if the manual is acceptable for the delivery and installation of the equipment or machinery. No equipment or machinery shall be tested or installed if the general content of the manual is found to be deficient. The final Operation and Maintenance Manuals, three (3) copies, must be submitted and favorably reviewed prior to final acceptance.

GC 8.5 EQUIPMENT START-UP

After all acceptance tests have been completed by the Contractor, but prior to final acceptance, the Contractor shall recheck all equipment for proper alignment and adjustment, check oil levels, relubricate all bearing and wearing points, and assure that all equipment is in proper condition for regular continuous operation. Final start-up of equipment requires forty-eight (48) hours advance notice to the Construction Manager and coordination with the user department of the City. Start-ups shall only occur Monday through Thursday.

GC 8.6 FINAL CLEAN UP

At the completion of the Work and before final inspection, the Contractor shall clean the Work Area, material sites, adjacent property and streets and all grounds occupied by the Contractor in connection with the Work of all rubbish, excess and waste materials, as well as all his/her tools, construction equipment, machinery and temporary facilities. All parts of the Work shall be left in a neat and clean condition. If the Contractor fails to clean up at the completion of the Work, the City may do so and the cost shall be charged to the Contractor.

GC 8.7 WARRANTY OF TITLE

No material, supplies, or equipment for the Work under this Contract shall be purchased subject to any chattel mortgage, security agreement, or under a conditional sale or other agreement by which an interest therein or any part thereof is retained by the seller or supplier. The Contractor warrants clear title to all material, supplies, and equipment installed or incorporated in the Work and agrees upon completion of all work to deliver the premises, together with all improvements and appurtenances constructed or placed thereon by the Contractor, to the City free from any claim, liens, security interest, or charges, and further agrees that neither the Contractor nor any person, firm, or corporation furnishing any materials or labor for any work covered by this Contract shall have any claims, liens, security interests or charges against this Project, provided that this shall not preclude the Contractor from installing metering devices or other equipment of utility companies, the title of which is commonly retained by the utility company. Nothing contained in this Section, however, shall defeat or impair the right of such persons furnishing materials or labor under any bond given by the Contractor for their protection or any right under any law permitting such persons to look to funds due the Contractor in the hands of the City. The provisions of this Section shall be inserted in all subcontracts and material contracts, and notices of its provisions shall be given to all persons furnishing materials for the work when no formal contract is entered into for such materials.

GENERAL CONDITIONS

GC 8.8 RECORD DRAWINGS

The Contractor shall keep at the Site a copy of the Contract drawings and specifications, including addenda and change orders, to which the Design Consultant, Construction Manager, and City shall have access at all times.

The Contractor shall maintain one (1) set of specifications and full size drawing prints and mark thereon in red any and all deviations from plan dimensions, elevations, or orientations, and all changes from addenda, change orders, and clarifications. Marked prints shall be updated at least weekly and shall be available to the City for review. Prior to Final

Acceptance by the City, the Contractor shall submit the record Drawings to the Construction Manager in the manner and format specified in the Special Conditions.

GC 8.9 WARRANTY

The Contractor hereby agrees to make, at its own expense, all repairs or removals and replacements necessitated by defects in materials or workmanship supplied under the terms of this Contract, and to pay for any damage to other works resulting from repairs or removals and replacements of such defects which become evident within one (1) year after the date of Substantial Completion of the Project by Carson City or within such longer period of time as may be prescribed by law or by the terms of any applicable technical specification. The Contractor further assumes responsibility for a similar guarantee for all work and materials provided by subcontractors or manufacturers of packaged equipment components. The Contractor also agrees to indemnify, defend, and hold the City, and its officers, agents, employees, and volunteers harmless from liability of any kind arising from damage due to said defects.

The Contractor shall execute and submit a completed Warranty Form in the format as appended to this section for the Work. The Warranty Form shall be submitted prior to the final acceptance of the Project or within five (5) days of the occupancy or use of a portion of the Work, whichever is applicable.

The Contractor shall, upon the receipt of written notice from the City, promptly make all repairs or removals and replacements arising out of defective materials, workmanship, or equipment. The City is hereby authorized to make such repairs or removals and replacements, and the Contractor and its Surety shall be liable for the cost thereof, if five (5) days after receipt of such written notice to the Contractor, the Contractor has failed to make or undertake the repairs or removals and replacements with due diligence. In case of emergency, where in the opinion of the City delay could cause serious loss or damage, repairs or removals and replacements may be made without notice being sent to the Contractor, and the expense in connection therewith shall be charged to the Contractor, and its Surety shall be liable for the cost thereof. Such action by the City shall not relieve the Contractor of the guarantees required by this Section or elsewhere in the Contract Documents.

This Section does not in any way limit the warranty on any items for which a longer warranty is specified or on any items for which a manufacturer or supplier gives a warranty for a longer period. The Contractor agrees to act as a co-guarantor with such manufacturer or supplier and shall furnish the City all appropriate guarantee or warranty certificates upon completion of the Work. No warranty period, whether provided for in this Section or elsewhere, shall in any way limit the liability of the Contractor or his/her sureties or insurers under the indemnity or insurance provisions of these General Conditions.

Prior to the expiration of the Warranty period, the City reserves the right to hold a meeting with the Contractor. The purpose of the meeting would be to review warranties, bonds, and maintenance requirements and determine required repair or replacement requirements of defective items.

For the purpose of this paragraph, acceptance of the Work or a portion of the Work by the City, shall not extinguish any covenant or agreement on the part of the Contractor to be performed or fulfilled under this Contract which has not, in fact, been performed or fulfilled at the time of such acceptance. All covenants and agreements shall continue to be binding on the Contractor until they have been fulfilled.

GENERAL CONDITIONS

WARRANTY FORM

Warranty For

_____ (Project/Component)

_____ (Location)

We hereby guarantee the _____ (Project/Component) _____ that we have constructed for a period of one (1) year from _____ (Date) _____ the date of Substantial Completion of the Work set by Carson City.

The following items are excluded from the provisions of this warranty:

We agree that if any of the material or equipment should fail due to any reason other than improper maintenance or improper operation, if any pipe or appurtenances should develop leakage, or if any settlement of fill or backfill occurs, or should any portion of the Work fail to fulfill any of the requirements of the Contract Documents, we will, within five (5) days of receipt of written notice of such defects, commence to repair or replace the same together with any other work which may be damaged or displaced in so doing.

In the event of our failure to comply with the above mentioned conditions within a reasonable time after being notified, or should the urgency of the case require repairs or replacements to be made before we can be notified or respond to notification, we do hereby authorize Carson City, to proceed to have the defect repaired and made good at our expense, and we will pay the cost therefor upon demand.

The warranty provided herein shall not be in lieu of, but shall be in addition to any warranties or other obligations otherwise imposed by the Contract Documents and by law.

Contractor:

Signed:

Title:

Date:

GENERAL CONDITIONS

SECTION 9.0 PREVAILING WAGE

GC 9.1 PREVAILING WAGE RATES

- A. The Contractor and subcontractors shall be bound by and comply with all federal, state and local laws with regard to minimum wages, overtime work, hiring and discrimination, including Chapter 338 of the NRS, which is entitled, "Public Works Projects." The Contractor shall ensure that all employees on the work site are paid in accordance with the CURRENT PREVAILING WAGE RATES AS APPROVED BY THE STATE LABOR COMMISSIONER, whenever the actual value of the Contract totals One Hundred Thousand Dollars (\$100,000) or more, or when required by the Special Conditions. A copy of the rates are attached hereto and included herein. If a Change Order causes a Contract to exceed One Hundred Thousand Dollars (\$100,000), the State Labor Commissioner may audit the entire Contract period.

When federal money is associated with the project making the Contract subject to both state and federal wage rates, the Contractor shall not pay less than the higher rate when the two rates differ for similar kinds of labor.

Questions involving the Prevailing Wage Rates for Carson City should be referred to the Labor Commissioner, State of Nevada, at (775)687-4850.

- B. Posting of Minimum Wage Rates - In accordance with NRS, Chapter 338, Section 338.020, the Contractor shall post the hourly and daily rate of wages to be paid to each of the classes of mechanics and workers on the site of Work of this Contract in a place generally visible to the workers.
- C. Pursuant to NRS 338.060 and 338.070, the Contractor hereby agrees to forfeit, as a penalty to the City, not less than Twenty Dollars (\$20) nor more than Fifty Dollars (\$50) for each calendar day or portion thereof that each worker employed on the Contract is paid less than the designated rate for any work done under the Contract, by the Contractor or any subcontractor under him/her, or is not reported to the City as required by NRS 338.070.
- D. The Contractor and each subcontractor shall keep or cause to be kept an accurate record showing the name, the occupation and the actual per diem, wages and benefits paid to each worker employed by him/her in connection with the public Work. The General Contractor shall collect the wage reports from the Sub-Contractors and ensure the receipt of a certified copy of each weekly payroll for submission to the City as one complete package.
- E. The record must be open at all reasonable hours to the inspection of the City, and its officers and agents. A copy of the record for each calendar week for the General Contractor and all Sub-Contractors must be sent to the City by the General Contractor no later than one (1) week after the end of the week. The copy must be open to public inspection as provided in NRS 239.010.
- F. The Contractor and all subcontractors hereby agree not to hinder on-site interviews of the Contractor's or subcontractor's workers by the Construction Manager or his/her representative to verify that the workers are being paid the prevailing wage rates.
- G. It is unlawful for any Contractor in connection with the performance of work under a contract with the state, or any of its political subdivisions, when payment of the Contract Price, or any part of such payment, is to be made from public funds, to refuse to employ or to discharge from employment any person because of his/her race, color, creed, national origin, sex, sexual preference or age, or to discriminate against a person with respect to hire, tenure, advancement, compensation or other terms, conditions or privileges of employment because of his/her race, creed, color, national origin, sex, sexual preference or age. The Contractor agrees to insert this

GENERAL CONDITIONS

provision in all subcontracts hereunder except subcontracts for standard commercial supplies or raw materials.

GC 9.2 NO EXTRA COMPENSATION

All work necessary to be performed after regular working hours, on Sundays or Legal Holidays, shall be performed without additional expense to the City. In case of extra work under the provisions of GC 6.4, MODIFICATION PROCEDURES, no additional payment will be made to the Contractor because of the payment by him/her of overtime wage rates for such work unless the use of overtime work in connection with such extra work is specifically ordered in writing by the City.

END OF GENERAL CONDITIONS

SPECIAL CONDITIONS

These Special Conditions amend or supplement the Standard Terms and Conditions and General Conditions of the Contract and add other Special Conditions to the contract document as indicated below, and amend or supplement the Technical Specifications. All provisions of the Contract which are not so amended or supplemented remain in full force and effect.

SC.1 SCOPE OF WORK

The Clear Creek Sanitary Sewer Extension Project consists of constructing approximately 2,500 lineal feet of sewer line, 1700 lineal feet of storm sewer, and 700 lineal feet of water line, as well as their associated appurtenances. This project also includes pulverizing the existing road and placing approximately 64,000 square feet of new asphalt, as well as curb and gutter, sidewalk, driveway aprons, spandrel and valley gutter, and pedestrian curb ramps.

SC.2 AMENDMENTS TO CONTRACT AWARD

CA. 10 Notice to Proceed

Replace entire paragraph with the following:

Within ten (10) calendar days of receipt of all required post-bid documents and information, including bonds, insurances, executed Contract, schedule of values and approved project construction schedule, the City will issue the Notice to Proceed.

CA. 11 Time: Completion of Project

A. Time

Change "calendar days" to "working days"

B. Liquidated Damages

Change "calendar days" to "working days"

SC.3 AMENDMENTS TO GENERAL CONDITIONS

The following provisions amend or supplement the General Conditions of the Contract. All provisions of the Contract which are not so amended or supplemented shall remain in full force and effect.

SECTION 1.0 INTENT, DEFINITIONS, ABBREVIATIONS

GC 1.3 Governing Order of Bidding and Contract Documents

Add the following to the end of the ninth order of precedence (standard specifications):
Revision No. 6 dated 2-29-2012.

GC 1.5 Definitions

Revise "Contract Time" as follows:

Replace "calendar days" with "working days".

Revise "Standard Specifications" to add the following revision date:
Revision No. 6 dates 2-29-2012.

Revise "Working Day" to add the following revision date:

SPECIAL CONDITIONS

Replace the entire paragraph with the following:

Working Day- A calendar day on which weather and other conditions not under the control of the Contractor will permit construction operations to proceed for at least 5 hours of the day with at least seventy-five (75) percent of the normal working force engaged in performing the current critical item(s) of work on the latest favorably reviewed Construction Schedule, exclusive, however, of Friday, Saturdays, Sundays, City recognized holidays, and any day that is incumbent upon the Contractor, by means of a Master Labor Agreement, to observe as a holiday. However, if the Contractor elects to work on such days, those days will be considered as working days.

SECTION 2.0 CONTRACT ADMINISTRATION AND RESPONSIBILITIES: OWNER'S REPRESENTATIVE, CONSTRUCTION MANAGER, DESIGN CONSULTANT AND CONTRACTOR:

GC 2.6.9 Contractor's Responsibility for the Work and Materials

Add the following:

The Contractor shall be responsible for marking in the field upon receipt of a USA Call Before You Dig request from the City, the location of the underground facilities installed by the Contractor, until such time as the City accepts in writing, the responsibility for marking the facilities installed by the Contractor. The City shall not be responsible for any damage to the facilities due to Contractor's failure to properly mark the facilities.

SECTION 3.0 PROGRESS OF WORK, MEETINGS, SCHEDULES

GC 3.5 Time of Completion

Add the following:

The successful Bidder, upon becoming the Contractor after having entered into a Contract with the City, shall commence the Work to be performed under the Contract on the date set by the City in the written Notice to Proceed, continuing the Work in accordance with the approved schedule and shall complete the entire Work by and within **180 working days**.

GC 3.11 Construction Schedules

A Type "A" Construction Schedule is required for this project.

GC 3.11.1 Construction Schedule (A)

A. General

Replace entire paragraph with the following:

The schedule shall be submitted as a part of the contract documents before the Pre-construction meeting and must be favorably reviewed by the Construction Manager and the City before the Notice to Proceed is issued. NOTE: The Construction Schedule must include and account for the total contract time specified in the Contract Documents.

GC 3.12.4 Weather Delays

Add the following:

In order to be granted a time extension for a weather delay, the Contractor must show critical path activities on the project schedule.

GC 3.13, Liquidated Damages

Revise the first paragraph as follows:

SPECIAL CONDITIONS

Replace every instance of the word "calendar" with "working".

Add the following:

In case of failure on the part of the Contractor to complete the Work within the limits in subsection 3.5, time of Completion, above, or within such additional time(s) as may be granted by formal action of the City, or the Contractor fails to prosecute the Work or any separable part thereof, with such diligence as will ensure its completion within the time(s) specified in the Contract or any extensions thereof, the Contractor shall pay to the City, as liquidated damages, the sum of \$1000 for each working day of delay until such reasonable time as may be required for final completion of the Work, together with any increased costs incurred by the City in completing the Work.

Time stated for completion shall not include the final cleanup and demobilization or work items not critical to the safe function of the project except as otherwise provided in the Special Conditions.

The signing of the proposal by the Bidder shall be prima facie evidence that the Contractor agrees that the amount of liquidated damages is fair and reasonable.

SECTION 4.0 SHOP DRAWINGS AND QUALITY CONTROL/INSPECTIONS

Add the following Subsection:

GC 4.6 Required Submittals

The following items, (included but not limited to) are required submittals:

General

- Bypass Pumping Plan
- Certified Payroll Reports, Weekly
- Construction Schedule
- Disposal Plan, Permits and Permissions
- State Labor Reporting Requirements
- Material Certificate Compliance
- NOI for Storm Water Prevention Plan
- Permits
- Record Drawings
- Schedule of Values
- Safety Program
- Traffic Control Plan
- Warranties
- Weekly BMP Log
- Notification Plan

Materials

- Aggregate Base
- Asphalt Mix Design
- Backfill
- Bedding
- Concrete Mix Design
- Pavement Marking Paint
- Sewer & Storm Sewer Manholes, Pipe
- Detectable Warning Plates
- Warning Tape
- Water Pipe, Fittings, Valves, Hydrants, Pit Setters, Boxes, Yokes

SPECIAL CONDITIONS

SECTION 5.0 PAYMENT

GC 5.1 General

Add the following:

Prior to the City processing the pay estimate, the Contractor shall submit to the City a copy of its CONTRACTOR'S MONTHLY REPORT OF PAYMENT TO SUBCONTRACTORS for all payments made to subcontractors within the pay estimate period.

GC 5.5 Partial Payments

Add the following paragraph following the 1st paragraph:

A Schedule of Values shall be submitted to the Construction Manager for approval, for all bid items for which the Contractor intends to submit a payment request when the Work included in that bid item is less than 100% complete. The Schedule of Values shall detail the costs for all the items included in the Description of Bid Items and Basis for Payment for the respective bid item. Incomplete or incorrect weekly payroll reports will cause pay requests to be returned.

GC 5.5.1 Partial Payments – Inclusion of Materials on Hand

Add the following:

The following materials are eligible for partial payments: None

SECTION 7.0 CONSTRUCTION FACILITIES AND TEMPORARY CONTROLS

GC 7.3.5 Working Hours

The Normal Working Hours for the project will be from (7:00) AM to (5:30) PM, Monday thru Thursday.

GC 7.3.7 Construction Cleaning

Add the following to the end of the paragraph:

The contractor shall be responsible for maintaining the integrity of all transportation surfaces, both asphalt and dirt, access roads, bike lanes, sidewalks, pathways, gates, etc. Dust, dirt, mud, gravel, etc. carried onto the transportation surface shall be cleaned off on a regular basis (at least once a day or as requested by City personnel). Failure to comply may result in the City having the area cleaned and the cost for the clean-up billed to the contractor.

GC 7.3.8 Disposal of Material

Add the following to the end of the 1st paragraph:

When disposing of construction waste material outside the City limits, the Contractor shall contact the appropriate local government departments concerning such codes and permits.

GC 7.3.9 Parking and Storage Areas

Add the following:

Material and equipment may be stored in the City's right-of-way within work areas closed to traffic only as approved by the Construction Manager prior to use.

GC 7.4.2 Traffic Control

SPECIAL CONDITIONS

Add the following:

Pedestrian and bicycle traffic patterns shall be preserved as much as is practical during construction. Any proposed sidewalk or bike lane closures shall be included with the Contractor's traffic control plan submittals, and shall include appropriate detour signage to review and acceptance by the Construction Manager.

GC 8.8 Record Drawings

Add the following section:

GC 8.8.1 Format and Manner of Record Drawings

The Contractor shall transfer all markings and record information to a clean set of Contract drawings. All vertical and horizontal information specified below shall be confirmed by the Contractor's Nevada Licensed Professional Land Surveyor and include the Surveyor's certificate. The Surveyor's certificate shall state that "The Record Drawings accurately reflect record information supplied by the Contractor and the actual vertical and horizontal information required by the Contract Special Conditions, to the best of my knowledge and belief". Record information shall be indicated by a clouded line around the changed item and a strikeout through the original items. The plan title sheet shall also contain the words "RECORD DRAWINGS", the Contractor's and Surveyor's name, address, phone number, contact person, and month/year of completion.

The Contractor shall submit both the original marked field plans and the completed record drawings plan set to the Construction Manager for review and acceptance.

Vertical and horizontal information to be confirmed by the Surveyor or the Surveyor's Subordinates shall include the following;

- Manhole: Center of frame and cover, and pipe inverts
- Valve: Center of frame and cover and top of nut
- Flush Valve: Center of frames and covers
- Fire Hydrant: Top of nut and top of cap
- Air Vacuum Release: Cover at the point closest to the main line location
- Riser: Center of box and cover and top of water main
- Utility Vaults: Center of frame and cover and bottom inside of vaults
- Top of Curb: 25' intervals where curb slopes less than 0.5%
- Angle Points

Contractor shall also submit the Record-of-Survey showing true positions of all roadway monuments as required in GC 2.6.10 to the Construction Manager for review and approval by the Carson City Engineer. Upon the Carson City Engineer's approval Contractor shall direct the Project Surveyor to record the Record-of-Survey unless otherwise arranged with the City Engineer.

SC.4.0 NOTIFICATIONS AND COORDINATION

SC.4.1 Residential and Commercial Properties

Contractor is responsible to notify all residential and commercial properties that will be affected by the project 72 hours in advance of street work. All commercial business will be delivered 2 notices. One will be for them to keep and one must be signed by a person in office along with address of said business. A sample of the notice must be submitted to the Construction Manager for approval prior to distribution.

SC. 4.2 Fire Department and Sheriff

Contractor shall notify the Carson City Fire Department and Sheriff Department dispatch center at (775) 887-2008 at least twenty-four (24) hours in advance of (approved by CM) rerouting public traffic when traffic patterns are to be altered due to construction operations. Said notification shall set forth the specific traffic patterns to be provided in lieu of the normal routing

SPECIAL CONDITIONS

and the estimated duration of such change(s).

SC. 4.3 Waste Management

Contractor shall notify Waste Management (Trash Pick-up) at (775) 887-0402 at least twenty-four (24) hours in advance of (approved by CM) rerouting public traffic when traffic patterns are to be altered due to construction operations. Said notification shall set forth the specific traffic patterns to be provided in lieu of the normal routing and the estimated duration of such change(s).

SC. 4.4 United States Postal Service

Contractor shall notify United States Postal Service at (775) 884-2300 at least twenty-four (24) hours in advance of construction operations which may affect access for the Postal Service. Said notification shall include specific traffic patterns to be provided in lieu of the normal routing and the estimated duration of such change(s). Contractor shall coordinate with the Postal Service to ensure that mail delivery is not impacted.

SC. 4.5 Jump Around Carson (JAC) Transit

Contractor shall notify Carson City RTC JAC (Transportation Bus) at (775) 841-7433 at least twenty-four (24) hours in advance of (approved by CM) rerouting public traffic when traffic patterns are to be altered due to construction operations. Said notification shall set forth the specific traffic patterns to be provided in lieu of the normal routing and the estimated duration of such change(s).

SC. 4.6 School Bus Center

Contractor shall notify the Carson City Fire Department and Sheriff Department dispatch center at (775) 998-2008 at least twenty-four (24) hours in advance of (approved by CM) rerouting public traffic when traffic patterns are to be altered due to construction operations. Said notification shall set forth the specific traffic patterns to be provided in lieu of the normal routing and the estimated duration of such change(s).

SC.5.0 AMERICAN IRON AND STEEL REQUIREMENTS (SRF)

American Iron and Steel requirements **do not** need to be followed for this project.

SC.6 SPECIAL PROVISIONS

SC 6.1 General

- A. Payment for the various items of the Proposal Summary shall be as specified herein.
- B. Payment at the amount set forth in the proposal for each bid item will be considered to be in full for completed Work and will cover labor, materials, equipment, supplies, rental of tools and machinery and all other expenditures incidental to satisfactory compliance with the Contract, unless otherwise specifically provided.
- C. Payment for each Bid Item shall include the following Work, and shall fully compensate for any necessary Work required to perform the construction operations specified and shall be considered to be included in the bid price for the items of Work and no additional compensation will be allowed therefore. This Work includes any necessary construction staking and layout, storm water pollution prevention, potholing to verify data, construction staking, dimensions and locations of subsurface facilities and service connections, sawcutting, removal and disposal of existing improvements, clearing, removal and disposal of vegetation, excavating, removal and disposal of excess material and overburden, de-watering, shoring, connection to existing and proposed pipes, cutting and plugging abandoned pipes intercepted by the trench section, removal and disposal of abandoned pipes and appurtenances within the trench section,

SPECIAL CONDITIONS

compacting, disinfection, bypass pumping, testing, and as well as other incidentals, for completion of the Work in conformance with the Contract Documents.

- D. The terms "construct, furnish, install, erect, perform, place, prepare, remove or replace" shall mean that the bid item is complete, in place, ready for use and recommended for payment by the Construction Manager. Items of work, either specified or inferred, but not included in the tabulation of bid items shall be considered as included in the price paid for other items of work.
- E. All Work under this Contract shall conform to the requirements of the 2012 edition of the "Standard Specifications for Public Works Construction" (SSPWC), except as modified by these Special Conditions or Technical Specification.
- F. Contractor is responsible to remove any snow that accumulates on new concrete within 24 hours. Failure to comply may result in the City having the area cleaned and the cost for clean-up billed to the contractor. Contractor is responsible for this maintenance until contract is closed out.

SC 6.2 Mobilization, Demobilization, and Clean-up

- A. Measurement of this item will be per Lump Sum.
- B. Payment Schedule for partial payments for Mobilization/demobilization and cleanup for all Schedules shall be as follows:

When the monthly partial payment estimate of the amount earned for the respective Schedule, not including these items, is 15% or more of the original Schedule contract amount, then 30% of this item will be included for payment in that, one monthly partial payment estimate.

When the monthly partial payment estimate of the amount earned for the respective Schedule, not including these items, is 50% or more of the original Schedule contract amount, then an additional 30% of this item will be included for payment in that, one monthly partial payment estimate.

When the monthly partial payment estimate of the amount earned for the respective Schedule, not including these items, is 75% or more of the original Schedule contract amount, then an additional 30% of this item will be included for payment in that, one monthly partial payment estimate. The remaining 10% of these items shall be paid under the final payment provisions.

- C. Work under this bid item shall consist of Contractor mobilization, demobilization, clean-up, permit coordination, and any preparatory Work and operations necessary for the movement of personnel, equipment, supplies and incidentals to the project site before beginning construction. Work under this item shall also include any other item of Work for which other bid items have not been established in this bid schedule.

SC 6.3 Traffic Control

- A. Measurement of this item will be per Lump Sum.
- B. Payment for Traffic Control will be pro rata based on the percent of Work completed under this schedule and based on the lump sum price named in the Proposal Summary, which price shall constitute full compensation for providing labor, materials, preparation and distribution of plans, notices and reports, luminaries, signing, light plants, cones, traffic drums, warning lights, sequential flashers, temporary striping, traffic control services/inspections outside of normal working hours, preparation of formal inspection reports by Traffic Control Supervisor, labor

SPECIAL CONDITIONS

tools, equipment, materials and incidentals required as a result of changes in the Contractor's work method or schedule.

- C. Clear Creek will be allowed to be closed to all through traffic except for residents in the construction area. A detour map has been provided which shows traffic being directed to Arthur Street by Lupin Drive on the west and Center Drive on the east of the construction zone.

SC 6.4 Surveying

- A. Measurement of this item will be per Lump Sum.
- B. Payment for Surveying will be pro rata based on the lump sum price named in the Proposal Summary, which price shall constitute full compensation for providing all surveying, calculations, construction staking, re-staking as required, as-built surveying, labor, materials and incidentals to perform the work.
- C. Work under this bid item includes all items common to this task.

SC 6.5 ¾" PE Water Service Line

- A. Measurements of this item will be per Lineal Foot.
- B. Payment for ¾" PE Water Service Line shall be made at the Unit Price named in the bid response.

SC 6.6 ¾" Single Pit Setter and Water Meter

- A. Measurement for this bid item will be per Each.
- B. Payment for ¾" single pit setter and water meter shall be made at the Unit Price named in the bid response.

SC 6.7 8" C900 Water Line

- A. Measurement of this item will be per Lineal Foot through valves and fittings in place.
- B. Payment for 8" C900 Water Line shall be made at the Unit Price named in the bid response.

SC 6.8 8" Gate Valve

- A. Measurement for this bid item will be per Each.
- B. Payment for 8" Gate Valve shall be made at the Unit Price named in the bid response.

SC 6.9 Fire Hydrant Assembly

- A. Measurement for this bid item will be per Each.
- B. Payment for Fire Hydrant Assembly shall be made at the Unit Price named in the bid response.

SC 6.10 ¾" Air Release Valve Assembly

- A. Measurement for this bid item will be per Each.

SPECIAL CONDITIONS

- B. Payment for 3/4" Air Release Valve Assembly shall be made at the Unit Price named in the bid response.

SC 6.11 Adjust Existing Valve Can to Grade

- A. Measurement for this item will be per Each.
- B. Payment for Adjust Existing Valve Can to Grade shall be made at the unit price named in the bid response.
- C. This item includes lowering the valves cans as necessary during construction prior to adjusting them to finish grade. This item does not include adjusting new valve cans to grade which is included in the new valve bid item.

SC 6.12 Reconstruct Existing 48" Diameter Sanitary Sewer Manhole

- A. Measurement for this bid item will be per Each.
- B. Payment for reconstructing the existing 48" diameter manholes shall be made at the Unit Price named in the bid response.
- C. This pay item covers work necessary to remove all sections of the existing manhole above the base section and reconstruct the manhole located at station 24+35.7.

SC 6.13 Modify Existing Sanitary Sewer Manhole With Drop Inlet

- A. Measurement for this bid item will be per Each manhole modified.
- B. Payment for payment for modifying the existing manhole with a drop inlet shall be made at the Unit Price named in the bid response.
- C. This pay item covers work necessary to modify the sewer manhole located at station 46+78.7.

SC 6.14 Adjust Existing Manhole Frame and Cover to Grade

- A. Measurement for this item will be per Each.
- B. Payment for adjusting existing manhole frames and covers to finish grade shall be made at the unit price named in the bid response.
- C. This item includes lowering the frames and covers as necessary during construction prior to adjusting them to finish grade. This item does not include adjusting new manholes to grade which is included in the new manhole bid item.

SC 6.15 48" Diameter Sanitary Sewer Manhole

- A. Measurement for this bid item will be per Each.
- B. Payment for 48" Diameter Sanitary Sewer Manhole shall be made at the Unit Price named in the bid response.

SC 6.16 4" SDR35 PVC Sanitary Sewer Pipe

- A. Measurement for this bid item will be per Lineal Foot.

SPECIAL CONDITIONS

- B. Payment for 4" SDR35 PVC Sanitary Sewer Pipe shall be made at the Unit Price named in the bid response.

SC 6.17 8" SDR35 PVC Sanitary Sewer Pipe

- A. Measurement for this bid item will be per Lineal Foot.
- B. Payment for 8" SDR35 PVC Sanitary Sewer Pipe shall be made at the Unit Price named in the bid response.

SC 6.18 10" SDR35 PVC Sanitary Sewer Pipe

- A. Measurement for this bid item will be per Lineal Foot.
- B. Payment for 10" SDR35 PVC Sanitary Sewer Pipe shall be made at the Unit Price named in the bid response.

SC 6.19 Type 4R Storm Sewer Inlet

- A. Measurement for this bid item will be per Each.
- B. Payment for Type 4R Storm Sewer Inlet shall be made at the Unit Price named in the bid response.

SC 6.20 48" Diameter Storm Sewer Manhole

- A. Measurement for this bid item will be per Each manhole installed.
- B. Payment for 48" Diameter Storm Sewer Manhole shall be made at the Unit Price named in the bid response.

SC 6.21 48" Storm Sewer Drop Inlet

- A. Measurement for this bid item will be per Each.
- B. Payment for 48" Storm Sewer Drop Inlet shall be made at the Unit Price named in the bid response.

SC 6.22 15" Class IV RCP Storm Sewer Pipe

- A. Measurement for this bid item will be per Lineal Foot.
- B. Payment for 15" Class IV RCP Storm Sewer Pipe shall be made at the Unit Price named in the bid response.

SC 6.23 15" HDPE Storm Sewer Pipe

- A. Measurement for this bid item will be per Lineal Foot.
- B. Payment for 15" HDPE Storm Sewer Pipe shall be made at the Unit Price named in the bid response.

SC 6.24 18" HDPE Storm Sewer Pipe

- A. Measurement for this bid item will be per Lineal Foot.

SPECIAL CONDITIONS

- B. Payment for 18" HDPE Storm Sewer Pipe shall be made at the Unit Price named in the bid response.

SC 6.25 18" HDPE Storm Sewer Pipe (Perforated)

- A. Measurement for this bid item will be per Lineal Foot.
- B. Payment for 18" HDPE Storm Sewer Pipe (Perforated) shall be made at the Unit Price named in the bid response.
- C. This item includes work required to install the 2" bank run gravel and woven geotextile around the perforated pipe.

SC 6.26 24" HDPE Storm Sewer Pipe

- A. Measurement for this bid item will be per Lineal Foot.
- B. Payment for 24" HDPE Storm Sewer Pipe shall be made at the Unit Price named in the bid response.

SC 6.27 24" HDPE Storm Sewer Pipe (Perforated)

- A. Measurement for this bid item will be per Lineal Foot.
- B. Payment for 24" HDPE Storm Sewer Pipe (Perforated) shall be made at the Unit Price named in the bid response.
- C. This item includes work required to install the 2" bank run gravel and woven geotextile around the perforated pipe.

SC 6.28 Pulverize Bituminous Surface, Blend , and Remove Excess for an 8" min. Base Section

- A. Measurement for this item will be per Square Foot.
- B. Payment for Pulverize Bituminous Surface, Blend, and Remove Excess for an 8" Base Sections shall be made at the Unit Price named in the bid response.
- C. The Contractor will be required to pulverize to the depth required in order to obtain a resultant section of 8" pulverized base on 4" asphalt that matches the finish grades shown on the plans. The pulverized base shall be in accordance with Section 200.01.04 Recycled Aggregate Base of the Standard Specifications for Public Works Construction. This item includes excavation, grading and Type 2 if needed to widen the roadway. Excess pulverized material may be used to provide the 8" depth in the widened area.

SC 6.29 Over Excavation of Unsuitable Materials

- A. Measurement for this item will be per Cubic Yard.
- B. Payment for Over Excavation of Unsuitable Materials shall be made at the Unit Price named in the bid response and is not subject to adjustment under section GC 6.4.4.
- C. The estimated quantity listed for Unclassified Excavation is provided for Bidders Information only. No guarantee of the accuracy of this volume is provided as it is up to the bidder to determine the actual quantity of material to be excavated.

SPECIAL CONDITIONS

SC 6.30 4" Plantmix Pavement Type 3 Agg., PG 64-28 NV

- A. Measurement for this item will be per Square Foot.
- B. Payment for 4" Plantmix Pavement Type 3 Agg., PG 64-28 NV shall be made at the unit price named in the bid response.
- C. Work under this item also includes Tack Coat application to existing or previously paved surfaces as required or directed by the Construction Manager. The Bituminous material for the Tack Coat shall be SS-1H, applied at a rate of 0.05 to 0.10 English gallons per square yard with the actual application rate determined by the Construction Manager at time of application. The asphalt mix shall include 1.5% hydrated lime.

SC 6.31 AC Driveway Apron on 6" Aggregate Base

- A. Measurement for this item will be per Square Foot.
- B. Payment for AC Driveway Apron shall be made at the unit price named in the bid response.

SC 6.32 Remove Existing PCC Sidewalk

- A. Measurement for this item will be per Square Foot.
- B. Payment for Removal of Existing PCC Sidewalk shall be made at the unit price named in the bid response.

SC 6.33 Type A PCC Sidewalk (4" Concrete on 4" Aggregate Base)

- A. Measurement for this item will be per Square Foot.
- B. Payment for Type A PCC Sidewalk shall be made at the unit price named in the bid response.
- C. This item excludes curb ramp landings and wings (when present) and detectable warning plates, which are paid separately under other bid items.

SC 6.34 Remove Existing PCC Curb and Gutter

- A. Measurement for this item will be per Lineal Foot
- B. Payment for Removal of Existing PCC Curb and Gutter shall be made at the unit price named in the bid response.

SC 6.35 Type 1 PCC Curb and Gutter on 6" Aggregate Base

- A. Measurement for this item will be per Lineal Foot.
- B. Payment for Type 1 PCC Curb and Gutter on 6" Aggregate Base shall be made at the unit price named in the bid response.
- C. This item excludes curb and gutter adjacent to curb ramp landings and wings or adjacent to PCC spandrel

SC 6.36 Remove Existing PCC Driveway/Apron

SPECIAL CONDITIONS

- A. Measurement for this item will be per Square Foot.
- B. Payment for Removal of Existing Driveway/Apron shall be made at the unit price named in the bid response.

SC 6.37 PCC Driveway Apron Type 1 (6" Conc. On 6" Aggregate Base)

- A. Measurement for this item will be per Square Foot.
- B. Payment for Residential PCC Driveway Apron shall be made at the unit price named in the bid response.
- C. This item includes monolithic curb/gutter adjacent to the driveway and retaining curb.

SC 6.38 Commercial PCC Driveway Apron (6" Conc. On 6" Aggregate Base)

- A. Measurement for this item will be per Square Foot.
- B. Payment for Residential PCC Driveway Apron shall be made at the unit price named in the bid response.
- C. This Item is for the entrance to APN 09-241-10. This item includes monolithic curb/gutter adjacent to the driveway and retaining curb.

SC 6.39 Residential PCC Driveway (6" Concrete on 6" Aggregate Base)

- A. Measurement for this item will be per Square Foot.
- B. Payment for PCC Driveway shall be made at the unit price named in the bid response.
- C. This item includes monolithic retaining curb adjacent to the driveway.

SC 6.40 PCC Valley Gutter (6" Concrete on 6" Aggregate Base)

- A. Measurement for this item will be per Square Foot.
- B. Payment for PCC Valley Gutter shall be made at the unit price named in the bid response.

SC 6.41 PCC Pedestrian Ramp with Detectable Warning Plate (4" Concrete on 4" Aggregate Base)

- A. Measurement for this item will be per Square Foot.
- B. Payment for PCC Pedestrian Ramp with Detectable Warning Plate shall be made at the unit price named in the bid response.
- C. This item includes new curb next to ramp landings and wings when not part of PCC spandrel.

SC 6.42 24" Solid White Stop Bar

- A. Measurement for this item will be per Lineal Foot.
- B. Payment for 24" Solid White Stop Bar shall be made at the unit price named in the bid response.

SPECIAL CONDITIONS

SC 6.43 4" Solid White Pavement Paint

- A. Measurement for this item will be per Lineal Foot.
- B. Payment for 4" Solid White Pavement Paint shall be made at the unit price named in the bid response.

SC 6.44 4" Double Solid Yellow Pavement Paint

- A. Measurement for this item will be per Lineal Foot.
- B. Payment for 4" Double Solid Yellow Pavement Paint shall be made at the unit price named in the bid response.

SC 6.45 6" White Dotted Line Pavement Paint (2' Stripe, 6' Space)

- A. Measurement for this item will be per Lineal Foot including spaces.
- B. Payment for 6" white dotted line pavement paint shall be made at the unit price named in the bid response.

SC 6.46 4" White Centerline Skip Stripe Pavement Paint (7' Stripe 21' Space)

- A. Measurement for this item will be per Lineal Foot including spaces.
- B. Payment for 4" white centerline skip stripe pavement paint shall be made at the unit price named in the bid response.

SC 6.47 Solid White Bicycle W/Arrow Legend

- A. Measurement for this item will be per Each.
- B. Payment for solid white bicycle with arrow legend pavement paint shall be made at the unit price named in the bid response.

SC 6.48 Install New Traffic Sign and Post

- A. Measurement for this item will be per Each.
- B. Payment for installing new traffic signs and posts shall be made at the unit price named in the bid response.

SC 6.49 Reinstall Existing Traffic Sign and Post

- A. Measurement for this item will be per Each.
- B. Payment for reinstalling existing traffic signs and posts shall be made at the unit price named in the bid response.

SPECIAL CONDITIONS

SC.7 CARSON CITY AMENDMENTS TO THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION 2012 (SSPWC):

Revision No. 1 Through Revision No. 6 - 2/29/2012

The Standard Specifications for Public Works Construction are hereby amended by adding, deleting or amending the following;

SC.7.1 AMENDMENTS TO THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION

PART 1 GENERAL PROVISIONS

GENERAL PROVISIONS **100.00-1**

100.01.15 ENGINEER. **100.00-4**

Add the following sentences;

For Work performed under a Contract with Carson City, the Engineer shall be the Construction Manager.

For all other Work performed under a Carson City permit, the Engineer shall be the City Engineer.

Add the following subsection;

100.01.36 APPROVED. When referring to the approved Plans or approved Special Conditions, approved means as approved by the City Engineer.

100.20 BASE LINE, BENCH MARKS AND REFERENCE POINTS
100.00-11

Delete the wording in it's entirety and substitute the following;

The Contractor shall retain a Nevada Licensed Professional Land Surveyor, and the Surveyor or his Subordinates shall stake out the horizontal and vertical positions of all the Work. The Contractor shall satisfy himself as to the accuracy of all measurements before constructing any permanent Work and shall not take advantage of any errors found on the Plans.

100.33 PROTECTION OF PERSON AND PROPERTY. **100.00-15**

Add the following sentence;

Any damages to Carson City facilities or utilities shall be immediately repaired by the Contractor at his own expense or by City personnel, as directed by the Engineer, and the Contractor shall be responsible for reimbursing Carson City for any and all Work required to repair or replace damaged facilities or utilities.

100.41 PUBLIC SERVICE EQUIPMENT. **100.00-17**

Modify the 1st paragraph;

Add the words "unless otherwise shown on the approved Plans or specified in the approved Special Conditions" to the end of the 2nd sentence.

Add the following sentences to the end of the 2nd paragraph;

SPECIAL CONDITIONS

Any damages to Carson City facilities or utilities shall be immediately repaired by the Contractor at his own expense or by City personnel, as directed by the Engineer, and the Contractor shall be responsible for reimbursing Carson City for any and all Work required to repair or replace damaged facilities or utilities. Sewer service laterals are owned, operated and maintained by the property owner, and are not marked as a utility by Carson City.

PART 3 CONSTRUCTION METHODS

300.00 CLEARING AND GRUBBING


300.00-1

300.04 PROTECTION OF UTILITIES AND UNDERGROUND FACILITIES.

Add the following sentence;


Any damages to Carson City facilities or utilities shall be immediately repaired by the Contractor at his own expense or by City personnel, as directed by the Engineer, and the Contractor shall be responsible for reimbursing Carson City for any and all Work required to repair or replace damaged facilities or utilities.

SPECIAL CONDITIONS



ACCEPTABLE
DETOUR ROUTE

\\CAPITAL_PROJECTS\Projects\050701-ClearCreek\Draw\02-Detour\Draw\01-01-2011\GIS\Tools\GIS_Tools\GIS_Tools.dwg




EXAMPLE OF PAY QUANTITIES

ALL QUANTITIES TO BE FIELD VERIFIED

NOT TO SCALE


SC-18



EXAMPLE OF PAY QUANTITIES

ALL QUANTITIES TO BE FIELD VERIFIED

NOT TO SCALE




EXAMPLE OF PAY QUANTITIES

ALL QUANTITIES TO BE FIELD VERIFIED

NOT TO SCALE

SC-20

SPECIAL CONDITIONS



NOTES:

- SEE "CURB RAMP GENERAL NOTES" DWG C-5.3.1 FOR FURTHER REQUIREMENTS.

NO.	REVISION	DATE	STANDARD DETAIL FOR PUBLIC WORKS CONSTRUCTION	SECTION
			PERPENDICULAR CURB RAMP APEX	CARSON CITY
				DRAWING NO. C-5.3.3
				DATE 7/2009
APPROVED BY: <i>[Signature]</i>		7/09		


050023 Clear Creek Sewer Extension

Technical Specifications

Carson City Public Works

INDEX

1006 Road Repair
1009 Dewatering
2001 Staking Excavation Backfill and Compaction for Water Lines
2002 Water Service Connections
2003 Polyethylene Tubing
2005 Polyvinyl Chloride Pipe
2009 Gate Valves
2012 Fire Hydrants
2013 Thrust Blocks
2014 Couplings Dismantling and Expansions Joints
2015 Water Main Hydrostatic Testing
2016 Water Main Disinfecting
2017 Underground Marking Tape and Tracer Wire
2019 Air Release and Air Vacuum Valves
3001 Staking Excavation, Backfill and Compaction for Sewer Lines
3002 Sewer Mains Services and Appurtenances
3003 Polyvinyl Chloride Pipe for Sewer
3005 Concrete Cutting and Core Drilling
4005 Concrete Curb, Gutter, Walks, and Driveways
4007 Asphalt Concrete Pavement
7000 Waterborne Pavement Striping



4/16/2015

TECHNICAL SPECIFICATIONS

DOCUMENT No. 1006 ROAD REPAIR (8/21/13)

1. General:

- 1.1. This section specifies the requirements for repair and replacement of paved and unpaved roads, approaches and driveways which have been cut, damaged or removed during construction to their original or better condition. At the end of each working day, all open trenches within operating (open to traffic) paved roadways or driveways shall be backfilled and a temporary patch of cold, road-mix asphalt concrete shall be installed unless otherwise specified in these Contract documents or authorized by Construction Manager. At the end of each working day, all open trenches within operating (open to traffic) unpaved areas shall be backfilled to match existing grade. During construction and prior to final surfacing, Contractor shall diligently maintain all temporary trench surfacing repairs to maintain a safe surface condition for the public traffic. Prior to completion of the Work, all temporary asphalt concrete pavement shall be removed and final paving shall be placed, and all unpaved areas shall be repaired as described below.

2. Asphalt Pavement Repairs:

- 2.1. Asphalt pavement structural section shall consist of Type 2, Class B, Aggregate Base material per Section 200.01.03, Crushed Aggregate Base, of the Standard Specifications, compacted to 95% relative density overlaid with Type 3, PG 64-22 Plantmix Bituminous Pavement at depths as specified on the drawings. Final asphalt concrete pavement and repairs shall be as specified in Document No. 4007 Asphalt Concrete Pavement, of these Technical Specifications.

3. Gravel Surface Roadway and Driveway Repairs:

- 3.1. Unpaved, gravel surfaced roadways and driveways shall be repaired to match existing conditions, but at a minimum four (4) inches thick section of Type 2, Class B, Crushed Gravel Base per Section 200.01.03 of the Standard Specifications, compacted to 95% relative density.
- 3.2. The subgrade shall be graded and shaped as required to construct the crushed gravel base surface. The subgrade shall be compacted to 90% relative density.
- 3.3. After placing, shaping, and compacting of the crushed gravel base, the finished surface shall be one-half inch above the adjacent surface.

4. Asphalt Surface Driveways:

- 4.1. Asphalt surfaced driveways shall be repaired to match the existing driveway structural section. The asphalt pavement shall be as specified in Document No. 4007 Asphalt Concrete Pavement of these Technical Specifications.
- 4.2. Subgrade preparation and crushed gravel base shall be as indicated for gravel surface driveways. The aggregate base shall be coated with prime coat prior to installation of the asphalt surface.

END OF DOCUMENT 1006

TECHNICAL SPECIFICATIONS

Document No. 1009 DEWATERING (1/7/15)

1. General:

- 1.1 The Work of this Section includes designing, furnishing, installing, maintaining, operating, monitoring, removing systems required to control groundwater levels and hydrostatic pressures during trench and structure excavation, and treatment of water, all in compliance with Nevada Division of Environmental Protection (NDEP) and Nevada Division of Water Resources (NDWR) requirements, and disposing of pumped water.
- 1.2 Dewatering shall include intercepting seepage; preventing loss of material from the trench and structure excavation; preventing rupture or heaving of the bottom of the excavation; and maintaining the water table at a minimum of one foot below excavation bottom and as necessary to complete the Work in a dry condition.

2. Submittals:

- 2.1 Contractor shall submit the following to Construction Manager:
 - 2.1.1 The proposed type of dewatering system including relief of hydrostatic head and procedure for maintaining the excavation in a dewatered and hydrostatically relieved condition.
 - 2.1.2 Arrangement, location, and depths of the components of the system.
 - 2.1.3 A complete description of equipment to be used, with installation, operation, and maintenance procedures.
 - 2.1.4 Standby equipment and power supply.
 - 2.1.5 Location, size, and construction details of sumps and discharge lines, including discharge points and drawings for removing system and restoring the area disturbed by the dewatering operations.
 - 2.1.6 Types and sizes of filters.
 - 2.1.7 Design calculations demonstrating adequacy of the selected system and equipment.
- 2.2 Contractor shall also submit to Construction Manager copies of correspondence with NDEP and NDWR regarding dewatering operations including Dewatering Permit, water quality tests, authorization to drill, well driller's license, and Well Driller's Report.

3. Design Criteria for Dewatering System:

- 3.1. Contractor shall design a dewatering system which will:
 - 3.1.1. Lower the groundwater level to a minimum of one foot below the bottom of the excavation and as necessary to complete the Work in a dry condition.
 - 3.1.2. Develop a substantially dry and stable subgrade for the performance of subsequent operations.
 - 3.1.3. Result in no damage to adjacent properties, buildings, structures, utilities, and other work.
 - 3.1.4. Not remove soil particles during pumping operations.
- 3.2. Contractor shall review and investigate the soils and groundwater conditions at the site and determine the type or combination of methods necessary to provide the dewatering required to perform the Work.
- 3.3. Dewatering procedures which cause, or threaten to cause, damage to new or existing facilities shall be modified to prevent damage. Contractor shall determine and implement modifications at no additional cost to Carson City.

TECHNICAL SPECIFICATIONS

4. Quality Control:

- 4.1. Contractor shall perform dewatering activities in compliance with the NRS and the Nevada Administrative Code, administered through NDEP and NDWR, and shall obtain all necessary permits to complete the Work of this Section. Contractor shall control the rate and effect of dewatering to avoid objectionable settlement and subsidence, and shall perform dewatering operations to adequately ensure integrity of the finished project.
- 4.2. Contractor shall conduct dewatering operations in a manner which will protect adjacent structures and facilities, and shall repair any damage caused by dewatering to adjacent structures and restore facilities at no additional cost to Carson City.

5. Equipment:

- 5.1. Contractor shall provide all equipment necessary for dewatering. At all times keep sufficient pumping equipment on-site, keep machinery in good working condition, and provide competent workers for operation of pumping equipment. Keep and maintain adequate standby pumping equipment on-site and available at all times to ensure efficient dewatering and maintaining of dewatering operation during any power failure.

6. Dewatering Installation and Operations:

- 6.1. Dewatering shall be accomplished in accordance with the reviewed submittals and special Permits. Inform Construction Manager of any changes made to accommodate field conditions and, on completion of the dewatering system installation, revise and resubmit dewatering drawings. Dewatering may include the use of:
 - 6.1.1. Well points
 - 6.1.2. Temporary pipelines for water disposal
 - 6.1.3. Rock or gravel placement
 - 6.1.4. Other means or methods reviewed by Carson City/State prior to installation.
- 6.2. Dewatering operations shall lower the groundwater level in excavations for prosecution of the Work, and provide a stable dry subgrade for the prosecution of subsequent operations. Operations shall commence prior to excavation and continue until a stable and dry subgrade is achieved. The water level shall be maintained at such lower elevations until no danger to the excavation, structure, or related facilities can occur because of buildup of excessive hydrostatic pressure. Maintain the water level at a minimum of one foot below the bottom of the excavation and as necessary to complete the Work until the structure has been satisfactorily completed, including sealing of joints, unless otherwise permitted by Construction Manager.
- 6.3. Conduct dewatering in a manner to preserve undisturbed bearing capacity of subgrade soils at proposed bottom of excavation. If foundation soils are disturbed or loosened by upward seepage of water or an uncontrolled flow of water after dewatering is in operation, Contractor shall be responsible for devising a plan and taking action to stabilize the soil and provide a firm subgrade, at no additional cost to Carson City.
- 6.4. Dewatering operations shall be prosecuted as required to prevent delays in construction. The responsible person in charge of the Dewatering Program shall be available for communication with the site personnel at all times, and shall be able to be on the site within one hour of being alerted.
- 6.5. Prevent flotation by maintaining a positive and continuous removal of water. Contractor shall accept responsibility and liability for damages which may result from failure to adequately keep excavations dewatered.
- 6.6. Requirements and procedures for using well points or wells are:
 - 6.6.1. Adequately space to provide necessary dewatering.

TECHNICAL SPECIFICATIONS

6.6.2. Sandpack and/or use other means to prevent pumping of fine sands or silts from the subsurface.

6.6.3. Continually check to ensure that the dewatering operation does not remove subsurface soils.

7. **Monitoring of Dewatering Operations:**

7.1. Contractor shall provide regular monitoring of the dewatering operations including, but not limited to, walking along the project a minimum of weekly to check for visual signs of settlement (i.e., cracking and so forth), discharge piping, flow rates and water quality. At no additional cost to Carson City, Contractor shall also provide a minimum of monthly surveying along the project, by a Nevada Licensed Land Surveyor, on existing improvements to check for signs of excessive settlement, and checking wells for groundwater levels.

8. **Water Disposal:**

8.1. Contractor shall dispose of water from the Work in a suitable manner without damage to adjacent property. Obtain approval and coordinate for the method and place of disposal of groundwater from Carson City and the Bureau of Water Pollution Control (BWPC). Contractor shall not drain water into Work built or under construction without the prior consent of Construction Manager. Upon approval of the Construction Manger, and prior to preparation of pipe or structure for acceptance, the pipeline or structure may be used to convey groundwater to sumps for pumping. Do not allow such water or associated debris to enter into any sanitary sewer system. Remove debris accumulated in the pipeline or structure and thoroughly clean prior to testing and acceptance.

8.2. Do not allow runoff from dewatering to flow in the curb, gutter, or street. Filter the water using an approved method to remove sand and fine-sized soil particles before disposal into any drainage system.

9. **Groundwater Release:**

9.1. Contractor shall perform release of groundwater to its static level in a manner which shall maintain the undisturbed state of natural foundation soils, prevent disturbance of compacted backfill and prevent flotation or movement of structures, pipelines, and sewers.

10. **Removal and Restoration:**

10.1. When groundwater control is no longer necessary, wells, equipment, drain lines and connections shall be removed in accordance with State regulations and the ground surface restored to its original conditions.

11. **Payment:**

11.1. Payment for dewatering shall be considered as included in the various items of Work requiring such dewatering, and no separate or additional compensation shall be allowed.

12. **END OF DOCUMENT 1009**

TECHNICAL SPECIFICATIONS

Document No. 2001 STAKING, EXCAVATION, BACKFILLING AND COMPACTING FOR WATER LINES (7/5/07)

1. General:

- 1.1 Before any excavation on the project, Contractor shall notify all local utility companies and "Call Before You Dig" at 1-800-227-2600. Excavation shall include the removal of all materials or obstructions of any nature, the installation and removal of all sheeting and bracing and the control of water necessary to construct the work as shown. Excavation work shall be performed in a safe and proper manner with suitable precautions taken against hazards of every kind. Sheeting and shoring shall conform to the requirements of OSHA and Section 305.06 of the Standard Specifications. There is a significant likelihood that groundwater will be encountered during trenching excavation. Contractor shall be prepared to install and maintain pumping equipment necessary to control groundwater during construction.
- 1.2 Backfill during freezing weather shall not be done except by permission of Construction Manager. No backfill material shall be installed on frozen or yielding surfaces, nor shall frozen materials, snow or ice be placed in any backfill.

2. Reference Standards:

- 2.1 Relative compaction or density, when hereinafter referred to, means the in-place dry density of the soil expressed as a percentage of the maximum dry density of the same soil as determined by the ASTM D1557-91 test procedure. The costs of site compaction or density testing shall be paid for by Carson City. The costs of all retests (from failed tests) shall be paid for by Contractor.

3. Staking Out the Work:

- 3.1 Contractor shall retain a Nevada Licensed Professional Land Surveyor, and the Surveyor or his Subordinates shall stake out the horizontal and vertical positions of all the Work. Contractor shall satisfy himself as to the accuracy of all measurements before constructing any permanent structure and shall not take advantage of any errors found on the drawings. Where new construction connects to existing facilities, Contractor shall pothole and establish the exact locations and elevations prior to construction of the facilities.
- 3.2 It shall be Contractor's responsibility to expose the existing water lines at the points of connection for the new lines and maintain the depths of cover and slopes as indicated on the drawings. It shall also be Contractor's responsibility to:
 - 3.2.1 Pothole existing utilities and, after approval by Construction Manager, modify water line grade as required to match or avoid existing utilities while maintaining the depth of cover required and the general slope of the pipe to prevent high points in the pipeline.
 - 3.2.2 Maintain the minimum amount of cover shown on the drawings, except as approved by Construction Manager.
 - 3.2.3 Adjust depth of cover, after approval by Construction Manager, as required to prevent changes in the pipe slope which would create high points at locations other than those indicated on the drawings.
 - 3.2.4 Have the Work staked in accordance with the lines and grades as shown on the drawings.

4. Trench Work:

TECHNICAL SPECIFICATIONS

4.1 Trench Configuration and Alignment:

4.1.1 Trenches shall be excavated to provide for the bedding as specified in subsection 5.1 Bedding.

4.1.2 The new pipeline shall be laid essentially as per the alignments and grades shown on the drawings.

4.1.3 Trenches and other excavations shall have the minimum width which Contractor can effectively excavate and install the improvements. Excessive widths will not be permitted. Trenches shall have a minimum width of twenty-four (24) inches greater than the outside diameter of the pipe to be installed. Deviations from this minimum width must be submitted to Construction Manager in writing for approval. The bottom of the trench shall be graded uniformly to provide a minimum cover of forty-two (42) inches over the top of the pipe unless otherwise shown on the drawings, provide continuous bedding support under the pipe, and to allow the pipe to be laid to the grades and alignments shown in the drawings.

4.2 Pipe Bedding: The trench shall be over excavated to a depth of at least six (6) inches below the bottom of the pipe and backfilled to the required grade of the bottom of the pipe with bedding material. The pipe bedding shall be brought to optimum moisture content and compacted to not less than 90% relative density. The pipe bedding at the trench bottom shall have a flat or semicircular cross section. The bottom of the trench for all pipe shall be graded and prepared to provide a firm and uniform bearing surface throughout the entire length of each pipe section except for excavation required at joints. Pipe couplings shall not rest on the trench bottom and laying the pipe on mounds will not be allowed.

4.3 Bedding Through the Pipe Zone: After center loading the pipe to prevent lateral movement, bedding material shall be placed in the trench simultaneously on each side of the pipe for the full width of the trench in layers not to exceed eight (8) inches in depth. Each layer or lift shall be compacted to at least 90% of maximum density evenly, on each side of the pipe throughout the pipe zone. The pipe zone is to extend from bottom of the pipe to twelve (12) inches above the top of the pipe and shall be backfilled with bedding material as specified herein.

4.4 Backfill Above the Pipe Zone: From twelve (12) inches above the top of pipe to the top of the trench, if not in existing pavement, or bottom of the pavement structure, if in existing pavement, pipe backfill shall consist of material as specified in subsection 5.2 Backfill. No oil cake, bituminous pavement, concrete, rock or other lumpy material shall be used in the backfill. Backfill material shall be compacted to not less than 90% relative density. All trenches shall be backfilled after pipe fittings and appurtenances have been installed, inspected and approved. All trash, wood, large rocks, waste material and other objectionable debris shall be removed from excavation prior to any material being placed in the trench. Backfill shall include the refilling and compacting of the trench or excavation.

4.4.1 Where existing underground pipes or conduits larger than three (3) inches in diameter cross the trench above the new work, the backfill from the bottom of the trench to the spring line of the intersecting pipe or conduit shall be Crushed Gravel Base material, Type 2, Class B, Aggregate Base conforming to the requirements of Section 200.01.03 of the Standard Specifications, compacted to 90% of maximum density. The aggregate base material shall extend two (2) feet on either side of the intersecting pipe or conduit which will insure that the material will remain in place while other backfill is placed.

4.4.2 Backfill by jetting shall not be allowed. Backfill shall be densified by mechanical compaction.

4.5 Site Excavation:

4.5.1 The bottom of the excavation shall not be more than one-tenth (0.10) foot above or below the lines and grades specified. If the elevation of structure excavation is not specified the excavation shall be not more than one-tenth (0.10) foot above or below the elevation specified for fill material below the structure. Cut slopes shall vary no more than five-tenths (0.5) foot from specified grade unless the excavation is in rock where the maximum variation should be two (2) feet. Unless

TECHNICAL SPECIFICATIONS

otherwise specified, excavations shall extend a sufficient distance from walls and footings to allow for placing and removal of forms, installation of services, and for inspection, except where concrete is specified to be placed directly against excavated surfaces. Upon completion of excavation, the existing subgrade shall be compacted to a minimum of 95% relative density.

4.5.2 Should the excavation be carried below the lines and grades specified on the drawings, or should the bottom of the excavation be disturbed because of Contractor's operations and require over-excavation and backfill, Contractor, at his expense, shall refill such excavated space to the proper elevation in accordance with the procedure specified for backfill.

4.6 Rock Excavation and Blasting:

4.6.1 No blasting will be permitted without the approval of Construction Manager. When blasting is permitted, it shall be done only by skilled operators and under the direction of a competent, properly licensed foreman.

4.6.2 Blasting will be permitted only when proper precautions are taken for the protection of persons, the work, and existing structures. Any damage done to persons, private property, the work, or existing structures shall be the responsibility of Contractor.

4.6.3 Blasting shall be done with explosives of such power and in such quantities and positions as not to make the excavation unduly large, or to shatter the faces of cuts which are to remain open. Excessive blasting or "overshooting" will not be permitted, and any material outside the authorized cross-section which may be shattered or loosened by blasting shall be removed and replaced with earth as herein specified, at Contractor's expense. Construction Manager shall have authority to require Contractor to discontinue any method of blasting which leads to "overshooting" or is dangerous to the public or destructive to property or to natural features.

4.6.4 Permits for blasting shall be obtained and paid for by Contractor.

4.7 Sheeting and Shoring:

4.7.1 Excavation for trenches shall be properly and substantially sheeted, braced, and shored as required by trench conditions. Sheeting, bracing, and shoring shall be designed and built to withstand all loads that might be caused by earth movement or pressure and shall be rigid, maintaining shape and position under all circumstances. Contractor's design for all sheeting and shoring shall be signed and sealed by a licensed Nevada Civil or Structural Engineer and the drawings submitted to Construction Manager prior to its construction.

4.7.2 During backfilling, any shoring shall be carefully removed by Contractor in such a manner as will result in a minimum of caving, lateral movement, or flowing of the soil. On approval of Construction Manager, Contractor may leave shoring in place, but in such an event, no payment will be made by Carson City for such materials left in place. Where trench shoring is left in place, it shall not be braced against the pipe.

5. Materials:

5.1 Bedding:

5.1.1 Pipe bedding material shall conform to the requirements of Section 200.03.02, Class A Backfill, of the Standard Specifications.

5.1.2 Bedding shall be placed in accordance with Section 305.08, Bedding, of the Standard Specifications.

TECHNICAL SPECIFICATIONS

5.2 Backfill:

- 5.2.1 Trench backfill shall conform to the requirements of the Standard Specifications, Section 200.03.06, Class E Backfill, unless otherwise specified.
- 5.2.2 Trench backfill shall be placed and compacted in accordance with Section 305, Trench Excavation and Backfill, of the Standard Specifications.
- 5.2.3 Backfill for any structure shall be Crushed Gravel Base material, Type 2, Class B, Aggregate Base conforming to the requirements of Section 200.01.03 of the Standard Specifications. No backfill material shall be deposited against concrete structures until the concrete has developed a minimum strength of 3,000 psi.
- 5.2.4 If site excavated material meets the requirements for Class "E" Backfill but exceeds optimum moisture content, Contractor shall take whatever measures are necessary to dry the material to a compactable moisture content. No additional compensation shall be allowed for such measures. If site excavated material does not meet "Class E Backfill" requirements in accordance with the Standard Specifications, Contractor may be directed by Construction Manager to remove and dispose of the unsuitable material to an approved disposal location and import acceptable material.

5.3 Pavement Structure:

- 5.3.1 Defined as that section from the top of the backfill to the road wearing surface. This section shall consist of Crushed Gravel Base material, Type 2, Class B, aggregate base conforming to the requirements of Section 200.01.03 of the Standard Specifications, compacted to 95% maximum dry density overlaid with asphalt concrete at a depth to match contiguous pavement, but not less than that specified in roadway sections. Refer to the Permanent Pavement Patch Detail on the drawings, and if applicable, also refer to the Patching Details for Work within NDOT Right-of-Way.

6. Construction:

6.1 Maximum Length of Open Trench:

- 6.1.1 Except by permission of Construction Manager, the maximum length of open trench where prefabricated pipe is used shall be five hundred (500) feet, or the distance necessary to accommodate the amount of pipe installed in a single day, whichever is the greater.

6.2 Control of Water:

- 6.2.1 When water is encountered, Contractor shall furnish, install, maintain and operate all necessary machinery, appliances, and equipment to keep excavations free from water until the placing of the bedding material, laying and jointing of the pipe, pouring of concrete, and placing of the backfill material has been completed, inspected, and approved and all danger of flotation and other damages is removed. Groundwater pumped from the trench shall be disposed of in such a manner as will not cause injury to public or private property, or constitute a nuisance or menace to the public, and shall be subject to the prior approval of Construction Manager and all regulatory requirements of the State of Nevada. If well points are used for dewatering, they shall be removed or abandoned according to State of Nevada regulations.

6.3 Special Foundation Treatment:

- 6.3.1 Whenever the bottom of the trench is soft, yielding, or in the opinion of Construction Manager otherwise unsuitable as a foundation for the pipe, the unsuitable material shall be removed to a depth approved by Construction Manager and replaced with suitable material approved by Construction Manager. Payment for this work will be made only if the bottom of the trench has become unstable due to circumstances beyond the control of Contractor. Payment for this work

TECHNICAL SPECIFICATIONS

will be made as specified in subsection 6.4 Modification Procedures of the General Conditions unless otherwise provided for in these Contract documents.

6.4 Restoration of Roadway Surfaces:

6.4.1 All road shoulders and pavement which are broken or damaged due to Contractor's operations shall be reconstructed by Contractor at no additional cost to Carson City. Reconstruction shall be subject to the approval of Construction Manager.

6.5 Repairs Required by Trench Settlement:

6.5.1 If, at any time during a one (1) year period from the date of final acceptance of the project, there is any settlement of the trenches requiring repairs to be made, or should any other defect appear in the system due to negligence or carelessness on the part of Contractor, Carson City will notify Contractor to immediately make such repairs as may be deemed necessary at Contractor's expense.

6.6 Surplus Material:

6.6.1 All surplus material shall be disposed of off site in accordance with applicable ordinances and environmental requirements. Contractor shall be responsible for ultimate disposal of surplus material. He shall also include in his bid the cost for disposal, in accordance with City, State, and Federal environmental laws, of all Asbestos Cement Pipe removed during construction.

END OF DOCUMENT 2001

TECHNICAL SPECIFICATIONS

Document No. 2002 WATER SERVICE CONNECTIONS (8/26/04)

1. Scope:

1.1 The work to be done under this Section consists of furnishing all labor, equipment, materials, supplies and incidentals necessary for installation of water service connections, and fire service connections.

2. Materials:

NAC 445A.66085 "Lead-free" defined and 445A.67125 "Distribution system: Materials" have been revised by the State Environmental Commission to include the Reduction of Lead in Drinking Water Act, Public Law 111-380, and the Community Fire Safety Act, Public Law 113-64. The revision may be found at <http://www.leg.state.nv.us/Register/2014Register/R118-14A.pdf>.

2.1 Service Connection Size:

2.1.1 The size of service connections shall be as shown on the construction drawings. All components of a service connection shall be the same size as the nominal designation of the service connection pipe; i.e., a one (1) inch connection will consist of a one (1) inch service saddle, and a one (1) inch corporation stop, unless otherwise shown on the drawings.

2.1.2 When replacing an existing service connection, if the existing service size encountered is larger than the existing service shown on the drawings, and the drawings do not indicate to replace to the larger size, the service shall be replaced to match the existing service. Contractor shall be compensated for the increase in size.

2.2 Service Saddles:

2.2.1 Service Saddles shall be manufactured specifically for the type and size of pipe upon which they are being used. The Service Saddle bodies shall be stainless steel or dipped fusion bonded epoxy coated ductile iron.

2.2.2 The bands (straps), nuts, and bolts shall be of 18-8 stainless steel. The bands of D.I. saddles shall be two (2) inch wide. One band shall be supplied for up to one (1) inch service sizes and two (2) for over one (1) inch. The gasket shall be constructed of Buna-N or Neoprene. The inlet threads shall be AWWA I.P. Thread.

2.3 Corporation and Curb Stops:

2.3.1 Corporation stops shall be constructed of brass and have AWWA I.P. Threads inlet and outlets suitable for flared connections to PE pipe. Corporation and curb stops shall be manufactured by Ford, Mueller or approved equal and be NSF 372 certified. Curb stops shall be the inverted key type, constructed of brass.

2.4 Meter Pit Setters and Boxes:

2.4.1 Meter pit setters for 3/4 " and 1" meter installations shall be the Carson City Standard Mueller/McCullough Thermal-Coil Meter Box complete with integral riser, inlet angle valve, and outlet check valve. Pit setter shall be fifteen (15) inches minimum diameter for single 3/4 " meter installations, and eighteen (18) inches minimum for double 3/4" meter installations and single 1" installations. Pit setters for 1-1/2" and 2" meter installations shall be as shown on the drawings.

2.4.2 Meter boxes for 3" to 8" meter installations shall be the Carson City Standard Christy B52 with M3 lid or as shown on the drawings.

3. Workmanship:

TECHNICAL SPECIFICATIONS

3.1 General:

3.1.1 Contractor shall install the water service; make all connections as required to the main, connection to the new meter service, and connection between the new meter and the building supply line or irrigation supply line as indicated on the drawings.

3.2 Installation:

3.2.1 Prior to installing the service saddle or tapping sleeve, remove all dirt or other foreign matter that may impair the quality of the completed connection. Then place service saddle or tapping sleeve at the desired location but not within eighteen inches (18") of any fitting, coupling, valve, bend, or end of pipe. Tighten as per manufacturer's recommendation.

3.2.2 Tubing shall be cut with square ends, reamed and flared with the proper size flaring tool, cleaned, and made up tightly. Care shall be taken to prevent the tube from kinking or buckling on short radius bends. Kinked or buckled sections of tube shall be cut out and the tube spliced with the proper brass fittings, at Contractor's expense. All fittings, including reducers, shall be brass.

3.2.3 Connections between the new service, building supply line or irrigation supply line, and existing service or supply lines shall be neat and watertight with adequate pipe to prevent stress at joints.

3.3 Existing Meter Relocations:

3.3.1 Contractor shall, ONLY in the presence of the Carson City Inspector, remove individual meters from the existing pit setter or meter set, and immediately relocate the meter to the new pit setter or meter set. Domestic meters shall be relocated so that they serve the same domestic building supply line as before the relocation. Irrigation meters shall be relocated so that they serve the same irrigation supply line as before the relocation.

3.4 New Meter Installations:

3.4.1 Contractor shall obtain from Carson City a no cost Permit for a new meter installation. Upon completion of the water service installation and acceptance of all testing and inspection of the new water service and any applicable water main, Contractor shall submit a completed "Utility Billing Water/Sewer Service Application" to Construction Manager. Carson City will then install the new meter.

END OF DOCUMENT 2002

TECHNICAL SPECIFICATIONS

Document No. 2003 POLYETHYLENE TUBING (3/15/07)

1. General:

1.1 This section covers polyethylene tubing which shall be furnished and installed complete and in place with all jointing materials, fittings and other appurtenances as shown on the Plans or as otherwise required for a complete installation.

2. Materials:

2.1 Tubing:

2.1.1 Polyethylene tubing shall conform to NSF Standard No. 14, AWWA Standard C901, and to the specifications of ASTM D 2737. Polyethylene tubing shall be copper tubing size (CTS), pressure class 200, have a dimension ratio (DR) of not more than 9.0, and shall be made with materials designated PE3408 by the Standard PE Code.

2.1.2 All repairs or connections to new or existing P.E., copper or galvanized water service lines, "to 2", shall be MUELLER CTS 110 COMPRESSION TYPE FITTINGS OR APPROVED EQUAL.

2.2 Fittings:

2.2.1 Fittings shall meet the requirement set forth in AWWA C901 and shall be Flare-Nut type.

3. Installation:

3.1 Polyethylene tubing shall be installed in accordance with the manufacturer's recommendations and in accordance with AWWA C901.

END OF DOCUMENT 2003

DOCUMENT No. 2005 POLYVINYL CHLORIDE PIPE (3/31/14)

1. General:

- 1.1. This section covers pressure water supply polyvinyl chloride pipe which shall be furnished and installed complete with all jointing materials, fittings and other appurtenances shown on the drawings or otherwise required for a complete installation. Contractor shall furnish, install and test pipe, fittings and appurtenances of the dimensions and types and to the lines and grades shown on the drawings and specified herein.

2. Unloading PVC Pipe:

- 2.1. Prolonged exposure to temperatures near freezing make PVC sensitive to impact and extra care shall be taken in handling PVC during cold weather.
- 2.2. PVC pipe may be off-loaded by hand, either by passing over the side or off the truck end. Sliding one (1) length on another is standard practice in unloading PVC pipe, but lengths in the bottom layer shall be lifted off of the rough surface of the truck body to avoid erosion.
- 2.3. Compact shipping units (palletized bundles in a wood frame) are used to ship large orders of pipe. These units can be unloaded by conventional fork lifts.

3. Materials:

3.1. Pressure Pipe:

- 3.1.1. PVC pressure pipe shall conform to AWWA C900 or C905, as shown on the drawings. Pressure class for C900 or pressure rating for C905 shall be as shown on the drawings and have an outside diameter equivalent to that of cast iron pipe. The standard pipe length shall be twenty (20) feet.
- 3.1.2. PVC pressure piping shall be manufactured by CertainTeed Corporation; Diamond Plastic Corporation; Northern American Pipe Corporation or Northern Pipe Products. Any other manufacturer shall require a formal substitution request.
- 3.1.3. All PVC pipe and fittings shall be installed within one hundred twenty (120) calendar days from date of manufacture. Contractor shall submit manufacture date to Construction Manager prior to pipe installation. Contractor shall avoid, to the extent possible, prolonged exposure of Polyvinyl Chloride Pipe to sun and/or temperatures near or below freezing.

3.2. Identification Marks:

- 3.2.1. Pipe and couplings shall be clearly and permanently marked with all information required by AWWA C900 and AWWA C905, respectively.

3.3. Testing:

- 3.3.1. All materials shall be sampled and tested in accordance with all requirements of AWWA C900 and AWWA C905, respectively. Pipe not manufactured in the United States shall be tested as required above by an approved testing laboratory within the United States.

3.4. Affidavit of Compliance:

- 3.4.1. The manufacturer shall furnish an affidavit of compliance certifying that all tests have been conducted and that the materials comply with the applicable standards and these

specifications. Test information shall be retained and shall be available if required by Engineer.

3.5. Couplings:

3.5.1. Each length of pipe shall be furnished with a coupling consisting of either a PVC sleeve and two (2) sealing rings or an integrally cast bell and one (1) sealing ring designed to hold the pipe in alignment, provide flexibility, separate the ends of the pipe lengths, resist applied earth pressures and provide fluid tightness.

3.6. Rubber Rings:

3.6.1. Rubber rings shall conform to Subsection 203.15.03.01 of the SSPWC.

3.7. Fittings:

3.7.1. Fittings shall be PVC, short body gray iron, or ductile iron conforming to ANSI A21.10 (AWWA C153, C110, or C907). Cast iron fittings for pipe twelve (12) and smaller shall be pressure rated for 250 psi. Ductile iron for fittings shall conform to ASTM A536 Grade 80-60-03 or 70-5-05 and fittings for pipe twenty-four (24) inches or smaller shall be pressure rated for 350 psi.

3.8. Joints:

3.8.1. Flanged Joints:

3.8.1.1. Flanges shall conform to ANSI B16.1 and shall be 250 psi, flat-faced. Bolts shall be of corrosion-resisting steel conforming to the requirements of ASTM A193, Grade B7. Bolts shall conform to ASTM A194, Grade 2H Heavy Series. The fit shall be free fit (Class 2), except that medium fit (Class 3) shall be provided in holes tapped for studs. Bolts and nuts used for submerged service shall be made from Type 304 stainless steel and shall conform in design to the above specifications.

3.8.1.2. Studs and bolts shall be of such length that no less than 1/4 inch nor more than 1/2-inch will be projected through the nut when drawn tight. All bolt heads and nuts shall be hexagonal except where special shapes are required.

3.8.1.3. Gaskets shall conform to ASTM D1330, Grade I, red rubber, full faced, 1/8-inch thick.

3.8.2. Mechanical Joints:

3.8.2.1. Mechanical joints shall conform to ANSI A21.11.

3.8.3. Push-on Joints:

3.8.3.1. Push-on joints shall conform to ANSI A21.11 except that gaskets shall be neoprene or other synthetic rubber. Push-on joints shall have their ring grooves and rings compatible with the pipe ends. The grooves shall be gauged for tolerance before arriving at the job site and the grooves and interior surfaces of the bell shall be smooth and free from ridges, notches and uneven surfaces.

3.9. Restraints

3.9.1. All restraints shall be Romac Industries "600" Series, Diamond Plastics Diamond Lok, RomaGrip or approved equal.

4. Installation:

- 4.1. Installation shall conform to the manufacturer's recommendations except as modified by these specifications and as shown on the drawings.
- 4.2. All laying, jointing and testing for defects and leakage shall be performed in the presence of Engineer and shall be subject to his approval before acceptance. Materials found during construction to have defects will be rejected and Contractor shall promptly remove such defective material from the site.

5. Trenching, Bedding and Backfill:

- 5.1. Requirements for trenching, bedding and backfill shall be as specified; as required by applicable permits and regulations; and as required by applicable safety codes.
- 5.2. Pipe shall be laid on a shaped trench foundation or shaped bedding as required and with properly dug bell or coupling holes. Supporting pipe on blocks or mounds of earth or bedding material will not be permitted.

6. Handling and Stockpiling:

- 6.1. Pipe, fittings and accessories shall be handled in a manner that will insure installation in a sound, undamaged condition. Equipment, tools and methods used in unloading, reloading, hauling and laying pipe and fittings shall be such that the pipe and fittings are not damaged. Hooks inserted in ends of pipe shall have broad, well-padded contact surfaces. No unpadded hooks or wire brushes shall be permitted to contact plastic lining. Pipe and fittings in which lining has been broken, split or loosened shall be replaced by and at the expense of Contractor. Where damaged areas are small and readily accessible, Contractor may be permitted to repair the lining in accordance with the manufacturer's instructions. Store pipe on a flat surface so as to support the barrel evenly. Store random lengths separately where they will be readily available. Individual lengths of pipe should be stocked in piles of no higher than three (3) feet. If pipe is to be stored outside for periods longer than thirty (30) calendar days, the pipe must be covered to protect it from prolonged exposure to the sun's rays. The pipe shall be covered with canvas or another opaque material which shall not be clear plastic sheets. Provisions shall be made for air circulation under the sheet.
- 6.2. Cutting
 - 6.2.1. Cutting and machining of pipe shall be accomplished in accordance with the pipe manufacturer's standard recommendations. Pipe shall not be cut with a cold chisel, flame, standard iron pipe cutter, or any other method that may fracture the pipe, produce ragged, uneven edges or split the pipe end. Cut ends shall be machined smooth to the proper dimensions.

7. Pipe Laying:

- 7.1. The pipe shall be laid to the lines and grades shown on the drawings and specified herein and the sections shall be closely jointed to form a smooth flow line. Immediately before placing each section of pipe in final position, the bedding shall be checked for firmness and uniformity of surface.
- 7.2. The radius of curvature of the trench shall determine the maximum length of pipe section that can be used without exceeding the allowable deflection at a coupling. The deflection at any flexible joint shall not exceed that prescribed by the manufacturer of the pipe. The

manufacturer's printed installation guide outlining the radii of curvature that can be negotiated with pipe sections of various lengths shall be followed.

- 7.3. Proper implements, tools, and facilities as recommended by the pipe manufacturer's standard printed installation instructions shall be provided and used by Contractor for safe and efficient execution of the work. All pipe, fittings, valves, and accessories shall be carefully lowered into the trench by means of derrick, ropes, or other suitable equipment in such a manner as to prevent damage to pipe and fittings. Under no circumstances shall pipe or accessories be dropped or dumped into the trench.
- 7.4. The pipe and accessories shall be inspected for defects prior to lowering into the trench. Any defective, damaged or unsound pipe shall be repaired or replaced. All foreign matter or dirt shall be removed from the interior of the pipe before lowering into position in the trench. Pipe shall be kept clean during and after laying. All openings on the pipe line shall be closed with watertight expandable type sewer plugs or test plugs at the end of each day's operation or whenever the pipe openings are left unattended. The use of burlap, wood, or other similar temporary plugs will not be permitted.

8. Distributing Along the Trench:

- 8.1. Pipe should be strung as near the trench as possible, but, if the trench has not been dug, it shall be kept out of the way of the excavator. It shall be protected from blasting, traffic, equipment or other hazards. Where damage as a result of vandalism could occur, only enough pipe for one day's laying shall be strung. The pipe shall be strung so that the bell ends point in the direction that the work is progressing.

9. Jointing:

- 9.1. Each pipe joint shall be joined either with a coupling consisting of a PVC sleeve and two (2) rubber gaskets, or an integral bell with one (1) rubber gasket.
- 9.2. The gasket and the gasket seat inside the collar or bell shall be wiped clean before the gasket is inserted. At this time a thin film of lubricant shall be applied to the gasket and to the outside of the clean pipe end. Lubricant other than that furnished with the pipe shall not be used. The end of the pipe shall be then forced into the collar or bell to complete the joint.
- 9.3. The assembly of the joint shall be made in accordance with the printed recommendations of the manufacturer. This shall be accomplished with an assembly tool if so recommended by the manufacturer, so that the resulting position of the sleeve shall be such that is centered over pipe ends. After assembly of the coupling, the rubber gasket location shall be checked with a suitable gauge. Gaskets for the full circumference of the pipe shall be located at a distance from the coupling or bell end as recommended by the manufacturer of the couplings, if the distance does not fall within required limits, the joint shall be disassembled and reassembled in an acceptable manner.
- 9.4. When pipe laying is not in progress, the open end of the pipe shall be closed by approved means to prevent trench water from entering pipe. Adequate backfill shall be deposited on pipe to prevent floating of pipe. Any pipe which has floated shall be removed from the trench, cleaned, and relaid in an acceptable manner. No pipe shall be laid when, in the opinion of Engineer, the trench conditions or weather are unsuitable for such work.

10. Installation of Fittings:

- 10.1. Fittings shall be installed utilizing standard installation procedures. Fittings shall be lowered into trench by means of rope, cable, chain, or other acceptable means without damage to the fittings. Cable, rope, or other devices used for lowering fitting into trench, shall be attached

around exterior of fitting for handling. Under no circumstances shall the cable, rope or other device be attached through the fitting's interior for handling. Fittings shall be carefully connected to pipe or other facility, and joint shall be checked to insure a sound and proper joint.

- 10.2. Mechanical fittings, joints and appurtenances shall be assembled and installed using a torque measuring or torque-indicating wrench and per AWWA standards. The use of an impact wrench or similar construction method is prohibited.

11. Thrust Blocking:

- 11.1. Concrete thrust blocking shall be provided at all tees, elbows, wyes, caps, valves, hydrants, reducers, and other points of unbalanced thrust. Thrust blocking shall be poured so the thrust surface bears against undisturbed soil. Thrust blocking shall be as specified in Document No. 2013 Thrust Blocks of these Technical Specifications.

END OF DOCUMENT 2005

TECHNICAL SPECIFICATIONS

DOCUMENT No. 2009 GATE VALVES (8/14/14)

1. General:

- 1.1. This section specifies underground gate valves and appurtenances to be installed on water or reclaimed water mains where shown on the drawings in accordance with the Carson City Standard Details C-3.1.4 - Gate Valve and C-3.1.6 - Valve Box & Lid.
- 1.2. Gate Valves shall be American AVK, American Flow Control, Clow, M & H, Mueller or equal resilient-seated gate valves conforming to AWWA C509 or C515 and shall be UL listed and FM approved.

2. Design:

- 2.1. Valve shall be non-rising stem (NRS) wedge type resilient-seated with O-Ring stem seals and low zinc copper alloy or stainless steel stem, equipped with a two (2) inch standard operating nut. Ends shall be designed for direct connection to the type of pipe or fitting which the valve is adjoined to, or as shown on the drawings. Valves shall open when turned counterclockwise.
- 2.2. The minimum design working pressure for valves twelve (12) inches in diameter and smaller shall be 200 psig and shall be 150 psig for larger valves. Valves shall be designed to have full port opening for unrestricted flow. The valve waterway shall be smooth and shall have no depressions or cavities in seat area.

3. Valve Boxes:

- 3.1. Concrete valve boxes with cast iron covers shall be provided for all buried valves. Valve boxes shall be provided with colored PVC (schedule 40 minimum) extension sleeves. Valve box covers shall be labeled, with pick hole access. Valve boxes and covers shall be Christy G5 traffic valve box with G5C lid, or approved equal.

4. Installation:

- 4.1. Valves shall be installed as shown on the drawings with support block and valve box and riser. Valves shall be installed with valve box centered over operating nut and plumb.
- 4.2. All valves shall be operated by Contractor prior to and following installation to assure free movement, proper seating and full-port opening.
- 4.3. Mechanical fittings, joints and appurtenances shall be assembled and installed

using a torque measuring or torque-indicating wrench and per AWWA standards. The use of an impact wrench or similar construction method is prohibited.

5. Protective Coatings:

- 5.1. Valves shall be provided with a shop-applied fusion-bonded epoxy coating on interior and exterior surfaces conforming to AWWA C550.
- 5.2. Any damage to the protective coating including scratches, nicks, etc. shall be repaired prior to the installation using an approved coating.
- 5.3. All exposed metal on valves and fittings such as nuts and bolts including damage during installation shall be coated prior to backfill with an approved coating.

6. Valve Identification:

- 6.1. All valves located outside the pavement structure shall be identified with a Utility Marker. Water valve markers shall be blue Carsonite High Performance Utility Marker (CRM - 306608), 5'-6" with blue valve decal (CWV 116) or approved equal. Marker shall be installed no more than 5 feet from the valve measured perpendicular to the water main or roadway.

END OF DOCUMENT 2009

TECHNICAL SPECIFICATIONS

Document No. 2012 FIRE HYDRANTS (8/14/14)

1. Scope:

1.1. The work to be done under this section consists of furnishing all plant, labor, equipment, materials, supplies and incidentals and performing all work required for furnishing and installing the fire hydrant assemblies, complete.

2. Trench Excavation and Backfill:

2.1. Trench excavation and backfill shall conform to the requirements as specified in Document No. 2001 Staking, Excavation, Backfilling and Compacting for Water Lines of these Technical Specifications.

3. Pipe:

3.1. The water pipe to be installed from the water main to the fire hydrant shall be the same type of pipe utilized for construction of the water system improvements.

4. Valves and Valve Boxes:

4.1. Valve and valve boxes for fire hydrants shall conform to the requirements as specified in Document No. 2009 Gate Valves of these Technical Specifications.

5. References:

5.1. References herein are made to the standards, tests, methods, and specifications of research and technical organizations as follows:

ITEM	STANDARD SPECIFICATION, TEST OR METHOD DESIGNATION
Fire Hydrants	AWWA C502

6. Materials:

6.1. Fire hydrant shall conform to the requirements of Section 307 of the Standard Specifications and this section of these Technical Specifications.

6.2. All hydrants shall be as follows:

- A. The size of a valve opening shall be five and one quarter inch (5¼") with two (2) two and one half inch (2½") N.S.T. (National Standard Thread) nozzles; one Harrington HHHS five inch (5") integral hydrant Storz, or approved equal,

- with blind cap & cable. A yellow and black Calpico (or approved equal) "Out of Service" indicator shall be installed on one of the 2½" nozzles until the hydrant is in service and removal of the "Out of Service" indicator is authorized by the Construction Manager. The inlet connections shall be a six inch (6") size and the operating nut shall be a one and one half inch (1½") pentagon, open to the left.
- B. Fire hydrants shall be of the compression type with the valve closing with the pressure. All hydrants shall be in accordance with the latest specifications of the American Water Works Association. All parts entering into the manufacture will be interchangeable. All fire hydrants shall be non-freezing and self-draining.
- C. The top of the hydrant shall be constructed so that the operating threads are immersed in an oil reservoir. The oil reservoir shall be sealed at both top and bottom by "O" rings to prevent oil or water leakage. The bonnet assembly shall be unitized and flanged to the tip barrel for easy removal as one unit without disassembly or loss of lubricant in the field. The main valve opening shall be controlled with a positive stop built into the bonnet assembly. The hydrant shall be of the safety ground flange design at a point two inches (2") above ground line. In the event of a traffic accident, the barrel will not become broken, nor the main operating stem become broken or bent, which parts shall be easily and quickly replaced. The safety flange design shall be constructed to ensure more accurate control of impact stresses and eliminate the uncertainties of frangible bolt and lug designs such as corrosive and varying bolt strength. The drain valves shall be bronzed to bronzed seat with quadring and shall be positively operated by main operating nut. The design shall permit full three hundred and sixty (360) degree rotation in any desired position location & placement of the hydrant shall be in accordance with all Fire Department regulations. Hydrants shall be constructed for lengthening or making repairs without the necessity of digging. Hydrant barrel shall be centrifugally cast ductile iron.
- D. Hydrants shall be subjected, after assembly to two (2) tests under a hydraulic pressure of 300 pounds per square inch. One (1) test shall be made with the whole interior of the hydrant under pressure; and another with the main valve closed and the foot piece under pressure from the inlet side. Under the above test procedure, there shall be no leakage through the main valve, drain valve, or stuffing box, or through the castings or the joints of the assembled hydrant. Leakage or other imperfections found in either test shall be corrected before the hydrant is accepted. The test is not required for any existing fire hydrants.

7 Workmanship:

Document No. 2012 FIRE HYDRANTS (8/13/14)

- 7.1 Fire Hydrant installation shall conform to the requirements of Subsection 307.09, "Setting Hydrants", of the Standard Specifications for Public Works Construction.
- 7.2 Contractor shall notice, coordinate and cooperate with the Fire Department before any shut-down of a fire hydrant or water line is to be made. Contractor shall keep the Fire Department fully informed on any emergency repairs being made which affect the water distribution system.
- 7.3 All buried metallic materials of the fire hydrant assemblies shall be encased in polyethylene (plastic wrap) in accordance with the requirements of AWWA C105.
- 7.4 Before the fire hydrant assembly is backfilled, Contractor shall contact the inspector for an inspection review using the Carson City Public Works Department "Inspection for Fire Hydrants" form. The inspection shall be performed in the presence of Contractor and the inspector. Also included in the inspection will be a check of the street valve to assure full open position.

END OF DOCUMENT 2012

TECHNICAL SPECIFICATIONS

DOCUMENT No. 2013 THRUST BLOCKS (8/21/13)

1. General:

- 1.1. Thrust blocks shall be installed in the locations shown on the Drawings and in general, everywhere a buried pressure conduit changes direction according to Carson City "Standard Details for Public Works Construction".

2. Materials:

- 2.1. Concrete used for thrust blocks shall have a minimum compressive strength of 4000 psi at twenty-eight (28) calendar days when tested in accordance with ASTM.

3. Installation:

- 3.1. Thrust blocks shall be installed such that they bear against the pipe fitting (not the pipe) on one side and against undisturbed earth on the other side.
- 3.2. Thrust block concrete shall not obstruct removal of flange bolts from fittings. Concrete shall be prevented from adhering to the fittings. Either a liquid bond breaker shall be applied to the fitting, or an impervious membrane (plastic, building paper, etc.) shall be used.
- 3.3. The bearing area against the undisturbed soil shall be measured in a vertical plane, perpendicular to the axis of the pipe, or the line bisecting the extensions of the pipes entering a fitting. The bearing area shall be as set forth in the thrust block table in the Drawings.

END OF DOCUMENT 2013

TECHNICAL SPECIFICATIONS

DOCUMENT No. 2014 COUPLINGS, DISMANTLING, AND EXPANSION JOINTS (8/21/13)

1. General:

- 1.1. Couplings, dismantling and expansion joints shall be installed in the locations and conform to the sizes shown on the Drawings.

2. Materials:

2.1.1. Bolted Couplings:

- 2.1.1.1. Bolted couplings shall have malleable iron followers, steel sleeves, high strength bolts with hexagon nuts and wedge-type resilient material gaskets. Bolted couplings shall be designed for a working pressure of 150 psi and shall be as manufactured by Romac Series 501, or equal. Coupling restraints shall be installed in the locations as shown on and detailed in the Drawings.

2.1.2. Flanged Coupling Adapters:

- 2.1.2.1. Flanged coupling adapters shall have high grade gray iron or steel bodies with malleable or ductile iron followers with high strength bolts and wedge-type resilient material coupling gaskets and "O-ring" flange gaskets. Flange coupling adapters shall be designed for a working pressure of 150 psi and shall be as manufactured by Romac Series FCA501, or equal.

2.1.3. Restrained Couplings:

- 2.1.3.1. When noted on the Drawings, bolted couplings or flanged coupling adapters shall be restrained with couplings equipped with anchor boss and anchor bolts. These couplings shall be installed in strict conformance to the Drawings and manufacturer's recommendations. Restrained couplings for PVC pipe shall restrain by contacting the circumference of the pipe. Restraining devices which point load PVC pipe, in the opinion of Construction Manager, shall not be considered or allowed.

2.1.4. Expansion Joints:

- 2.1.4.1. Expansion joints shall be installed where indicated on the Drawings. Expansion joints shall have a neoprene cover and a teflon tube and be equipped with thrust control rods. Expansion joints shall be Holz Series 980 molded expansion joints or equal.

2.1.5. Dismantling Joints:

- 2.1.5.1. Dismantling joints shall have high grade gray iron or steel bodies with malleable or ductile iron followers with high strength bolts and wedge-type resilient material coupling gaskets and O-ring flange gaskets. Dismantling joints shall be as manufactured by Romac Series DJ 400, or approved equal.

3. Installation:

- 3.1. Couplings, dismantling and expansion joints shall be installed in accordance with the manufacturer's recommendations. All buried couplings shall be wrapped with two (2) layers of ten (10) mil polyethylene film and sealed with ten (10) mil plastic tape.

TECHNICAL SPECIFICATIONS

- 3.2. Mechanical fittings, joints and appurtenances shall be assembled and installed using a torque measuring or torque-indicating wrench and per AWWA standards. The use of an impact wrench or similar construction method is prohibited.

END OF DOCUMENT 2014

TECHNICAL SPECIFICATIONS

DOCUMENT No. 2015.1 PVC WATER MAIN HYDROSTATIC TESTING (8/25/2014)

1. General:

- 1.1. This specification supersedes Section 336.03.08, Pressure Line - Pressure and Leakage Tests, of the Standard Specifications. Water mains shall be pressure tested in accordance with AWWA C605 and all the following requirements.

2. Test Pressure:

- 2.1. Test pressure for water distribution pipe shall be the class designation/rating of the pipe.

3. Procedure:

- 3.1. Pressure and leakage tests shall be performed at the same time. The total testing time for each section of a new main installed shall be a minimum of two (2) hours.
- 3.2. When pipeline installation, testing and backfilling can be accomplished in the same day, backfill only enough to prevent lifting of the pipe prior to filling with water and field testing. When conditions require that trenches be backfilled immediately after the pipe has been laid, testing shall be conducted prior to placement of permanent surface.
- 3.3. After the main has been laid it shall be filled with water for a minimum of twenty-four (24) hours before being subjected to the hydrostatic pressure test. Each section of pipeline shall be filled slowly with water and all air expelled by means of taps at points of highest elevation.
- 3.4. The specified test pressure shall be applied by means of a pump connected to the pipe in a manner satisfactory to Engineer. The test pressure shall be maintained for the specified time during which all exposed pipe, couplings, fittings, valves, and hydrants shall be examined carefully.
- 3.5. All cracked or defective elements shall be removed and replaced and the test repeated until all visible leakage has been stopped and the requirements as specified in Subsection 4 Allowable Leakage have been met.

4. Allowable Leakage:

- 4.1. No pipe installation will be accepted if the leakage for the section of the line that is tested is greater than that determined by the following formula:

	$Q = \frac{LD\sqrt{P}}{148,000}$
Where:	Q = Allowable Leakage (gallons per hour)
	L = Length of pipe section being tested
	D = Nominal diameter of pipe (inches).
	P = Test pressure (psig).

- 4.2. If the test leakage in any section is greater than permitted, Contractor shall, at his own expense, locate and repair the defective materials until the leakage is within the permitted allowance. All visible leaks shall be repaired regardless of the amount or rate of leakage.

TECHNICAL SPECIFICATIONS

5. Measurement of Leakage:

- 5.1. Leakage shall be defined as the quantity of water that must be supplied into the newly laid pipe, or any valved section thereof, to maintain pressure within five (5) psi (0.35 Bar) of the specified test pressure after the air in the pipeline has been expelled and the pipe filled with water. The quantity of water supplied to maintain pressure shall be quantified by means of a positive displacement measurement from a reservoir of known volume. Leakage shall not be measured by a drop in pressure in a test section over a period of time.

END OF DOCUMENT 2015.1

TECHNICAL SPECIFICATIONS

DOCUMENT No. 2016 WATER MAIN DISINFECTING (8/21/13)

1. General:

- 1.1. Disinfection of water mains shall be accomplished in accordance with all the requirements set forth in AWWA C651-05 unless otherwise specified herein.
- 1.2. Precautions shall be taken to protect pipe interiors, fittings, and valves against contamination. Pipe delivered for construction shall be stored so as to minimize entrance of foreign material. When pipe laying is not in progress, for example, at the close of the day's work or during breaks or rest periods all openings in the pipeline shall be closed by water tight plugs. Joints of all pipe in the trench shall be completed before work is stopped. If water accumulates in the trench, the plugs shall remain in place until the trench is dry.
- 1.3. If dirt, that in the opinion of Engineer, will not be removed by flushing enters the pipe, the interior of the pipe shall be cleaned and swabbed as necessary with a 5% hypochlorite disinfecting solution.
- 1.4. No contaminated material capable of supporting growth of micro-organisms shall be used for sealing joints. Packing material shall be handled in such a manner as to avoid contamination.
- 1.5. Yarning or packing material shall consist of molded or tubular rubber rings or rope of treated paper, or other approved materials. Materials such as jute or hemp shall not be used. Packing Materials shall be handled in a manner which prevents contamination.
- 1.6. The lubricant used in the installation of sealing gaskets shall be suitable for use in potable water. It shall be delivered to the job in enclosed containers and shall be kept clean.

2. Procedure:

2.1. General:

- 2.1.1. Unless otherwise stated herein, the tablet method of disinfection shall be used. Tablets shall be calcium hypochlorite tablets, conform to ANSI/AWWA B300, and must contain approximately 65 percent available chlorine by weight. Calcium hypochlorite tablets intended for pool use shall not be used. However, since this method requires scrupulous cleanliness to be effective, it will not be allowed if trench water or foreign material has entered the main. If the pipe, in Engineer's opinion is not in a clean condition another method prescribed in AWWA C651 -05 shall be used for disinfection even if the tablets have already been installed.

2.2. Placement of Tablets:

- 2.2.1. Tablets shall be placed in each section of pipe and also in hydrants, hydrant branches, and other appurtenances. They shall be attached by an adhesive, except for the tablets placed in hydrants and in the joints between the pipe sections. All the tablets within the main must be at the top of the main. If the tablets are fastened before the pipe section is placed in the trench, their position shall be marked on the section to assure that there will be no rotation.
- 2.2.2. Disinfection tablets shall be placed using Titebond Multi-Purpose Clear 100% Silicone, or approved equal food grade silicon. There shall be no adhesive on the tablet except on the broad side next to the surface to which the tablet is attached.

TECHNICAL SPECIFICATIONS

2.3. Filling and Contact:

2.3.1. When installation has been completed, the main shall be filled with water at a velocity of less than one (1) foot per second. Precautions shall be taken to ensure that air pockets are eliminated. This water shall remain in the pipe for at least twenty-four (24) hours. If the water temperature is less than 41°F, the water shall remain in the pipe for at least 48 hr. Valves shall be manipulated so that the strong chlorine solution in the line being treated will not flow back into the line supplying the water.

2.4. Dosage:

2.4.1. The number of hypochlorite tablets to be attached to the inside of each section of pipe shall be as shown in the following Table:

Number of 5-g calcium hypochlorite tablets required for dose of 25 mg/L*						
Pipe Diameter (inches)	Length of Pipe Section (feet)					
	13 or less	18	20	30	40	
Number of 5-g Calcium Hypochlorite Tablets						
4	1	1	1	1	1	
6	1	1	1	2	2	
8	1	2	2	3	4	
10	2	3	3	4	5	
12	3	4	4	6	7	
14	4	5	5	8	10	
16	4	6	7	10	13	
18	6	7	8	12	16	
20	7	9	10	15	20	
24	9	13	14	21	28	

*Based on 3.25-g available chlorine per tablet; any portion of tablet rounded to next higher integer

Table based on Table 2 and Part 4.4.2.2 of AWWA C651-05. For other pipe sizes and lengths, refer to AWWA C651-05

2.5. Final Flushing:

2.5.1. After the applicable retention period, the heavily chlorinated water shall be flushed from the main until the chlorine concentration in the water leaving the main is no higher than that generally prevailing in the system, or less than one (1) mg/l. Contractor is responsible for disposal of chlorinated flushing water. No additional payment will be made for disposal of flushing water. Chlorine residual determination shall be made to ascertain that the heavily chlorinated water has been removed from the pipeline.

2.6. Bacteriologic Tests:

2.6.1. After final flushing and before the water main is placed in service, two consecutive sets of acceptable samples, taken 24 hours apart, shall be collected from the new main. At least one set of samples shall be collected from every 1,200 feet of new water main, plus one set from the end of the line and one set from each branch and submitted by Contractor to the Carson City Wastewater Reclamation Plant Laboratory for testing for bacteriologic quality and shall show the absence of coliform organisms.

2.7. Repetition of Procedure:

2.7.1. If the initial disinfection fails to produce satisfactory samples, disinfection shall be repeated until satisfactory samples have been obtained at Contractor's expense. The tablet

TECHNICAL SPECIFICATIONS

method cannot be used in these subsequent disinfections. When the samples are satisfactory, the main may be placed in service.

END OF DOCUMENT 2016

TECHNICAL SPECIFICATIONS

DOCUMENT No. 2017 UNDERGROUND MARKING TAPE AND TRACER WIRE (8/21/13)

1. General:

- 1.1. Underground marking tape shall be installed above all buried water pipelines.

2. Materials:

- 2.1. Tape shall be non-detectable polyethylene marking tape. Tape shall be blue in color and shall be three (3) inches wide by 4 mil thick and shall bear large printing denoting, "Buried Water Line Below".
- 2.2. Tracer wire shall be 12 gauge coated solid copper wire taped every 5 (five) feet to all water mains, water services, air releases etc. and shall remain continuous and conductive throughout all components of the water system. All splices, as from a service wire to a main wire, shall be soldered and wrapped with UL listed electrical tape.

3. Installation:

- 3.1. Underground marking tape shall be installed according to the manufacturer's instructions and as shown on the Drawings.
- 3.2. Marking tape shall be continuous from valve to valve. Tape shall be placed flat with the writing facing up and shall be laid twelve (12) inches above the top of pipe between the bedding and the trench backfill.
- 3.3. Tracer wire shall be installed as shown on the Drawings.
- 3.4. Tracer wire shall be continuous throughout the entire project, and shall be connected to any existing water tracer wire exposed through the course of the project.

END OF DOCUMENT 2017

TECHNICAL SPECIFICATIONS

DOCUMENT No. 2019 AIR RELEASE, AND AIR AND VACUUM VALVES (8/21/13)

1. General:

- 1.1. Air release, and air and vacuum valves shall be installed in the locations and shall conform to the types and sizes shown on the Plans.

2. Materials:

- 2.1. Air and vacuum valves shall be designed to allow large quantities of air to escape out the orifice when filling a pipeline and to close water tight when the liquid enters the valve. The air and vacuum valve shall also permit large quantities of air to enter through the orifice when the pipeline is being drained to break the vacuum. The valve shall consist of a body, cover, baffle, float and seat. The baffle will be designed to protect the float from direct contact of the rushing air and water to prevent the float from closing prematurely in the valve. The seat shall be fastened into the valve cover without distortion and shall be easily removed if necessary. The float shall be stainless steel designed to withstand 300 psi or more. The float shall be center guided for positive seating.
- 2.2. Air release valves shall be designed to release accumulated air from a pipe while the pipe is in operation and under pressure. Resilient seats shall be replaceable and provide drop tight shut-off to the full valve operating pressure rating of 150 psi.
- 2.3. The bolts and nipples of the valve must be tar coated for resistance to corrosion. Air release valves shall be "Valmatic" or APCO brand valves, or approved equal. Air and vacuum valves shall be APCO brand, or approved equal.

3. Installation:

- 3.1. Air release, and air and vacuum valves shall be installed in accordance with the manufacturer's recommendations.
- 3.2. Mechanical fittings, joints and appurtenances shall be assembled and installed using a torque measuring or torque-indicating wrench and per AWWA standards. The use of an impact wrench or similar construction method is prohibited.

END OF DOCUMENT 2019

TECHNICAL SPECIFICATIONS

Document No. 3001 STAKING, EXCAVATION, BACKFILLING AND COMPACTING FOR SEWER LINES (12/30/14)

1. General:

- 1.1. Before any excavation on the project, Contractor shall notify all local utility companies and "Call Before You Dig" at 1-800-227-2600. Excavation shall include the removal of all materials or obstructions of any nature, the installation and removal of all sheeting and bracing and the control of water necessary to construct the work as shown. Excavation work shall be performed in a safe and proper manner with suitable precautions taken against hazards of every kind. Sheeting and shoring shall conform to the requirements of OSHA and Section 305.06 of the Standard Specifications. There is a significant likelihood that groundwater will be encountered during structure excavation. Contractor shall be prepared to install and maintain pumping equipment necessary to control groundwater during construction.
- 1.2. Pumping to maintain sewer service will be required. Contractor shall have on site, sufficient sized pumps and length of hose to accomplish this task. Contractor shall have a backup pump available at all times. Contractor shall be responsible for all cleanups, fines or other ramifications resulting from a spill.
- 1.3. Back fill during freezing weather shall not be done except by permission of Construction Manager or his representative. No backfill material shall be installed on frozen surfaces, nor shall frozen materials, snow or ice be placed in any backfill.

2. Reference Specifications and Standards:

- 2.1. Relative compaction or density, when hereinafter referred to, means the in-place dry density of the soil expressed as a percentage of the maximum dry density of the same soil as determined by the ASTM D1557 test procedure. The costs of site compaction or density testing shall be paid for by Carson City. The costs of all retests (from failed tests) shall be paid for by Contractor.

3. Staking Out the Work:

- 3.1. Contractor shall retain a Nevada Licensed Professional Land Surveyor, and the Surveyor or his Subordinates shall stake out the horizontal and vertical positions of all the Work. Contractor shall satisfy himself as to the accuracy of all measurements before constructing any permanent structure and shall not take advantage of any errors found on the Drawings. Where new construction connects to existing facilities, Contractor shall pothole and establish the exact locations and elevations prior to construction of the facilities.
- 3.2. Construction surveying, at a minimum, should include the location and depth for

manholes, and intermediate stakes for line and grade of the sewer lines. It shall be Contractors responsibility to expose the existing sewer lines at the points of connection for the new lines and to maintain the depths of cover and slopes as indicated on the Drawings. It will also be Contractor's responsibility to pothole existing utilities and, after approval by Construction Manager, modify the grade as required to match or avoid existing utilities while maintaining the general slope of the pipe.

4. Trench Work:

4.1. Trench Configuration and Alignment:

4.2. Trenches shall be excavated to provide for the bedding as specified in subsection 11.1 Bedding.

4.3. The new pipeline shall be laid essentially as per the alignments and grades shown on the Drawings.

4.4. Trenches and other excavations shall have the minimum width which Contractor can effectively excavate and install the improvements. Excessive widths will not be permitted. Trenches shall have a minimum width of twenty four (24) inches greater than the outside diameter of the pipe to be installed. Deviations from this recommended width must be submitted to Construction Manager in writing for approval. The bottom of the trench shall be graded uniformly to provide a continuous bedding support under the pipe, and to allow the pipe to be laid to the grades and alignments shown in the Drawings.

5. Pipe Bedding:

5.1. The trench shall be over excavated to a depth of at least six (6) inches below the bottom of the pipe and backfilled to the required grade of the bottom of the pipe with bedding material. The pipe bedding shall be brought to optimum moisture content and compacted to not less than 90% relative density. The pipe bedding at the trench bottom shall have a flat or semicircular cross section. The bottom of the trench for all pipe shall be graded and prepared to provide a firm and uniform bearing surface throughout the entire length of each pipe section except for excavation required at joints. Pipe couplings shall not rest on the trench bottom and laying the pipe on mounds will not be allowed.

6. Bedding Through the Pipe Zone:

6.1. After center loading the pipe to prevent lateral movement, select granular material free from stones, clods, or other deleterious material shall be placed in the trench simultaneously on each side of the pipe for the full width of the trench in layers not to exceed eight (8) inches in depth. Each layer or lift shall be compacted to at least 90% of maximum density, evenly, on each side of the pipe

throughout the pipe zone. The pipe zone is to extend from bottom of the pipe to twelve (12) inches above the top of the pipe and shall be backfilled with bedding material as specified herein.

7. Backfill Above the Pipe Zone:

- 7.1. From twelve (12) inches above the top of pipe to the top of the trench, if not in existing pavement, or bottom of the pavement structure, if in existing pavement, pipe backfill shall consist of material as specified in subsection 11.2 Backfill. No oil cake, bituminous pavement, concrete, rock or other lumpy material shall be used in the backfill. Backfill material shall be compacted to not less than 90% relative density. All trenches shall be backfilled after pipe fittings and appurtenances have been installed, inspected and approved. All trash, wood, large rocks, waste material and other objectionable debris shall be removed from the excavation prior to any material being placed in the trench.
- 7.2. Where existing underground pipes or conduits larger than three (3) inches in diameter cross the trench above the new work, the backfill from the bottom of the trench to the spring line of the intersecting pipe or conduit shall be Crushed Gravel Base material, Type 2, Class B, Aggregate Base conforming to the requirements of Section 200.01.03 of the Standard Specifications, compacted to 90% of relative density. The aggregate base material shall extend two (2) feet on either side of the intersecting pipe or conduit which will insure that the material will remain in place while other backfill is placed.
- 7.3. Backfill by jetting shall not be allowed. Backfill shall be densified by mechanical compaction.

8. Site Excavation:

- 8.1. The bottom of the excavation shall not be more than one-tenth (0.10) foot above or below the lines and grades specified. If the elevation of structure excavation is not specified the excavation shall be not more than one-tenth (0.10) foot above or below the elevation specified for fill material below the structure. Cut slopes shall vary no more than five-tenths (0.5) foot from specified grade unless the excavation is in rock where the maximum variation may be two (2) feet. Unless otherwise specified, excavations shall extend a sufficient distance from walls and footings to allow for placing and removal of forms, installation of services, and for inspection, except where concrete is specified to be placed directly against excavated surfaces. Upon completion of excavation, the existing subgrade shall be compacted to a minimum of 90% relative density.
- 8.2. Should the excavation be carried below the lines and grades specified on the Drawings, or should the bottom of the excavation be disturbed because of Contractor's operations and require over-excavation and backfill, Contractor shall refill such excavated space to the proper elevation in accordance with the

procedure specified for backfill.

9. Rock Excavation and Blasting:

- 9.1. No blasting will be permitted without the approval of Construction Manager. When blasting is permitted, it shall be done only by skilled operators and under the direction of a competent, properly licensed foreman.
- 9.2. Blasting will be permitted only when proper precautions are taken for the protection of persons, the work, and existing structures. Any damage done to persons, private property, the work, or existing structures shall be the responsibility of Contractor.
- 9.3. Blasting shall be done with explosives of such power and in such quantities and positions as not to make the excavation unduly large, or to shatter the faces of cuts which are to remain open. Excessive blasting or "overshooting" will not be permitted, and any material outside the authorized cross-section which may be shattered or loosened by blasting shall be removed and replaced with earth as herein specified, at Contractor's expense. Construction Manager shall have authority to require Contractor to discontinue any method of blasting which leads to "overshooting" or is dangerous to the public or destructive to property or to natural features.
- 9.4. Permits for blasting shall be obtained and paid for by Contractor.

10. Sheeting and Shoring:

- 10.1. Excavation for trenches shall be properly and substantially sheeted, braced, and shored as required by trench conditions. Sheeting, bracing, and shoring shall be designed and built to withstand all loads that might be caused by earth movement or pressure and shall be rigid, maintaining shape and position under all circumstances. Contractor(s) design for all sheeting and shoring shall be signed and sealed by a licensed Nevada Civil or Structural Engineer and the drawings submitted to Construction Manager prior to its construction.
- 10.2. During backfilling, any shoring shall be carefully removed by Contractor in such a manner as will result in a minimum of caving, lateral movement, or flowing of the soil. On approval of Construction Manager, Contractor may leave shoring in place, but in such an event, no payment will be made by Carson City for such materials left in place. Where trench shoring is left in place, it shall not be braced against the pipe.

11. Materials:

11.1. Bedding:

- 11.1.1. Pipe bedding material shall conform to the requirements of Section 200.03.02, Class A Backfill, of the Standard Specifications, except as noted on the drawings.
- 11.1.2. Bedding shall be placed in accordance with Section 305.08, Bedding, of the Standard Specifications.

11.2. Backfill:

- 11.2.1. Trench backfill shall conform to the requirements of Section 200.03.06, Class E Backfill, of the Standard Specifications, unless otherwise specified.
- 11.2.2. Trench backfill shall be placed and compacted in accordance with Section 305, Trench Excavation and Backfill, of the Standard Specifications.
- 11.2.3. Backfill for any structure shall be Crushed Gravel Base material, Type 2, Class B, Aggregate Base conforming to the requirements of Section 200.01.03 of the Standard Specifications.
- 11.2.4. If site excavated material meets the requirements for Class (E) Backfill but exceeds optimum moisture content, Contractor shall take whatever measures are necessary to dry the material to a compactable moisture content. No additional compensation shall be allowed for such measures. If site excavated material does not meet "Class E Backfill" requirements in accordance with the Standard Specifications, Contractor may be directed by Construction Manager to remove and dispose of the unsuitable material to an approved disposal location and import acceptable material.

12. Pavement Structure:

- 12.1. Defined as that section from the top of the backfill to the road wearing surface. This section shall consist of Crushed Gravel Base material, Type 2, Class B, Aggregate Base conforming to the requirements of Section 200.01.03 of the Standard Specifications, compacted to 95% relative density overlaid with asphalt concrete at a depth to match the contiguous pavement, but not less than that specified for roadway sections. Refer to the Permanent Pavement Patch Detail on the Drawings and, if applicable, also refer to the Patching Details for Work within NDOT Right-of Way.

13. Construction:

13.1. Maximum Length of Open Trench:

- 13.1.1. Except by permission of Construction Manager, the maximum length of open trench where prefabricated pipe is used shall be five hundred (500) feet, or the distance necessary to accommodate the amount of pipe installed in a single day, whichever is the greater.

13.2. Control of Water:

- 13.2.1. When water is encountered, Contractor shall furnish, install, maintain and operate all necessary machinery, appliances, and equipment to keep excavations free from water until the placing of the bedding material, laying and jointing of the pipe, pouring of concrete, and placing of the backfill material has been completed, inspected, and approved and all danger of flotation and other damages is removed. Groundwater pumped from the trench shall be disposed of in such a manner as will not cause injury to public or private property, or constitute a nuisance or menace to the public, and shall be subject to the prior approval of Construction Manager and all regulatory requirements of the State of Nevada. If well points are used for dewatering, they shall be removed or abandoned according to State of Nevada regulations.

13.3. Special Foundation Treatment:

- 13.3.1. Whenever the bottom of the trench is soft, yielding, or in the opinion of Construction Manager otherwise unsuitable as a foundation for the pipe, the unsuitable material shall be removed to a depth approved by Construction Manager and replaced with suitable material approved by Construction Manager. Payment of this work will be made only if the bottom of the trench has become unstable due to circumstances beyond the control of Contractor. Payment for this work will be made as specified in subsection 6.4 Modification Procedures of the General Conditions, unless otherwise provided for in these Contract documents.

13.4. Restoration of Roadway Surfaces:

- 13.4.1. All road shoulders and pavement which are broken or damaged due to Contractor's operations shall be reconstructed by Contractor at no additional cost to Carson City. Reconstruction shall be subject to the approval of Construction Manager.

13.5. Repairs Required by Trench Settlement:

- 13.5.1. If, at any time during a one (1) year period from the date of final acceptance of the project, there is any settlement of the trenches

requiring repairs to be made, or should any other defect appear in the system due to negligence or carelessness on the part of Contractor, Carson City will notify Contractor to immediately make such repairs as may be deemed necessary at Contractor's expense.

14. Surplus Material:

- 14.1. All surplus material shall be disposed of offsite in accordance with applicable ordinances and environmental requirements. Contractor shall be responsible for ultimate disposal of surplus material.

END OF DOCUMENT 3001

TECHNICAL SPECIFICATIONS

Document No. 3002 SEWER MAINS, SERVICES & APPURTENANCES (2/4/15)

1. Scope:

- 1.1. The work to be done under this section consists of furnishing labor, equipment, materials and incidentals and performing all work necessary for furnishing and installing sewer mains, manholes, pump stations, force mains and laterals.
- 1.2. Trench excavation and backfill shall conform to the requirements as specified in Document No. 3001 Staking, Excavation, Backfilling, and Compacting for Sewer Lines of these Technical Specifications.

2. Materials:

2.1. Gravity Sewer Pipe:

- 2.1.1. Gravity Sewer Pipe shall be PVC SDR 35 pipe as specified in Section 203.15 of the Standard Specifications, unless otherwise noted on the drawings.

2.2. Pipe Fitting:

2.2.1. Gravity Wyes and Bends:

- 2.2.1.1. All fittings, wyes and bends shall be manufactured for the brand and type of pipe supplied. The joints shall be Neoprene or rubber-gasketed bell and spigot or with couplings to match pipe specifications.
- 2.2.1.2. All lateral connections shall enter the sewer main on a 45 degree angle in the center of the top quadrant. Laterals are not to drop straight in from the top of main.

2.3. Manholes:

- 2.3.1. Manholes shall be precast, unless otherwise approved by Construction Manager, and as specified in Section 204 of the Standard Specifications, except as indicated on drawings. An approved water stop shall be placed on all PVC pipe entering the manhole.

3. Workmanship:

3.1. Pipe:

- 3.1.1. The sewer pipe shall be installed according to Section 306 of the Standard Specifications. Variance from established line and grade shall not be greater than five hundredths of a foot from grade and not more than five hundredths of a foot from alignment, and shall always maintain the slope as specified on the drawings. Following the completion of the installation, the pipe shall be balled, flushed, and mandreled.
- 3.1.2. Contractor shall be required to use a pipe laser while installing the pipe for grade and alignment control.

3.2. Manholes:

- 3.2.1. Bases shall be constructed to maintain invert flow slopes with minimum thickness of concrete under inverts and pipe entry into manhole as indicated on drawing details. Sections and extensions shall be laid straight and true with rim level. The joints shall be sealed with a double layer of an approved plastic or mastic material to exclude all groundwater. After setting each section, push with weight, such as backhoe bucket, with

TECHNICAL SPECIFICATIONS

wood blocking to prevent damage, to set joint firmly to prevent future settling. After installation and before backfilling, fill/coat the upper interior 24-inch section joints/cracks as indicated on drawing details with an approved non-shrink grout. All manhole joints so grouted shall be at no additional cost to Carson City.

4. Sewer Line Tests:

4.1. Air Testing:

4.1.1. The following provisions supercede Section 336.03.07.04, Air Pressure Tests, and Section 336.03.07.04.1, Test Requirements, of the Standard specifications.

4.1.2. Amount of Testing:

4.1.2.1. Contractor shall air test all the sewer lines after backfilling and settling of the trenches and shall furnish all equipment and personnel required to perform the tests. In addition to the air test of pipe, Contractor shall vacuum test all of the manholes. Any manhole which doesn't pass shall be repaired and retested until satisfactory.

4.1.2.2. To facilitate the detection of any leaks that may have occurred during the pipe laying operation, Contractor may, as his option, air test any or all of the sewer lines prior to backfilling. However, this test will be in addition to the required air or hydrostatic test following the backfilling and settling of the trench.

4.1.3. Leakage Allowance:

4.1.3.1. The leakage allowance requirements of the air test shall be considered satisfied for the section of pipeline being tested if the time required for the pressure to decrease from 3.5 pounds per square inch (psi) to 2.5 psi is greater than 30 minutes between manholes.

4.1.4. Testing Procedure:

4.1.4.1. The low pressure air test is a test which determines the rate at which air under pressure leaves an isolated section of pipeline. This rate indicates the presence or absence of pipe damage and/or pipe of poor quality. The test procedure is described as follows: The section of pipe to be tested is plugged at each end. The ends of all branches, laterals, and wyes which are to be included in the test are sealed or plugged. All plugs shall be carefully braced to prevent slippage and blowout due to internal pressure. One of the plugs provided must have an inlet tap or the provision for connecting an air hose.

4.1.4.2. Connect one end of the air hose to the inlet tap on the plug and connect the other end of the hose to portable air control equipment. The air control equipment can then be connected to a source of air supply such as a portable air compressor.

4.1.4.3. After the air hoses are properly connected, inject air into the test section. Monitor the air pressure so that the pressure inside the pipe does not exceed five (5) pounds per square inch gauge (psig).

4.1.4.4. When the pressure inside the test section reaches four (4) psig, throttle the air supply so that the internal pressure is maintained between four (4) and three and five-tenths (3.5) psig for at least two (2) minutes for the temperature of the air to come to equilibrium with the pipe walls.

4.1.4.5. After the temperature has been allowed to stabilize for the two (2) minute

TECHNICAL SPECIFICATIONS

period, the air supply should be disconnected, and the pressure allowed to decrease to three and five-tenths (3.5) psig. At three and five-tenths (3.5) psig, a stop watch is to be started to determine the time required for the pressure to drop to two and five-tenths (2.5) psi.

4.2. Deflection Test:

4.2.1. The following supercedes Section 336.03.09.01, Deflection Test for Plastic Pipe and Fittings, of the Standard Specifications:

4.2.2. Installed pipe shall be tested to insure that vertical deflections for plastic pipe do not exceed the maximum allowable deflection. For all pipes 27-inch ID or less, a mandrel shall be pulled through the pipe by hand to ensure that maximum allowable deflections, as shown in the following table, have not be exceeded.

Table 1

Nominal Size (inches)	SDR-35 ASTM Base Inside Diameter (inches)	Allowable Deflection (percent)	Mandrel Size (inches)
8	7.665	5	7.282
10	9.563	5	9.085
12	11.361	5	10.793
15	13.898	4	13.342
18	16.976	4	16.297
21	20.004	4	19.204
24	22.480	4	22.581
27	25.327	4	24.314

4.2.3. Deflection tests shall not be performed until after completion of placement and compaction of backfill. The pipe shall be flushed prior to testing. If the mandrel fails to pass, the pipe will be deemed to be overdeflected. All costs incurred by Contractor attributable to mandrel and deflection testing, including any delays, shall be borne by Contractor at no additional cost.

4.2.4. The mandrel shall:

4.2.4.1. Have an odd number of legs (9 legs minimum) and be a rigid, nonadjustable mandrel having an effective length not less than its nominal diameter.

4.2.4.2. Be fabricated of steel; be fitted with pulling rings at each end; be stamped or engraved on some segment, other than a runner, indicating the pipe material specification, nominal size, and mandrel OD; and be furnished in a suitable carrying case labeled with the same data as stamped or engraved on the mandrel.

4.3. Television Inspection:

4.3.1. Following completion of the pipe installation, and after the pipe has been balled, flushed, and mandreled, Carson City personnel will television inspect the sewer pipe installation. Contractor shall provide adequate notice to Carson City as to when lines will be ready for television inspection. Any obvious defects in grade, installation, materials, leaks or other problems shall be repaired by Contractor. Contractor shall provide all traffic control for Carson City's inspection.

TECHNICAL SPECIFICATIONS

4.4. Vacuum Testing of Manholes:

4.4.1. The following provisions are added to the Standard Specifications:

4.4.2. **Vacuum Tests of Manholes.** Contractor shall furnish all labor, equipment, and materials necessary to perform a manhole vacuum test. Vacuum test equipment shall be approved by Construction Manager or his representative Inspector. All vacuum tests shall be conducted in the presence of Construction Manager or his representative.

4.4.3. **Test Requirements.** Each manhole shall be tested immediately after assembly and prior to backfilling. All lift holes shall be plugged with an approved non-shrink grout. All pipes entering the manhole shall be plugged, taking care to securely brace the plug from being drawn into the manhole. The test head shall be placed at the inside of the top of the cone section and the seal inflated in accordance with the manufacturer's recommendations.

4.4.4. A vacuum of 10 inches of mercury shall be drawn and the vacuum pump shut off. With the valves closed, the time shall be measured for the vacuum to drop to 9 inches. The manhole shall pass if the time is equal to or greater than then minimum test time as specified in ASTM C1244 Table 1 "Minimum Test Times for Various Manhole Diameters in Seconds."

4.4.5. If the manhole fails the initial test, necessary repairs shall be made with a non-shrink grout while the vacuum is still being drawn. Retesting shall proceed until a satisfactory test is obtained.

5. **Water and Sewer Main Separations:**

5.1. Water distribution and sewage collection lines must be laid in separate trenches at least 10 feet apart. In well drained dry ground where sewage flow is by gravity at greater than 2 feet per second, water lines may be in the same trench on undisturbed earth 6 feet horizontally and 3 feet vertically above the sewer line.

5.2. All water and sewer main crossings shall be protected by using C900-Class 150 pipe for the sewer main a distance of 10 feet on each side of the water main. No joints will be allowed within 10 feet of the water main. An alternate method of concrete encasement for the 10 feet on each side of the water main will also be allowed. (See Carson City Standard Detail, Drawing No. C-9.1 (page 31).

5.3. Sewer mains crossing water mains shall be laid to provide a minimum vertical distance of eighteen inches (18") between the outside of the water main and the outside of the sewer main. This shall be the case where the water main is either above or below the sewer. The crossing shall be arranged so that the sewer joints will be equal distanced and as far as possible from the water main joints. Where the water main crossed under a sewer, adequate structural support shall be provided for the sewer to prevent damage to the water main. In crossing areas where there is less than eighteen inches (18") vertical clearance and where C-900 pipe is used a minimum of six inches (6") between outside of sewer pipe and outside of water pipe is required.

6. **END OF DOCUMENT 3002**

TECHNICAL SPECIFICATIONS

Document No. 3003 POLYVINYL CHLORIDE PIPE FOR SEWER (12/30/14)

1. General:

- 1.1. This section covers sanitary sewer polyvinyl chloride pipe which shall be furnished and installed complete with all jointing materials, fillings and other appurtenances shown on the Drawings or otherwise required for a complete installation. Contractor shall furnish, install, and test pipe, fittings and appurtenances of the dimensions and types and to the lines and grades shown on the Drawings and specified herein.

2. Unloading PVC Pipe:

- 2.1. Prolonged exposure to temperatures near freezing make PVC sensitive to impact and extra care shall be taken in handling PVC during cold weather.
- 2.2. PVC pipe may be off-loaded by hand, either by passing over the side or off the truck end. Sliding one (1) length on another is standard practice in unloading PVC pipe, but lengths in the bottom layer shall be lifted off of the rough surface of the truck body to avoid erosion.
- 2.3. Compact shipping units (palletized bundles in a wood frame) are used to ship large orders of pipe. These units can be unloaded by conventional fork lifts.

3. Materials:

3.1. Description:

- 3.1.1. This specification covers PVC Solid Wall Pipe to be used for sanitary sewers, storm drains and house connection sewers. Pipe and fittings shall be made from PVC compounds as defined and described in ASTM D-1784 for Rigid Poly (vinyl chloride), Compounds and Chlorinated Poly (vinyl chloride) Compounds. Pipe and fittings shall meet the requirements of ASTM D-3034 PSM (SDR 35). The pipe and materials shall be made of PVC plastic having a cell classification of 1245B or 1245C (with minimum tensile modulus of 500.000 psi), as defined in ASTM D-1784.

3.2. Testing:

- 3.2.1. Hydrostatic pressure test. A pipe joint constructed of joint compound shall not leak when subjected to an internal hydrostatic pressure of ten (10) pounds per square inch for a period of five (5) minutes.

3.3. Pressure Pipe:

Document No. 3003 POLYVINYL CHLORIDE PIPE FOR SEWER (12/30/14)

3.3.1. When called for on the Drawings, in the details or in these specifications, PVC pressure pipe shall conform to AWWA C900. Pipe class shall be as shown on the Drawings or as called for in these specifications and have an outside diameter equivalent to cast iron pipe. The standard pipe length shall be 20 feet.

4. Identification Marks:

4.1. Pipe and couplings shall be clearly and permanently marked with all information required by AWWA C900.

4.2. Testing:

4.2.1. All materials shall be sampled and tested in accordance with all requirements of AWWA C900. Pipe not manufactured in the U.S. shall be tested as required above by an approved testing laboratory within the U.S.

4.3. Affidavit of Compliance:

4.3.1. The manufacturer shall furnish an affidavit of compliance certifying that all tests have been conducted and that the materials comply with the applicable standards and these specifications. Test information shall be retained and shall be available if required by Engineer.

4.4. Couplings:

4.4.1. Each length of pipe shall be furnished with a coupling consisting of either a PVC sleeve and two (2) sealing rings or an integrally cast bell and one (1) sealing ring designed to hold the pipe in alignment, provide flexibility, separate the ends of the pipe lengths, resist applied earth pressures and provide fluid tightness.

4.5. Rubber Rings:

4.5.1. Rubber rings for joint sealing shall conform to ASTM D1869. All rubber rings shall be stored at a central point and distributed as needed. They shall be kept clean, away from oil, grease, excessive heat, and the electrical motors which produce ozone. If rubber rings are not to be used immediately, they shall be stored in their cartons, as shipped, in a cool, dark place out of the direct rays of the sun.

4.6. Joints:

4.6.1. Joints may be solvent weld where the spigot wedges into a tapered socket and the surfaces fuse together. Solvent cements shall conform to ASTM-

D2564 and assembly procedures shall conform to ASTM D-2855. Joints may be elastomeric gasket material providing a water tight seal. Elastomeric gasket joint assembly shall be in accordance with the pipe manufacturer's recommendations. Elastomeric compound shall comply in all respects with the physical requirements specified in ASTM 1869, C-361, or C-443.

5. Installation:

5.1. General:

5.1.1. Installation shall conform to the manufacturer's recommendations except as modified by these specifications and as shown on the drawings.

5.1.2. All laying, jointing and testing for defects and leakage shall be performed in the presence of Engineer and shall be subject to his approval before acceptance. Materials found during construction to have defects will be rejected and Contractor shall promptly remove such defective material from the site.

5.2. Trenching and Backfill:

5.2.1. Requirements for trenching, bedding, and backfill shall be as specified; as required by applicable permits and regulations; and as required by applicable safety codes.

5.2.2. Pipe shall be laid on a shaped trench foundation or shaped bedding as required and with properly dug bell or coupling holes. Supporting pipe on blocks or mounds or earth or bedding material will not be permitted.

5.3. Handling and Stockpiling:

5.3.1. Pipe, fittings and accessories shall be handled in a manner that will insure installation in a sound, undamaged condition. Equipment, tools and methods used in unloading, reloading, hauling and laying pipe and fittings shall be such that the pipe and fittings are not damaged. Hooks inserted in ends of pipe shall have broad, well-padded contact surfaces. No unpadded hooks or wire brushes shall be permitted to contact plastic lining. Pipe and fittings in which lining has been broken, split or loosened shall be replaced by and at the expense of Contractor. Where damaged areas are small and readily accessible, Contractor may be permitted to repair the lining in accordance with the manufacturer's instructions. Store pipe on a flat surface so as to support the barrel evenly. Store random lengths separately where they will be readily available. Individual lengths of pipe should be stocked in pipes of no higher than three (3) feet. If pipe is to be stored outside for periods of longer than thirty (30) calendar days, the pipe must be covered to protect it from prolonged exposure to sun's rays. The pipe shall be covered with

canvas or another opaque material which shall not be clear plastic sheets. Provisions shall be made for air circulation under the sheet.

5.4. Cutting:

5.4.1. Cutting and matching of pipe shall be accomplished in accordance with the pipe manufacturer's standard recommendations. Pipe shall not be cut with a cold chisel, flame, standard iron pipe cutter, nor any other method that may fracture the pipe, produce ragged, uneven edges or split the pipe end. Cut ends shall be machined smooth to the proper dimensions.

5.5. Pipe Laying:

5.5.1. The pipe shall be laid to the lines and grades shown on the drawings and specified herein and the sections shall be closely jointed to form a smooth flow line. Immediately before placing each section of pipe in final position, the bedding shall be checked for firmness and uniformity of surface. Contractor shall use a pipe laser or beam laser to assure grade and alignment. Carson City Public Works Department will waive the light test providing a pipe laser is used. Any deviation will be approved prior to construction by Project Engineer.

5.5.2. Proper implements, tools, and facilities as recommended by the pipe manufacturer's standard printed installation instructions shall be provided and used by Contractor for safe and efficient execution of the work. All pipe, fittings, valves, and accessories shall be carefully lowered into the trench by means of derrick, ropes, or other suitable equipment in such a manner as to prevent damage to pipe and fittings. Under no circumstances shall pipe or accessories be dropped or dumped into the trench.

5.5.3. The pipe and accessories shall be inspected for defects prior to lowering into the trench. Any defective, damaged or unsound pipe shall be repaired or replaced. All foreign matter or dirt shall be removed from the interior of the pipe before lowering into position in the trench. Pipe shall be kept clean during and after laying. All openings on the pipe line shall be closed with watertight expandable type sewer plugs or test plugs at the end of each day's operation or whenever the pipe openings are left unattended. The use of burlap, wood, or other similar temporary plugs will not be permitted.

5.6. Distributing Along the Trench:

5.6.1. Pipe should be strung as near the trench as possible, but, if the trench has not been dug; it shall be kept out of the way of the excavator. It shall be protected from blasting, traffic equipment or other hazards. Where damage as a result of vandalism could occur, only enough pipe for one day's laying shall be strung. The pipe shall be strung so that the bell ends point in the

direction that the work is progressing.

5.7. Jointing:

- 5.7.1. Each pipe joint shall be joined either with a coupling consisting of a PVC sleeve and two (2) rubber gaskets, or an integral bell with one (1) rubber gasket.
- 5.7.2. The gasket and the gasket seal inside the collar or bell shall be wiped clean before the gasket is inserted. At this time a thin film of lubricant shall be applied to the gasket and to the outside of the clean pipe end. Lubricant other than that furnished with the pipe shall not be used. The end of the pipe shall be then forced into the collar or bell to complete the joint.
- 5.7.3. The assembly of the joint shall be made in accordance with the printed recommendations of the manufacturer. This shall be accomplished with an assembly tool if so recommended by the manufacturer, so that the resulting position of the sleeve shall be such that is centered over pipe ends. After assembly of the coupling, the rubber gasket location shall be checked with a suitable gauge. Gaskets for the full circumference of the pipe shall be located at a distance from the coupling or bell end as recommended by the manufacturer of the couplings, If the distance does not fall within required limits, the joint shall be disassembled and reassembled in an acceptable manner.
- 5.7.4. When pipe laying is not in progress, the open end of the pipe shall be closed by approved means to prevent trench water from entering the pipe. Adequate backfill shall be deposited on pipe to prevent floating of pipe. Any pipe that has floated shall be removed from the trench, cleaned, and re-laid in an acceptable manner. No pipe shall be laid when, in the opinion of Engineer, the trench conditions or weather are unsuitable for such work.

5.8. Installation of Fittings:

- 5.8.1. Fittings shall be installed utilizing standard installation procedures. Fittings shall be lowered into trench by means of rope, cable, chain, or other acceptable means without damage to the fittings. Cable, rope, or other devices used for lowering fitting into trench, shall be attached around exterior of fitting for handling. Under no circumstances shall the cable, rope or other device be attached through the fitting's interior for handling. Fittings shall be carefully connected to pipe or other facility, and joint shall be checked to insure a sound and proper joint.

END OF DOCUMENT 3003

TECHNICAL SPECIFICATIONS

Document No. 3005 CONCRETE CUTTING AND/OR CORE DRILLING (12/30/14)

1. Scope:

- 1.1. This section covers the cutting and core drilling of existing concrete vaults and manholes for tank and pipe installation.
- 1.2. All concrete shall be cut the full depth so as not to chip outside or inside walls when the cut area is removed.
- 1.3. Steel shall be cut and covered with one (1) inch of grout so as not to puncture pipe projecting through the opening.
- 1.4. All openings shall be cut larger than the size of the tank or pipe to be installed, as required by manufacturer for installation of a pipe penetration connector/seal.
- 1.5. When cutting a manhole in order to place a sewer pipe in the base, the base is to be ground out to match the new pipe inside diameter that is installed and the existing invert and new pipe invert are to match.
- 1.6. A pipe penetration connector/seal, KOR-N-SEAL I & II Wedge Type, or approved equal, shall be installed on all core drilled pipe penetrations of vaults or manholes.
- 1.7. Loading of the wall area above the hole cut for the tank or water pipe shall be prohibited until the pipetank or waterline is set, and the connector/seal is installed.
- 1.8. If an additional section of wall area is removed and repoured, a flexible type material three fourths (3/4) of an inch shall be placed between the tank or pipeline and the poured concrete. This material shall be approved prior to installation by Project Engineer. All cuts shall be sealed water tight on the exterior wall of the vault with plastic mastic before backfilling.

END OF DOCUMENT 3005

TECHNICAL SPECIFICATIONS

Document No. 4005 CONCRETE CURB, GUTTER, WALKS, AND DRIVEWAYS (6/16/2014)

1. General:

- 1.1. This section includes any saw cutting and concrete removal, forming, pouring, and finishing curb, gutters, walks, and driveways.
- 1.2. Reference Specifications and Standards:
- 1.3. Unless otherwise specified herein, all work shall conform to the Standard Specifications.

2. Materials:

- 2.1. All Portland Cement Concrete, unless otherwise indicated, shall have synthetic fiber-reinforcement (at a minimum of 1 lb/CY) with a coarse aggregate gradation conforming to Size No. 67 in Section 200.05.03 of the Standard Specifications, and shall have a 1 to 4 inch slump and 4 to 7 percent entrained air. The minimum 28-day compressive strength shall be 4000 psi. Cement shall be Type II.

3. Subgrade:

- 3.1. The subgrade shall be prepared as specified in Subsection 302.02 of Standard Specifications.
- 3.2. All subgrade shall be compacted to a relative compaction of not less than ninety (90) percent for a minimum depth of six (6) inches, in accordance with test procedures set forth in ASTM D1557-70, Method C.

4. Dimensions:

- 4.1. Unless specified otherwise, the minimum thickness for concrete walks shall be four (4) inches. All other dimensions shall be as shown on the drawings.

5. Drainage Outlets:

- 5.1. Contractor will be required to provide suitable outlets through new curb for all existing building drains along the line of work.
- 5.2. The fully depressed curb opening at driveway entrances shall be one (1) inch above gutter flow line at the curb face. The top of the fully depressed portion of the curb shall be finished to a transverse 3/4 inch slope toward the gutter.

5.3. Where walk is to be constructed across driveways to commercial establishments, the thickness thereof shall be six (6) inches, unless otherwise specified on the drawings. At residential driveways, the thickness of the walk will be four (4) inches unless otherwise specified.

6. Forming:

6.1. All forming shall be done in accordance with Subsection 312.06 in Standard Specifications.

7. Slip Forms:

7.1. At the option of Contractor, and with the approval of Engineer, slip form equipment may be used for the construction of curb and gutter. The slip form equipment shall conform to the requirements in Subsection 312.07 in Standard Specifications.

8. Placement:

8.1. Concrete shall be placed for curb, gutters, walks, and driveways as specified in Subsection 312.08 in Standard Specifications.

9. Joints:

9.1. Joints in concrete curb, gutter, and walks shall be designated as expansion joints and weakened plane joints, and shall be constructed as specified by Subsection 312.09 in Standard Specifications.

10. Finishing and Curing:

10.1. Finish work and curing shall conform to specifications in Subsection 312.10 and 312.11 in Standard Specifications.

11. Defective Work:

11.1. Any new work found to be defective or damaged prior to its acceptance shall be repaired or replaced by Contractor at no expense to Carson City.

11.2. Removal of Existing Concrete Curb, Walk, Gutters, Cross Gutters, and Driveways:

11.3. Concrete shall be removed to neatly sawed edges with saw cuts made to a minimum depth of one and a half (1-1/2) inches. Concrete sidewalk or driveway to be removed shall be neatly sawed in straight lines either parallel to the curb or at right angles to the alignment of the sidewalk. Curb, gutters, sidewalks and driveways shall be removed to the nearest weakened plane

joint or, if within four feet (4') of an expansion joint to that expansion joint. No section to be replaced shall be smaller than thirty (30) inches in either length or width. Curb and gutter shall be sawed to a depth of one and one half (1-1/2) inches on a neat line at right angles to the curb face.

11.4. All materials removed shall be hauled from the site, at Contractor's expense, to a recognized landfill site approved by Engineer, unless otherwise specified. The construction area shall be left with a neat and finished appearance.

11.5. Existing improvements, adjacent property, utilities and other facilities, and trees and plants that are not to be removed shall be protected from injury or damage resulting from Contractor's operations.

12. Backfilling and Cleanup:

12.1. Backfilling to the finished surface of the newly constructed improvement must be completed before acceptance of the work.

12.2. Upon completion of the work, the surface of the concrete shall be thoroughly cleaned and the site left in a neat and orderly condition.

END OF DOCUMENT 4005

TECHNICAL SPECIFICATIONS

Document No. 4007 ASPHALT CONCRETE PAVEMENT (8/13/14)

1. General:

- 1.1. Work under this section includes mixing, delivery, placement, trimming and compaction of plantmix asphalt concrete on a prepared aggregate base including tack coats and fog seal.
- 1.2. All work shall be performed in accordance with Sections 316, Tack Coat; 317, Seal coats; and 320, Plantmix Bituminous Pavement, of the Standard Specifications, except as modified herein.
- 1.3. A tack coat of SS-1h asphalt emulsion, diluted 50-50 with water, shall be applied to all vertical asphalt or concrete join surfaces prior to placement of plantmix bituminous pavement. The application rate shall be 0.10 to 0.15 gallons per square yard.
- 1.4. When more than one course of asphalt concrete is placed, the surface of the first course shall be treated with a tack coat of SS-1h asphalt emulsion, diluted 50-50 with water, applied at the rate of 0.05 to 0.10 gallons per square yard.
- 1.5. Residential roadways shall use type 3 aggregate, collectors and arterial shall use type 2 aggregate per Section 200.02.03, Plantmix and Roadmix Aggregate, of the Standard Specifications. Asphalt cement material shall be PG 64-22 unless polymer additive is required then PG 64-28 shall be used. The asphalt concrete shall be compacted to not less than 96% of its Marshall maximum density when compacted with 50 blows per side.
- 1.6. A fog seal coat of SS-1h asphalt emulsion, diluted 50-50 with water, shall be applied to all completed asphalt surfaces including milled asphalt surface prior to the asphalt concrete overlay." The fog seal shall be applied at the rate of 0.06-0.08 gallons per square yard. Application shall not commence until at least twenty-four (24) hours after final rolling. The pavement temperature shall be at least 70 degrees F. at the time of application, and the ambient temperature shall be at least 50 degrees F.

2. Construction:

- 2.1. The following shall be in addition to the requirements contained in Section 320.03.03, Pavers, of the Standard Specifications.
 - 2.1.1. Pavers placing the final lift of the plant mix bituminous pavement for any uniform roadway section shall be equipped with an automatic control system capable of operating in conjunction with either a ski type device of

not less than 30 feet in length or a taut wire set to grade.

- 2.1.2. Contractor shall furnish all equipment required and shall install all stakes and wire required for the wire system. The automatic system shall be used for construction of the final lift.

END OF DOCUMENT 4007

WATERBORNE PAVEMENT STRIPING

A. DESCRIPTION

1. **General.** This work consists of applying permanent pavement striping and markings on the completed pavement. Use rapid dry waterborne traffic paint materials for the waterborne pavement striping item shown in the proposal.

B. CONSTRUCTION

1. **General.** Perform engineering for the location of the pavement striping according to the plans, Special Provisions, these specifications, and as directed. The location of striping shall be the striping pattern depicted on the plan sheets.

Place markings in proper alignment. All striping and pavement markings shall be white except the handicap stall marking which shall be blue. Remove and replace markings not placed in proper alignment or pattern by approved methods.

Protect the pavement striping and markings from public traffic until dry.

Painted pavement striping shall be four (4) inches wide unless otherwise noted.

2. **Striping Equipment.** Use equipment with a system capable of spraying both yellow and white paint, mounted on a truck of sufficient size and stability, and having an adequate power source to produce lines of uniform dimension and prevent application failure. Use equipment capable of placing stripes on the left and right sides and of placing two lines simultaneously with either line in a solid or intermittent pattern in yellow or white, and of applying glass beads at the proper rate. All guns must be in full view of operators at all times. Provide equipment with a metering device to register the accumulated installed footage for each gun, each day. Include at least one operator in each vehicle who is a technical expert in equipment operations and application techniques. Use equipment designed so that the pressure gauges for each pump are constantly visible to the operator at all times during its operation so that any fluctuation and pressure difference can be monitored immediately. Equip each paint tank with a mechanical agitator.

For rapid dry waterborne traffic paint materials use only equipment designed for water based paints.

After opening containers of rapid dry waterborne traffic paint, maintain a thin layer of water on the surface of the paint during storage to prevent skinning.

3. **Application.** Rapid Dry Waterborne Traffic Paint. Apply paint to an approved clean and dry surface. Apply by a single application with a machine capable of dispensing beads immediately after paint is applied. Do not use thinner unless otherwise approved.

Do not apply paint when the ambient air temperature or the pavement temperature is below 7°C (45°F).

Apply Nev.Type II 6050 waterborne paint markings to obtain a twenty five (25) mils minimum wet film thickness, measured without drop-on glass beads.

Produce markings of uniform thickness and with uniform distribution of glass beads throughout the line width. The width of lines shall be as specified with tolerance of \pm one quarter (1/4) inch for four (4) inch lines and one half (1/2) inch for wider lines. Produce markings with sharp edges and cutoff at the ends.

4. **Final Acceptance.** Final acceptance will be based on satisfactory compliance with these specifications. Work will have a six month warranty.

END OF DOCUMENT



nevada

Office of the Labor Commissioner



2015 PREVAILING WAGE RATES CARSON CITY

DATE OF DETERMINATION: October 1, 2014

APPLICABLE FOR PUBLIC WORKS PROJECTS BID/AWARDED
OCTOBER 1, 2014 THROUGH SEPTEMBER 30, 2015*

***Pursuant to NAC 338.040(3), "After a contract has been awarded, the prevailing rates of wages in effect at the time of the opening of bids remain in effect for the duration of the project."**

As [Amendments/Addenda](#) are made to the wage rates, such will be posted to sites of the respective counties. Please review regularly for any amendments posted or contact our offices directly for further assistance with any amendments to the rates.

[AIR BALANCE TECHNICIAN](#)
[ALARM INSTALLER](#)
[BOILERMAKER](#)
[BRICKLAYER](#)
[CARPENTER](#)
[CEMENT MASON](#)
[ELECTRICIAN-COMMUNICATION TECH.](#)
[ELECTRICIAN-LINE](#)
[ELECTRICIAN-NEON SIGN](#)
[ELECTRICIAN-WIREMAN](#)
[ELEVATOR CONSTRUCTOR](#)
[FENCE ERECTOR](#)
[FLAGPERSON](#)
[FLOOR COVERER](#)
[GLAZIER](#)
[HIGHWAY STRIPER](#)
[HOD CARRIER-BRICK MASON](#)
[HOD CARRIER-PLASTERER TENDER](#)
[IRON WORKER](#)

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

[LABORER](#)
[MECHANICAL INSULATOR](#)
[MILLWRIGHT](#)
[OPERATING ENGINEER](#)
[OPERATING ENG. STEEL FABRICATOR/ERECTOR](#)
[OPERATING ENGINEER-PILEDRIVER](#)
[PAINTER](#)
[PILEDRIVER \(NON-EQUIPMENT\)](#)
[PLASTERER](#)
[PLUMBER/PIPEFITTER](#)
[REFRIGERATION](#)
[ROOFER](#) (Does not include sheet metal roofs)
[SHEET METAL WORKER](#)
[SPRINKLER FITTER](#)
[SURVEYOR \(NON-LICENSED\)](#)
[TAPER](#)
[TILE /TERRAZZO WORKER/MARBLE MASON](#)
[TRAFFIC BARRIER ERECTOR](#)
[TRUCK DRIVER](#)
[WELL DRILLER](#)
[LUBRICATION AND SERVICE ENGINEER \(MOBILE AND GREASE RACK\)](#)
[SOIL TESTER \(CERTIFIED\)](#)
[SOILS AND MATERIALS TESTER](#)

PREVAILING WAGE RATES INCLUDE THE BASE RATE AS WELL AS ALL APPLICABLE FRINGES

NRS 338.010(21) “Wages” means:

- (a) The basic hourly rate of pay; and
- (b) The amount of pension, health and welfare, vacation and holiday pay, the cost of apprenticeship training or other similar programs or other bona fide fringe benefits which are a benefit to the workman.

NRS 338.035 Discharge of part of obligation of contractor or subcontractor engaged on public work to pay wages by making certain contributions in name of workman. The obligation of a contractor engaged on a public work or a subcontractor engaged on a public work to pay wages in accordance with the determination of the Labor Commissioner may be discharged in part by making contributions to a third person pursuant to a fund, plan or program in the name of the workman.

ATTACHMENT A

CRAFT	RATE
AIR BALANCE TECHNICIAN	<u>ADD SHEET METAL ZONE RATE</u>
Air Balance-Journeyman	52.68
Air Balance-Foreman	55.55
Air Balance-General Foreman	58.42
ALARM INSTALLER	
Alarm Installer-Journeyman	25.69
BOILERMAKER	
Boilermaker	65.94
BRICKLAYER	<u>ADD ZONE RATE</u>
Bricklayer-Journeyman	33.70
Bricklayer-Foreman	34.95
Bricklayer-General Foreman	35.70
CARPENTER	<u>ADD ZONE RATE</u>
Carpenter-Journeyman	40.27
Carpenter-Foreman	43.02
CEMENT MASON	<u>ADD ZONE RATE</u>
Cement Mason-Journeyman	35.75
Cement Mason-Foreman	38.00
ELECTRICIAN COMMUNICATION TECHNICIAN	<u>ADD ZONE RATE</u>
Communication Technician-Installer	32.40
Communication Technician	35.86
Communication-Senior Technician	38.53
ELECTRICIAN-LINE	
Electrician-Groundman	45.49
Electrician-Lineman	67.18
Electrician-Foreman	73.02

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

Electrician-General Foreman	78.90
Heavy Equipment Operator	55.58

ELECTRICIAN-NEON SIGN

Electrician-Neon Sign	47.28
-----------------------	-------

ELECTRICIAN-WIREMAN

Wireman	52.65	<u>ADD ZONE RATE</u>
Cable Splicer	56.56	
Wireman-Foreman	56.56	
Wireman-General Foreman	60.48	

ELEVATOR CONSTRUCTOR

Elevator Constructor-Journeyman Mechanic	87.91
Elevator Constructor-Mechanic in Charge	95.74

FENCE ERECTOR

Fence Erector	16.99
---------------	-------

FLAGPERSON

Flagperson	29.24	<u>ADD LABORER ZONE RATE</u> See Amendment 1
------------	-------	--

FLOOR COVERER

Floor Coverer-Journeyman	37.44
Floor Coverer-Foreman	40.22

GLAZIER

Glazier	25.76
---------	-------

HIGHWAY STRIPER

Highway Striper	35.36	<u>ADD LABORER ZONE RATE</u>
-----------------	-------	--

HOD CARRIER-BRICK MASON TENDER

Brick Mason-Journeyman	30.82	<u>ADD ZONE RATE</u>
Brick Mason-Foreman	31.32	

ATTACHMENT A

HOD CARRIER-PLASTER TENDER

ADD ZONE RATE

Plasterer Tender-Journeyman	35.36
Plasterer-Gun Tender	36.36
Plasterer Tender-Foreman	35.72

IRON WORKER

Ironworker-Journeyman	60.30
Ironworker-Foreman	63.65
Ironworker-General Foreman	67.34

LABORER

SEE GROUP CLASSIFICATIONS

ADD ZONE RATE See Amendment 1

Landscaper	26.95
Furniture Mover	28.25
Group 1	32.11
Group 1A	29.24
Group 2	32.21
Group 3	32.36
Group 4	32.61
Group 4A	33.86
Group 5	32.91
Group 6	
Nozzlemen, Rodmen	32.91
Gunmen, Materialmen	32.61
Reboundmen	32.36
Gunite Foremen	33.31

MECHANICAL INSULATOR

ADD ZONE RATE

Mechanical Insulator-Mechanic	58.21
Mechanical Insulator-Foreman	60.71
Mechanical Insulator-General Foreman	62.21

MILLWRIGHT

ADD ZONE RATE

Millwright	54.76
------------	-------

ATTACHMENT A

OPERATING ENGINEER
SEE GROUP CLASSIFICATIONS **ADD ZONE RATE**

Group 1	46.24
Group 1A	49.00
Group 2	49.53
Group 3	49.80
Group 4	50.54
Group 5	50.84
Group 6	51.01
Group 7	51.26
Group 8	51.85
Group 9	52.17
Group 10	52.52
Group 10A	52.71
Group 11	52.95
Group 11A	54.59
Group 11B	55.40
Foreman	54.59

Add 7% to base rate for "Second" Shift

Add 12.5% to base rate for "Special" shift

**OPERATING ENGINEER-STEEL FABRICATOR &
ERECTOR**
SEE GROUP CLASSIFICATIONS **ADD ZONE RATE**

Group 1	61.54
Group 1 Truck Crane Oiler	55.37
Group 1 Oiler	53.20
Group 2	60.03
Group 2 Truck Crane Oiler	55.12
Group 2 Oiler	53.20
Group 3	58.79
Group 3 Truck Crane Oiler	54.90
Group 3 Oiler	52.98
Group 3 Hydraulic	54.57
Group 4	57.06

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

Group 5	55.96
Add 7% to base rate for "Second" Shift	
Add 12.5% to base rate for "Special" Shift	

OPERATING ENGINEER -PILEDRIIVER
SEE GROUP CLASSIFICATIONS **ADD ZONE RATE**

Group 1	61.01
Group 1 Truck Crane Oiler	55.55
Group 1 Oiler	53.63
Group 2	59.47
Group 2 Truck Crane Oiler	55.37
Group 2 Oiler	53.43
Group 3	58.02
Group 3 Truck Crane Oiler	55.12
Group 3 Oiler	53.20
Group 4	56.51
Group 5	55.40
Group 6	54.29
Group 7	53.33
Group 8	52.37
Add 7% to base for "Second" Shift	
Add 12.5% to base for "Special" Shift	

PAINTER

Brush/Roller Painter	33.49
Spray Painter/Paperhanger	34.34
Sandblaster	34.84
Structural Steel & Steeplejack	35.34
Swing Stage	36.34
Special Coating Application-Brush	34.84
Special Coating Application-Spray	35.34
Special Coating Application-Spray Steel	35.59
Foreman	\$1.00 above highest Journeyman

PILEDRIIVER

Piledriver-Journeyman	53.96
-----------------------	-------

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

Piledriver-Foreman	57.63
PLASTERER	<u>ADD ZONE RATE</u>
Plasterer-Journeyman	36.87
Plasterer-Foreman	39.12
PLUMBER/PIPEFITTER	
Plumber-Journeyman	47.10
Plumber-Foreman	50.19
Plumber-General Foreman	53.28
REFRIGERATION	
Refrigeration-Journeyman	43.68
ROOFER (Does not include sheet metal roofs)	
Roofer	22.61
SHEET METAL WORKER	<u>ADD ZONE RATE</u>
Sheet Metal-Journeyman	52.68
Sheet Metal-Foreman	55.55
Sheet Metal-General Foreman	58.42
SPRINKLER FITTER	
Sprinkler Fitter-Journeyman	35.00
Sprinkler Fitter-Foreman	35.00
Sprinkler Fitter-General Foreman	35.00
SURVEYOR	<u>ADD ZONE RATE</u>
Surveyor	49.80
TAPER	
Taper	38.98
TILE SETTER/TERRAZZO WORKER/MARBLE MASON-FINISHER	
Tile, Terrazzo and Marble Finisher	36.25

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

TILE SETTER/TERRAZZO WORKER/MARBLE MASON

ADD ZONE RATE

Tile Setter-Journeyman	51.41
Tile Setter-Foreman	53.41
Tile Setter-General Foreman	61.41
Terrazzo/Marble Mason-Journeyman	51.41
Terrazzo/Marble Mason-Foreman	53.41
Terrazzo/Marble Mason-General Foreman	61.41

TRAFFIC BARRIER ERECTOR

ADD LABORER ZONE RATE

See Amendment 1

Traffic Barrier Erector	32.11
-------------------------	-------

TRUCK DRIVER

Truck Driver	20.55
--------------	-------

WELL DRILLER

Well Driller	40.80
--------------	-------

LUBRICATION AND SERVICE ENGINEER (MOBILE AND GREASE RACK)

ADD OPERATING ENG. ZONE RATE

Lubrication and Service Engineer (mobile and grease rack)	51.01
---	-------

SOIL TESTER (CERTIFIED)

Soil Tester (Certified)	40.11
-------------------------	-------

SOILS AND MATERIALS TESTER

Soils and Materials Tester	40.11
----------------------------	-------

ATTACHMENT A

Job Descriptions for Recognized Classes of Workmen

Regarding job descriptions for public works projects, please take notice of the following:

1. Pursuant to NAC 338.0095(1)(a), "A workman employed on a public work must be paid based on the type of work that the workman actually performs on the public work and in accordance with the recognized class of the workman."
2. The work description for a particular class is not intended to be jurisdictional in scope nor to be construed as limiting or prohibiting any worker from performing the work of one or more classes.
3. Any person who believes that a type of work is not classified, or who otherwise needs clarification pertaining to the recognized classes or job descriptions, shall contact the Labor Commissioner, in writing, for a determination of the applicable classification and pay rate for a particular type of work.
4. The job descriptions set forth or referenced herein supersede any and all descriptions previously agreed upon by the Labor Commissioner in any settlement agreements or stipulations arising out of contested matters.
5. The following specific provisions, where applicable, shall prevail over any general provisions of the job descriptions:
 - Amendments to the prevailing wage determinations;
 - Group Classifications and/or descriptions recognized by the Labor Commissioner and included with wage determinations for a particular type of work in a particular county.

AIR BALANCE TECHNICIAN, includes but is not limited to:

Inspecting, testing, programming, documenting, adjusting and balancing heating, cooling and ventilating systems using specialized tools and testing equipment to attain performance standards specified in the design of the systems.

ALARM INSTALLER, includes but is not limited to:

1. Installing or testing electrical protective signaling systems used to provide notification of fire, burglary or other irregularities on the premises of the subscriber of the system;
2. Installing of wiring and signaling units;
3. Repairing electrical protective signaling systems
4. Starting up, programming and documenting systems;

BOILERMAKER, includes but is not limited to:

1. Constructing, assembling, maintaining and repairing stationary steam boilers and boiler house auxiliaries;
2. Aligning structures or plate sections to assemble boiler frame tanks or vats;

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

3. Assisting in the testing of assembled vessels, directing cleaning of boilers and boiler furnaces;
4. Inspecting and repairing boiler fittings, including, without limitation, safety valves, regulators, automatic-control mechanisms, water columns and auxiliary machines.

BRICKLAYER, includes but is not limited to:

1. Laying materials, including without limitation, brick, structural tile and blocks of concrete, cinder, glass, gypsum and terra cotta, but not including stone, to construct or repair walls, partitions, arches, sewers, and other structures;
2. Laying and aligning bricks, blocks or tiles to build or repair structures for high temperature equipment, including, without limitation, cupola, kilns, ovens and furnaces; and
3. Fastening or fusing brick or other building materials to structures with wire clamps, anchor holes, torches or cement.
4. Pointing-cleaning-caulking of all types of masonry; caulking of window frames encased in masonry on brick, stone or cement structures, including grinding and cutting out on such work and sand blasting, steam cleaning and gunite work.
5. Pointing, cleaning and weatherproofing of buildings, grain elevators and chimneys built of stone, brick or concrete, including grinding and cutting out, sand blasting and gunite work on the same.

CARPENTER, includes but is not limited to:

1. Laying out, constructing, erecting, fabricating, installing and repairing structures and fixtures of wood, plywood, or alternative materials, doors and hardware and the fastening of the same, inclusive of garage or overhead door openers, cabinets, framework, floors, and acoustical ceiling systems using carpenter's hand tools and power tools;
2. Installing or erecting metal studs, drywall, lathing, wall partitions, prefabricated EFIS panels or any other system of panels that is attached to the interior or exterior of any building or structure, insulation and all types of ceilings;
3. Pre-cast concrete and concrete form work which includes but is not limited to: setting of templates, layout, fabrication, constructing, placing, erection, rigging and hoisting, stripping and removing of all forms which are to be reused;
4. Plywood decking, including, without limitation, stacking and installation of the plywood and the plywood decking;
5. Cutting, setting, removing of beam sides and soffits, bracing, and pads;
6. Constructing all wood panel forms and frame wall;
7. Building, erecting and disassembling self-supporting scaffolds that are more than 14 feet in height;
8. Laying out, cutting, joining, fitting of Foam Architectural Elements if same are attached mechanically; and
9. Shaping, cutting and planing by any means if done by hand or machine.

CEMENT MASON, includes but is not limited to:

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

1. Smoothing and finishing surfaces of poured concrete floors, walls, sidewalks and curbs to specified textures;
2. Patching holes with fresh concrete or an epoxy compound;
3. Molding expansion joints and edges through the use of edging tools, jointers and straightedges;
4. Setting of curb and gutter forms one board high;

ELECTRONIC COMMUNICATION TECHNICIAN, includes but is not limited to:

1. Pulling cable, installing and trimming devices, terminating loops, circuits, or other data gathering points;
2. Termination of main control panels, racks, or other head end equipment, as well as testing of all circuits from the field devices to the main control panels and/or equipment;
3. Utilizing test equipment for the purpose of troubleshooting and verifying the integrity of the circuits in question;
4. Using hand tools to assemble and install data communication lines and equipment computer systems, antennas and towers;
5. Disassembling equipment to adjust, repair or replace parts using hand tools;
6. Starting up, programming and documenting systems;
7. Measuring, cutting, splicing, connecting, soldering and installing wire and cable associated with communication systems

ELECTRICIAN LINEMAN, includes but is not limited to:

1. Erecting and repairing wood poles and prefabricated light duty metal towers, cable and related equipment to construct overhead transmission and distribution power lines used to conduct electrical energy between generating stations, substations and consumers;
2. Directing and assisting electrician ground men in attaching cross arms, insulators, lightning arresters, switches, wire conductors and auxiliary equipment to poles and towers in preparation of erecting the poles or towers;
3. Climbing erected poles or towers and installing equipment such as transformers
4. Strings wire conductors between erected poles with assistance of ground helpers and adjusts slack in conductors to compensate for contraction and elongation of conductors due to temperature variations, using winch.

ELECTRICIAN GROUNDMAN, includes but is not limited to:

1. Working under the direct supervision of linemen, including the operation of jackhammers and man hauls;
2. Loading and unloading of materials and equipment used by electrician lineman.
3. Does not include climbing poles, towers or other structures or working in the proximity of energized lines or equipment;

ELECTRICIAN-NEON SIGN, includes but is not limited to:

1. Installing, servicing and repairing plastic, neon and illuminated signs;
2. Ascending ladders or operating hydraulic or electric hoist to install, service, or examine sign to determine cause of malfunction;

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

3. Wiring, rewiring or removing defective parts and installing new parts using electrician's tools;
4. Removing sign or part of sign for repairs, such as structural fabrication, scroll repair, or transformer repair;

ELECTRICIAN WIREMAN, includes but is not limited to:

1. Laying out plans, installing, testing and repairing wiring, electrical fixtures, apparatus and control equipment;
2. Measuring, cutting, bending, threading, assembling and installing electrical conduit by using tools including, without limitation, a hacksaw, pipe threader, or conduit bender;
3. Pulling wiring through conduit;
4. Splicing wires;
5. Connecting wiring to lighting fixtures and power equipment;
6. Installing control and distribution apparatus, including, without limitation, switches, relays and circuit breakers, and fastening such apparatus into place;
7. Connecting power cables to equipment, including, without limitation, electric ranges and motors, and installing grounding leads;
8. Testing the continuity of a circuit to ensure electrical compatibility and safety of components using testing instruments, including, without limitation, an ohmmeter, a battery and buzzer, and an oscilloscope;
9. As necessary, cutting and welding steel structural members;

ELEVATOR CONSTRUCTOR, includes but is not limited to:

1. Assembling, installing, repairing and maintaining electric and hydraulic freight and passenger elevators, escalators and dumbwaiters;
2. Cutting pre-fabricated sections of framework, rails and other elevator components to specified dimensions, using acetylene torch, power saw, and disc grinder;
3. Installing cables, counterweights, pumps, motor foundations, escalator drives, guide rails, elevator cars, and control panels, using hand tools;

FENCE ERECTOR, includes but is not limited to:

1. Erecting or repairing chain link, wooden, tortoise, wire/wire mesh, or temporary fencing;
2. Mixing and pouring concrete around bases of posts and tamping soil into post hole to embed post;
3. Digging post holes with a spade, post hole digger or power driven auger;
4. Aligning posts through the use of lines or by sighting;
5. Verifying vertical alignment of posts with a plumb bob or spirit level;

FLAG PERSON, includes but is not limited to:

1. Directing movement of vehicular traffic through construction projects;
2. Distributing traffic control signs and markers along site in designated pattern;
3. Informing drivers of detour routes through construction sites;

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

FLOOR COVERER, includes but is not limited to:

1. Applying blocks, strips or sheets of shock-absorbing, sound-deadening or decorative covering to floors and walls, including carpets or rugs;
2. Measuring and cutting covering materials, such as rubber, linoleum, astro-turf, or cork tile and foundation material such as felt, using rule, straightedge, linoleum knife and snips;
3. Spreading adhesive cement over floor to cement foundation material to floor for sound-deadening, and to prevent covering from wearing at the board joints;
4. Rolling finished floors to smooth the floor and press cement into base and covering;
5. Fitting of devices for the attachment of carpet, linoleum, rubber and all resilient floor coverings and the fitting of metal edges, corners and caps used in the installation of the foregoing materials and all other preparatory work;

GLAZIER, includes but is not limited to:

1. Installing, setting, cutting, preparing, or removal of glass, or materials used in lieu thereof, including, without limitation, in windows, doorways, showers, bathtubs, skylights and display cases;
2. Installing glass on surfaces, including, without limitation, fronts of buildings, interior walls and ceilings;
3. Installing pre-assembled framework for windows and doors designed to be fitted with glass panels, including stained glass windows by using hand tools;
4. Loading and arranging of glass on trucks at the site of the public work;

HIGHWAY STRIPER, includes but is not limited to:

1. Painting highways, streets and parking surfaces by using manually propelled or mechanically propelled machines, brushes, rollers or spray guns;
2. Installing any device or application of any material used in lieu of paint for traffic direction, including, without limitation, buttons, tapes, plastics, rumble bars and other similar materials;

HOD CARRIER-BRICK MASON TENDER, includes but is not limited to:

1. Tending to or assisting brick masons, bricklayers and stonemasons;
2. Mixing, packing, wheeling and tempering mortar and fire clay;
3. Mixing, supplying and holding materials or tools;
4. Mixing, handling and conveying all other materials used by brick masons, bricklayers and stone masons;
5. Building scaffolds, trestles, boxes and swinging staging used exclusively by bricklayers and stone masons;
6. Hanging cables and placing putlogs;
7. Carrying bricks and mortar in a hod;
8. Cleaning work area and equipment of bricklayers and stone masons

HOD CARRIER-PLASTERER TENDER, includes but is not limited to:

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

1. Serving Plasterers in any capacity;
2. Handling materials after the materials are delivered as used by a Plasterer;
3. Building and handling all necessary trestle, scaffolding and planking of scaffolding for the exclusive use of Plasterers;
4. Building mortar boxes, mortar boards and stands.

IRONWORKER, includes but is not limited to:

1. Performing duties, as part of a crew, to raise, place and unite girders, columns and other structural steel members to form completed structures or structure frameworks;
2. Setting up hoisting equipment for raising and placing structural steel members;
3. Fastening steel members to cable of hoist, using chains, cable or rope;
4. Forcing steel members into final position using turnbuckles, crowbars, jacks, hand tools;
5. Aligning rivet holes in steel members with corresponding holes in previously placed steel members by driving drift pins to handle of wrench through holes;
6. Bolting aligned steel members to keep them in position until the steel members can be permanently riveted, bolted or welded into place;
7. Cutting and welding steel members;
8. Installing and repairing gates, iron doors, flagpoles, iron fences and roof decking;
9. Installing corrugated sheets when attached to steel frames;
10. Stud welding of all iron, steel and metal to structural steel;
11. Handling and setting of steel and metal joists;
12. Loading, unloading, hoisting, handling, signaling, placing and erecting of pre-stressed and pre-cast materials;
13. Handling, racking, sorting, cutting, bending, hoisting, placing, burning, welding and tying all material used to reinforce concrete construction;

LABORER, includes but is not limited to:

Perform tasks involving physical labor at building, highway, and heavy construction projects, tunnel and shaft excavations, and demolition sites. May operate hand and power tools of all types: air hammers, earth tampers, cement mixers, small mechanical hoists, and a variety of other equipment and instruments. May clean and prepare sites, dig trenches, set braces to support the sides of excavations, erect scaffolding, clean up rubble and debris, and remove asbestos, lead, and other hazardous waste materials. May assist other craft workers.

MARBLE MASON, includes but is not limited to:

1. Cutting, tooling, and setting marble slabs in floors and walls of buildings and renovating and polishing marble slabs previously set in buildings;
2. Trimming, facing and cutting marble to a specific size using a power saw, cutting and facing equipment, and hand tools
3. Drilling holes in marble slabs and attaching brackets;
4. Spreading mortar on the bottom and sides of a marble slab and on the side of adjacent marble slabs;
5. Setting blocks in positions, tamping a marble slab into place and anchoring bracket attachments with wire;

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

6. Filling joints between marble slabs with grout and removing excess grout with a sponge;
7. Cleaning and beveling cracks and chips on marble slabs using hand tools and power tools;
8. Heating cracked or chipped areas of a marble slab with a blowtorch and filling the defect with a composition mastic that matches the grain of the marble slab; and
9. Polishing marble slabs and other ornamental stone to a high luster by using hand tools and power tools.

MECHANICAL INSULATOR, includes but is not limited to:

1. Covering and lining structures with cork, canvas, tar paper, magnesia and related materials;
2. Installing blown-on insulation on pipe and machinery;
3. Lining of mechanical room surfaces and air handling shafts;
4. Filling and damming of fire stops and penetrations including, but not limited to, electrical and mechanical systems;
5. Foam applications for the purpose of thermal, acoustical, or fire protective purposes, including RTV foams or equivalents, applied to mechanical or electrical systems;
6. Duct lining and duct wrapping, direct application and installation of fire protection of grease ducts, exhaust systems, or any other ductwork for acoustical or thermal purposes;
7. Insulation of field joints on pre-insulated underground piping and the pouring of Gilsilite or its equivalent;
8. The application of material, including metal and PVC jacketing, on piping, fittings, valves, flanges, boilers, ducts, plenums, flues, tanks, vats, equipment and any other hot or cold surface for the purpose of thermal control;

MILLWRIGHT, includes but is not limited to:

1. Installing machinery and equipment according to layout plans, blueprints and other drawings in industrial establishments by using hoists, lift trucks, hand tools and power tools;
2. Dismantling machines by using hammers, wrenches, crowbars and other hand tools;
3. Assembling and installing equipment, including, without limitation, shafting, conveyors, monorails and tram rails, by using hand tools and power tools;
4. Constructing foundations for machines by using hand tools and building materials, including, without limitation, wood, cement and steel;
5. Assembling machines and bolting, welding, riveting or otherwise fastening them to a foundation or other structure by using hand tools and power tools; and
6. Repairing and lubricating machines and equipment (at the site of the public work) assembled and used by millwrights.

OPERATING ENGINEER, includes but is not limited to:

Operate one or several types of power construction equipment, such as motor graders, bulldozers, scrapers, compressors, pumps, derricks, shovels, tractors, or front-end loaders to excavate, move, and grade earth, erect structures, or pour concrete or other hard surface pavement.

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

PAINTER, includes but is not limited to:

1. All painting of walls, equipment, buildings, bridges and other structural surfaces by using brushes, rollers and spray guns;
2. Application of wall coverings/wall paper;
3. Removing old paint to prepare surfaces before painting the surface;
4. Mixing colors or oils to obtain desired color or consistency;
5. Sanding surfaces between coats and polishing final coat to a specified finish;
6. Cutting stencils and brushing and spraying lettering and decorations on surfaces;
7. Washing and treating surfaces with oil, turpentine, mildew remover or other preparations;
8. Filling cracks, holes and joints with caulk, putty, plaster or other filler by using caulking gun or putty knife;

PILEDRIVER, includes but is not limited to:

1. Operating pile drivers mounted on skids, barge, crawler, treads or locomotive crane to drive piling as foundations for structures including, without limitation, buildings, bridges and piers;
2. Barking, shoeing, splicing, form building, heading, centering, placing, driving, staying, framing, fastening, automatic pile threading, pulling and/or cutting off of piling;
3. Fabricating, forming, handling and setting of all such pre-cast, pre-stressed and post-stressed shapes that are an integral part of docks, piers, wharves, bulkheads, jetties, and similar structures;

PIPEFITTER, includes but is not limited to:

Assembling, installing, modifying and maintaining pipe systems, pipe supports and pneumatic equipment and related machines and equipment components for steam, hot water, heating, cooling, lubricating, sprinkling and industrial and processing systems which may require:

- a. Cutting, threading and hammering pipe to specifications using tools, including, without limitation, saws, cutting torches and pipe threaders and benders;
- b. Attaching pipes to walls, structures and fixtures, including without limitation, radiators or tanks, using brackets, clamps, tools, or welding equipment;
- c. Coating non-ferrous piping materials by dipping in mixture of molten tin and lead to prevent erosion, or galvanic and electrolytic action;

PLASTERER, includes but is not limited to:

1. Applying coats of plaster onto interior or exterior walls, ceilings, or partitions of buildings to produce a finished surface according to blueprints, architects' drawings and oral instruction;
2. Creating decorative textures in finish coat by using sand, pebbles or stones;
3. Installing guide wires on exterior surfaces of buildings to indicate thickness of plaster or stucco;
4. Applying weatherproof, decorative covering to exterior surfaces of a building;
5. Molding and installing ornamental plaster pieces, panels and trim;

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

6. Directing workers to mix plaster to a desired consistency;
7. Assembly of EFIS panels;
8. Laying out, cutting, joining, fitting and installation of Architectural Foam Elements which are trowel applied or adhesive set;
9. Applying, shaping, cutting, and planing in preparation for netting done by hand or machine;
10. All plaster or synthetic finishes applied to Foam Architectural Elements

PLUMBER, includes but is not limited to:

Assembling, installing and repairing pipes, fittings and fixtures for heating, water and drainage systems inside of buildings and to a point 5 feet outside of buildings which may therein require:

- a. Repairing and maintaining plumbing by replacing defective washers, repairing or mending broken pipes, and opening clogged drains;
- b. Assembling pipe sections, tubing and fittings by using screws, bolts, solder, plastic solvent and caulking;
- c. Installing pipe assemblies, fittings, valves and fixtures, including, without limitation, sinks, toilets and tubs, by using hand tools and power tools;
- d. Cutting openings in structures, excluding concrete, to accommodate pipe and pipe fittings by using hand tools and power tools;
- e. Filling pipes and plumbing fixtures with water or air and observing pressure gauges to detect and locate leaks.

REFRIGERATION MECHANIC, includes but is not limited to:

1. Installing and repairing industrial and commercial refrigeration systems;
2. Mounting compressors, condensers and other refrigeration components to the frame of a refrigerator by using hand tools and acetylene welding equipment;
3. Assembling structural and functional components needed for refrigeration, including, without limitation, controls, switches, gauges, wiring harnesses, valves, pumps, compressors, condensers, cores and pipes;
4. Installing expansion and control valves by using hand tools and acetylene welding equipment;
5. Cutting, bending, threading and connecting pipe from functional components to water, power or refrigeration systems;
6. Fabricating and assembling components and structural portions of a refrigeration system;

ROOFER, includes but is not limited to:

1. Installing and covering roofs and structures with slate, asphalt, wood and other related materials, other than sheet metal, by using brushes, knives, punches, hammers and other tools;
2. Spraying roofs, sidings and walls with material to bind, seal, insulate or soundproof sections of a structure;
3. Installation of all plastic, slate, slag, gravel, asphalt and composition roofing, and rock asphalt mastic when used for damp and waterproofing;

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

4. Installation of all damp resisting preparations when applied on roofs with mop, three-knot brush, roller, swab or spray system;
5. All types of preformed panels used in waterproofing;
6. Handling, hoisting and storing of all roofing, damp and waterproofing materials;
7. The tear-off and/or removal of roofing and roofing materials;

SHEET METAL WORKER, includes but is not limited to:

1. Fabricating, assembling, dismantling, installing or repairing:
 - o Sheet metal roofs, including #30 felt roofing paper installed to form a metal roofing system;
 - o Sheet metal parts or equipment, including, without limitation, duct work, metal lockers and kitchen equipment;
 - o Air-veyor and air-handling systems, regardless of materials used;
2. Setting up and operating fabrication machines to cut, bend and straighten sheet metal;
3. Shaping metal over anvils, blocks or forms using a hammer;
4. Operating soldering and welding equipment to join sheet metal parts;
5. Inspecting, assembling and smoothing seams and joints of burred surfaces;
6. Welding, soldering, bolting, riveting, screwing, clipping, caulking or bonding component parts to assemble products by using hand tools, power tools and devices for lifting and handling;

SPRINKLER FITTER, includes but is not limited to:

Installing, dismantling, maintaining, repairing, adjusting and correcting all fire protection and fire control systems, including the installation of piping or tubing, appurtenances and equipment pertaining thereto, including both overhead and underground water mains, fire hydrants, and hydrant mains, standpipes and hose connection to sprinkler systems, sprinkler tank heaters, air lines and thermal systems used in connection with sprinkler and alarm systems.

SURVEYOR, includes but is not limited to:

1. Planning ground surveys designed to establish base lines, elevation and other geodetic measurements;
2. Compiling data relevant to the shape, contour, gravitation, location, elevation and dimension of land and land features on or near the surface of the Earth for engineering, map making, mining, land evaluation, construction and other purposes;
3. Surveying bodies of water to determine navigable channels and to secure data for construction of breakwaters, piers and other marine structures;
4. Computing data necessary for driving and connecting underground passages, underground storage and volume of underground deposits.

TAPER, includes but is not limited to:

1. Sealing joints between plasterboard or other wallboards to prepare a wall surface for painting or papering;
2. Mixing sealing compound by hand or with a portable electric mixer and spreading the compound over the joints between boards using a trowel, broad knife, or spatula;

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

3. Filling cracks and holes in walls and ceilings with sealing compound ;
4. Applying texturing compound and primer to walls and ceiling to prepare a surface for a final finish by using brushes, rollers and spray guns;
5. Coating of joint compound or taping mud;

TERRAZZO WORKER, includes but is not limited to:

1. Applying cement, sand, pigment and marble chips to floors and stairways to attain durable and decorative surfacing according to specifications or drawings;
2. Spreading mixtures of sand, cement and water over surface with a trowel to form terrazzo;
3. Cutting metal division strips and pressing the metal division strips into a terrazzo base so that top edges form a desired design or pattern and define level of finished floor surface;
4. Spreading mixtures of marble chips, cement, pigment and water over a terrazzo base to form a finished surface by using a float and trowel;
5. Pre-casting terrazzo blocks in wooden forms

TILE SETTER, includes but is not limited to:

1. Applying tile and materials made for tile in tile-like units to walls, floors, ceilings and promenade roof decks following design specification;
2. Applying glazed, unglazed, mosaic and other ceramic tiles, which are used as a surface on floors, walls, ceilings, and other surfaces and which must be set to specific grade;
3. Applying and floating all setting beds into which glazed, unglazed, mosaic, or other ceramic tiles are set;
4. Leveling and plumbing tiles to a specified grade

TILE, TERRAZZO AND MARBLE FINISHER, includes but is not limited to:

1. Supplying and mixing construction materials for a tile setter, terrazzo worker or marble setter;
2. Applying grout and finishing the surface of installed tile, terrazzo and marble;
3. Cleaning installed tile, terrazzo and tile surfaces;
4. Renovation and filling chipped, cracked and broken pieces of tile, terrazzo and marble;
5. Grinding and polishing tile, terrazzo and marble;
6. Assisting a tile setter, terrazzo worker or marble setter;

TRAFFIC BARRIER ERECTOR, includes but is not limited to:

Erects or places instruments to provide directional assistance to traffic on or near the public works construction project.

TRUCK DRIVER, includes but is not limited to:

Driving a tractor trailer combination or a truck to transport goods or materials at the site of a public work or between sites of a public work. (Also, see descriptions listed with Truck Driver rates, if any.)

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

WELL DRILLER, includes but is not limited to:

1. Setting, operating or tending to portable drilling rig machinery and related equipment to drill wells;
 2. Extending stabilizing jackscrews to support and level a drilling rig;
 3. Installing water well pumps;
 4. Drillings wells for industrial water supplies, irrigation water supplies or water supplies for any other purpose; dewatering or other similar purposes; exploration; hole drilling for geologic and hydrologic information; and core drilling for geologic information.
-

ATTACHMENT A

GROUP CLASSIFICATIONS

LABORER, includes but is not limited to:

Group 1

All cleanup work of debris, grounds, and building including windows and tile

Dumpmen or Spotter (other than asphalt)
Handling and Servicing of Flares, Watchmen
General Laborer
Guide Posts and Highway Signs
Guardrail Erection and Dismantling
Limber, Brushloader and Piler
Pavement Marking and Highway Striping
Traffic Control Supervisor

Group 2

Choker setter or Rigger (clearing work only) Pittsburgh
Chipper and similar type brush shredders
Concrete worker (wet or dry) all concrete work not listed in Group 3
Crusher or Grizzly Tender
Greasing Dowels
Guinea Chaser (Stakemen)
Panel Forms (wood or metal) handling, cleaning and stripping of Loading and unloading,
(Carrying and handling of all rods and material for use in reinforcing concrete
Railroad Trackmen (maintenance, repair or builders)
Sloper
Semi-Skilled Wrecker (salvaging of building materials other than those listed in Group 3)

Group 3

Asphalt Workers (Ironers, Shovelers, Cutting Machine)
Buggymobile
Chainsaw, Faller, Logloader and Bucker
Compactor (all types)
Concrete Mixer under 1/2 yard
Concrete Pan Work (Breadpan type), handling, cleaning\stripping
Concrete Saw, Chipping, Grinding, Sanding, Vibrator
Cribbing, Shoring, Lagging, Trench Jacking, Hand-Guided Lagging Hammer
Curbing or Divider machine
Curb Setter (precast or cut)
Ditching Machine (hand-guided)
Drillers Helper, Chuck Tender
Form Raiser, Slip Forms
Grouting of Concrete Walls, Windows and Door Jams
Headerboardmen
Jackhammer, Pavement Breaker, Air Spade

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

Mastic Worker (wet or dry)
Pipewrapper, Kettlemen, Potmen, and men applying asphalt, creosote and similar type materials
All Power Tools (air, gas, or electric), Post Driver
Riprap-Stonepaver and RockSlinger, including placing of sack concrete wet or dry
Rototiller
Rigging and Signaling in connection with Laborers' work
Sandblaster, Potmen, Gunmen or Nozzlemen
Vibra-screed
Skilled Wrecker (removing and salvaging of sash, windows, doors, plumbing and electrical fixtures)

Group 4

Burning and Welding in connection with Laborers' work
Joy Drill Model TWM-2A, Gardner Denver Model DN143 and similar type drills (in accordance with Memorandum of Understanding between Laborers and Operating Engineers dated at Miami, Florida, Feb. 3, 1954) and Track Drillers, Diamond Core Drillers, Wagon Drillers, Mechanical Drillers on Multiple Units
High scalers
Concrete pump operator
Heavy Duty Vibrator with Stinger 5" diameter or over
Pipelayer, Caulker and Bander
Pipelayer-waterline, Sewerline, Gasoline, Conduit
Cleaning of Utility Lines
Slip Lining of Utility Lines (including operation of Equipment)
TV Monitoring and Grouting of Utility Lines
Asphalt Rakers

Group 4A

Foreman

Group 5

Construction Specialists
Blasters and Powdermen, all work of loading, placing, and blasting of all powder and explosives of any type, regardless of method used for such loading and placing
Asbestos removal
Lead abatement
Hazardous waste
Material removal

Group 6

Gunite Foremen, Nozzlemen, Rodmen, Gunmen, Materialmen, Reboundmen

OPERATING ENGINEER, includes but is not limited to:

Group 1

Engineer Assistant

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

Group 1A

Heavy Duty Repairman Helper
Oiler
Parts man

Group 2

Compressor Operator
Material Loader and/or Conveyor Operator (handling building materials)
Pump Operator

Group 3

Bobcat or similar loader, 1/4 cu. yd. or less
Concrete Curing Machines (streets, highways, airports, canals)
Conveyor Belt Operator (tunnel)
Forklift (under 20)
Engineer Generating Plant (500 K.W.)
Mixer Box Operator (concrete plant)
Motorman
Rotomist Operator
Oiler (truck crane)

Group 4

Concrete Mixer Operator, Skip type
Dinky Operator
Forklift (20' or over) or Lumber Stacker
Ross Carrier
Skip Loader Operator (under one (1) cu. yd.)
Tie Spacer

Group 5

Concrete Mixers (over one (1) cu. yd.)
Concrete Pumps or Pumpcrete Guns
Elevator and Material Hoist (one (1) drum)
Groundman for Asphalt Milling and similar

Group 6

Auger type drilling equipment up to and including 30 ft. depth digging capacity m.r.c.
Boom Truck or Dual Purpose a-Frame Truck
B.L.H. Lima Road Pactor or similar
Chip Box Spreader (Flaherty type or similar)
Concrete Batch Plant (wet or dry)
Concrete Saws (highways, streets, airports, canals)
Locomotives (over thirty (30) tons)
Maginnis International Full Slab Vibrator (airports, highways, canals and warehouses)
Mechanical Finishers (concrete) (Clary, Johnson, Bidwell Bridge Deck or similar types)
Mechanical Burn, Curb and/or Curb and Gutter Machine (concrete or asphalt)
Pavement Breaker, Truck Mounted, with compressor combination
Pavement Breaker or Tamper (with or without compressor combination)

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

Power Jumbo Operator (setting slip-forms, etc., in tunnels)
Roller Operator (except asphalt)
Self-Propelled Tape Machine
Self-Propelled Compactor (single engine)
Self-Propelled Power Sweeper Operator
Slip-Form Pump (power-driven by hydraulic, electric, air, gas, etc. lifting device for concrete forms)
Small Rubber-Tired Tractors
Snooper Crane, Paxton-Mitchell or similar
Stationary Pipe Wrapping, Cleaning and Bending Machine Operator

Group 7

Auger type drilling equipment over 30 ft. depth digging capacity m.r.c.
Compressor (over 2)
Concrete Conveyor or Concrete Pump, truck or equipment mounted (any assistance required shall be performed by an Assistant to Engineer) Boom length to apply
Concrete Conveyor, Building Site
Drilling and Boring Machine, vertical and horizontal (not to apply to waterliners, wagon drills or jack hammers)
Crusher Plant Engineer
Generators
Kolman Loader
Material Hoist (two (2) or more drums)
Mechanical Finishers or Spreader Machine (asphalt, Barber-Greene or similar)
Mine or Shaft Hoist
Pipe Bending Machines (pipeline only)
Pipe Cleaning Machines (tractor-propelled and supported)
Pipe Wrapping Machines (tractor-propelled and supported)
Portable Crushing and Screening Plants
Post Driller And/Or Driver
Pumps (over 2)
Roller Operator (asphalt)
Screedman (except asphaltic or concrete paving)
Screedman (Barber-Greene and similar) (asphaltic or concrete paving)
Self-Propelled Boom-Type Lifting Device (center mount) (on ten (10) ton capacity or less)
Slusher Operator
Surface Heater and Planer Operator
Trenching Machine (maximum digging capacity three (3) ft. depth) (Any assistance in the operation, if needed, shall be performed by an Assistant to Engineer)
Truck-Type Loader
Welding Machines (gasoline or diesel)

Group 8

Asphalt Plant Engineer
Asphalt Milling Machine
Cast-In-Place Pipe-Laying Machine
Combination Slusher and Motor Operator
Concrete Batch Plant (multiple units)

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

Dozer Operator
Drill Doctor
Elevating Grader Operator
Grooving and Grinding Machine (highways)
Ken Seal Operator
Loader (up to and including two and one-half (2 1/2) cu. yds)
Mechanical Trench Shield
Mixermobile
Push Cats
Road Oil Mixing Machine Operator Wood-Mixer (and other similar Pugmill equipment)
Rubber-Tired Earthmoving Equipment (up to and including thirty-five (35) cu. yds. "struck " m.r.c., Euclids, T-Pulls, DW10, 20, 21 and similar)
Self-Propelled Compactors with Dozer; Hyster 450, Cat 825 or similar
Sheepfoot
Small Tractor (with boom)
Soil Stabilizer (P & H or equal)
Timber Skidder (rubber-tired) or similar equipment
Tractor-Drawn Scraper
Tractor Operator
Tractor-Mounted Compressor Drill Combination
Trenching Machine Operator (over three (3) feet depth)
Tri-Batch Paver
Tunnel Badger or Tunnel Boring Machine Operator
Tunnel Mole Boring Machine
Vermeer T-600b Rock Cutter

Group 9

Chicago Boom
Combination Backhoe and Loader (up to and including 3/8 cu. yd.)
Combination Mixer and Compressor (gunite)
Heavy Duty Repairman and/or Welder
Lull Hi-Lift (twenty (20) feet or over)
Mucking Machine
Sub-Grader (Gurries or other types)
Tractor (with Boom) (D6 or larger)
Track-Laying-Type Earthmoving Machine (single engine with tandem scrapers)

Group 10

Boom-Type Backfilling Machine
Bridge Crane
Cary-Lift or similar
Chemical Grouting Machine
Derricks (two (2) Group 10 Operators required when swing engine remote from hoist)
Derrick Barges (except excavation work)
Euclid Loader and similar types
Gradesetter, Grade Checker
Heavy Duty Rotary Drill Rigs

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

Lift-Slab (Vagtborg and similar types)
Loader (over two and one-half (2 1/2 cu. yds. up to and including four (4) cu. yds.)
Locomotive (over one hundred (100) tons, single or multiple units)
Multiple-Engine Earthmoving Machines (Euclid Dozers, etc.)
Pre-Stress Wire Wrapping Machine
Rubber-Tired Scraper, Self-Loading
Single-Engine Scraper (over thirty-five (35) cu. yds.)
Shuttle Car (Reclaim Station)
Train Loading Station
Trenching Machine multi-engine with sloping attachments (Jefco or similar)
Vacuum Cooling Plant
Whirley Crane (up to and including twenty-five (25) tons)

Group 10A

Backhoe-Hydraulic (up to and including one (1) cu. yd.)
Backhoe (up to and including one (1) cu. yd.) (Cable)
CMI Dual Lane Auto-Grader SP30 or similar type
Cranes (not over twenty-five (25) tons) (hammerhead and gantry)
Finish Blade
Gradalls (up to and including one (1) cu. yd.)
Motor Patrol Operator
Power Shovels, Clamshells, Draglines, Cranes (up to and including one (1) cu. yd.)
Rubber-Tired Scraper, Self-Loading (twin engine)
Self-Propelled Boom-Type Lifting Device, center mount (over 10 tons up to and including 25 tons)

Group 11

Automatic Asphalt or Concrete Slip-Form Paver
Automatic Railroad Car Dumper
Canal Trimmer
Cary Lift, Campbell or similar type
Cranes (over twenty-five (25) tons)
Euclid Loader when controlled from the Pullcat
Highline Cableway Operator
Loader (over four (4) cu. yds. up to and including twelve (12) cu. yds.)
Multi-Engine Earthmoving Equipment (up to and including seventy-five (75) cu. yds. struck m.r.c.)
Multi-Engine Scrapers (when used to Push Pull)
Power Shovels, Clamshells, Draglines, Backhoes Gradalls (over one (1) cu. yd. and up to and including seven (7) cu. yds. m.r.c.)
Self-Propelled Boom-Type Lifting Device (center mount) (over 25 tons m.r.c.)
Self-Propelled Compactor (with multiple-propulsion power units)
Single-Engine Rubber-Tired Earthmoving Machine, with Tandem Scraper
Slip-Form Paver (concrete or asphalt)
Tandem Cats and Scraper
Tower Crane Mobile (including Rail Mount)
Truck Mounted Hydraulic Crane when remote control equipped (over 10 tons up to and including 25 tons)

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

Universal Liebherr and Tower Cranes (and similar types)
Wheel Excavator (up to and including seven hundred fifty (750) cu. yds. per hour)
Whirley Cranes (over twenty-five (25) tons)

Group 11A

Band Wagons (in conjunction with Wheel Excavators)
Operator of Helicopter (when used in construction work)
Loader (over twelve (12) cu. yds.)
Multi-Engine Earthmoving Equipment (over seventy-five (75) cu. yds. "struck" m.r.c.)
Power Shovels, Clamshells, Draglines, Backhoes, and Gradalls (over seven (7) cu. yds. m.r.c.)
Remote-Controlled Earth Moving Equipment
Wheel Excavator (over seven hundred fifty (750) cu. yds. per hour)

Group 11B

Holland Loader or similar or Loader (over 18 cu. yds.)

OPERATING ENGINEERS - Steel Fabricator & Erector

Group 1

Cranes over 100 tons
Derrick over 100 tons
Self-Propelled Boom Type Lifting Devices over 100 tons

Group 2

Cranes over 45 tons up to and including 100 tons
Derrick, 100 tons and under
Self Propelled Boom Type Lifting Device, over 45 tons
Tower Crane

Group 3

Cranes, 45 tons and under
Self Propelled Boom Type Lifting Device, 45 tons and under

Group 4

Chicago Boom
Forklift, 10 tons and over
Heavy Duty Repairman/Welder

Group 5

Boom Cat

ATTACHMENT A

OPERATING ENGINEER -Piledriver

Group 1

Derrick Barge Pedestal mounted over 100 tons
Clamshells over 7 cu. yds.
Self Propelled Boom Type Lifting Device, over 100 tons
Truck Crane or Crawler, land or barge mounted over 100 tons

Group 2

Derrick Barge Pedestal mounted 45 tons up to and including 100 tons
Clamshells up to and including 7 cu. yds.
Self Propelled Boom Type Lifting Device over 45 tons
Truck Crane or Crawler, land or barge mounted, over 45 tons up to and including 100 tons

Group 3

Derrick Barge Pedestal mounted under 45 tons
Self Propelled Boom Type Lifting Device 45 tons and under
Skid/Scow Piledriver, any tonnage
Truck Crane or Crawler, land or barge mounted 45 tons and under

Group 4

Assistant Operator in lieu of Assistant to Engineer
Forklift, 10 tons and over
Heavy Duty Repairman/Welder

Group 5

No current classification

Group 6

Deck Engineer

Group 7

No current classification

Group 8

Deckhand
Fireman

ATTACHMENT A

ZONE RATES

BRICKLAYER

In addition to BRICKLAYER rates add the applicable amounts per hour, calculated based on a radius of over fifty (50) miles from the Washoe County Courthouse in Reno, Nevada:

Zone 1-0-35 Miles	0.00
Zone 2-36-75 Miles	1.25
Zone 3-Over 75 Miles	5.37

CARPENTER (Building and Heavy Highway and Dam Construction)

In addition to CARPENTER rates add the applicable amounts per hour, calculated from the Washoe County Courthouse:

Zone 1-0 to 50 miles	\$0.00 (road miles of either the Carson City Courthouse or the Washoe County Courthouse)
Zone 2-51-150 miles	\$3.00
Zone 3-151-300 miles	\$4.00
Zone 4-301 miles and over	\$5.00

CEMENT MASON

In addition to CEMENT MASON rates add the applicable amounts per hour, calculated from the Reno Post Office, 50 So. Virginia St., Reno, Nevada:

Zone 1-0-90 miles	\$0.00
Zone 2-91 miles and over	\$6.00

ELECTRICIAN

In addition to Electrician rates add the applicable amounts per hour, calculated from the Washoe County Courthouse:

Zone 1-0-70 miles	\$0.00
Zone 2-71-90 miles	\$8.00
Zone 3 -91 miles and over	\$10.00

ELECTRICIAN-COMMUNICATION TECH

In addition to Electrician Communication Tech rates add the applicable amounts per hour, calculated from the Washoe County Courthouse:

Zone 1-0-70 miles	\$0.00
Zone 2-71-90 miles	\$5.00
Zone 3 -91 miles and over	\$7.00

HOD CARRIER-BRICK MASON TENDER

In addition to Hod Carrier Brick Mason Tender rates, add the applicable amounts per hour, calculated based on a radius from the Washoe County Courthouse:

Zone 1-35 to 75 miles	\$1.25
Zone 2-76 miles and over	\$7.50

HOD CARRIER-PLASTERER

In addition to Hod Carrier Plasterer rates add the applicable amounts per hour, calculated based on a radius from So. Virginia St., Reno, Nevada:

Zone 1-70 miles	\$0.00
-----------------	--------

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

Zone 70 miles and over \$8.00

LABORER (Highway and Dam Construction only)

In addition to LABORER rates add the applicable amounts per hour, calculated based on a radius from either the Carson City Courthouse or the Washoe County Courthouse:

Zone 1-0 to 50 miles \$0.00
Zone 2-51 to 150 miles \$3.00
Zone 3-151 to 300 miles \$4.00
Zone 4-301 miles and over \$5.00

LABORER (Building Construction)

In addition to LABORER rates add the applicable amounts per hour, calculated based on road miles from either the Carson City Courthouse or the Washoe County Courthouse:

Zone 1-0 to 50 miles \$0.00
Zone 2-51 to 150 miles \$3.00
Zone 3-151 to 300 miles \$4.00
Zone 4-301 miles and over \$5.00

MECHANICAL INSULATOR

In addition to MECHANICAL INSULATOR rates add the applicable amounts per hour, calculated based on a radius figured from Reno City Hall:

Zone 1-0-20 miles- \$1.25
Zone 2-21-40 miles- \$2.50
Over 40 miles- \$10.63

MILLWRIGHT

In addition to MILLWRIGHT rates, add the applicable amounts per hour, calculated on road miles from either the Carson City Courthouse or the Washoe County Courthouse:

Zone 1-1 to 15 miles \$1.25
Zone 2-15 to 35 miles \$2.50
Zone 3-35 miles and over \$10.63

OPERATING ENGINEER

In addition to: OPERATING ENGINEER; STEEL FABRICATOR and ERECTOR, PILEDRIVER, SURVEYOR, and LUBRICATION AND SERVICE ENGINEER rates add the applicable amounts per hour calculated based on a radius from the Washoe County Courthouse:

Zone 1-0 to 75 miles \$0.00
Zone 2-75 to 150 miles \$3.00
Zone 3-151 to 300 miles \$4.00
Zone 4-301 miles and over \$5.00

PLASTERER

2014-2015 Prevailing Wage Rates – Carson City County

ATTACHMENT A

In addition to PLASTERER rates add the applicable amounts per hour, calculated from the South Virginia and Mill Street, Reno, Nevada:

Zone 1-0-70 miles	\$0.00
Zone 2-70 miles and over	\$8.00

SHEET METAL WORKER

In addition to AIR BALANCE AND SHEET METAL WORKER rates, add the applicable amounts per hour, calculated based on a radius from the courthouse in Reno, Nevada:

Zone 1-0 to 75 miles	\$0.00
(including the City of Fallon and the Fallon Naval Air Base)	
Zone 2-over 75 miles	\$8.12

TILE/TERRAZZO WORKER/MARBLE MASON

In addition to TILE/TERRAZZO WORKER/MARBLE MASON rates add the applicable amounts per hour, calculated based on a radius of over fifty (50) miles from the City Hall of Las Vegas, Nevada:

0-40 Miles	\$0.00
41-50 Miles	\$2.50
51-70 Miles	\$4.37
Over 70 Miles	\$6.87

The area within the city limits of Boulder City and Primm, Nevada shall be considered free zones.