

CARSON CITY PURCHASING AND CONTRACTS
201 North Carson Street, Suite 3
Carson City, NV 89701
775-283-7137/FAX 887-2107
<http://www.carson-city.nv.us/index.aspx?page=998>

NOTICE TO CONTRACTORS
ADVERTISED BID #1415-165
BID TITLE "Combs Canyon Road Curb Improvements"
Labor Commissioner PWP # CC-2015-171

May 12, 2015

Addendum No. 1

The following is based on questions received on 5/12/15.

1. Q: Does Carson City Public Works provide density testing or is the contractor supposed to provide a GEO Tech to do so?

A: Yes, Carson City provides density testing.

2. Q: The Bid Plans show 6" of aggregate base for all AC patching and paving, BP.11 in the bid proposal shows 8" of aggregate base and BP.12 shows 12" of aggregate base. Which base thicknesses are correct?

A: Please make the following changes to the Bid Plan Set for the above mentioned project:

Delete Construction Note 2 on Sheet C2, C3, C4, C5, C6 and C7 of the Bid Plans and replace with the following:

Construct 4" AC Pavement on 12" Aggregate Base Compacted to 95% Per Detail C-5.1.6.

Delete Construction Note 3 on Sheet C2, C3 and C5 of the Bid Plans and replace with the following:

Construct 3" AC Pavement on 8" Aggregate Base Compacted to 95% Per Detail C-5.1.6.

End of Addendum 1