

CARSON CITY PURCHASING AND CONTRACTS
201 North Carson Street, Suite 3 Carson City, NV 89701
775-283-7137/FAX 887-2107
<http://www.carson.org/index.aspx?page=998>

NOTICE TO BIDDERS
Advertised Bid #1516-015
East West Transmission Main Ph. 2A-2

8/24/2015
Addendum No. 3

The following questions have been received as of 8/12/2015. Responses are in italics.

1. What is the difference between SC 6.2.31 WATERBORNE PAINT (BP.31) and SC 6.2.32 SIGNAGE AND STRIPING (BP.32).

The two items may be combined. Therefore:

- Please delete item BP.32 SIGNAGE AND STRIPING in its entirety.
- Please replace Attachment B with the attached revised Bid Proposal Form.
- Please replace SC 6.2.31 WATERBORNE PAINT (BP.31) in its entirety with the following:

SC 6.2.31 WATERBORNE PAINT (BP.31)

Work under these bid items shall conform to the requirements of Section 324, "PAINTING, PAVEMENT AND MARKING" and applicable Technical Specifications.

Measurement of this item will be on a Lump Sum basis.

Payment for this item will be made at the unit price named in the Proposal Summary, which price shall constitute full compensation for furnishing and installing all pavement markings shown in the plans and specifications including "piano keys", stop bars, solid striping, skip striping, lane lines, legends, parking stripes, cross hatch, chevrons, handicapped legends, curb paint and all other labor, tools, equipment, materials and incidentals required to perform the work.

2. Where are the grindings to be stockpiled?

The grindings shall be stockpiled per the Construction Manager's direction at the Public Works Corporate Yard, 3505 Butti Way. Grindings shall be clean and free of dirt, base etc.

3. If no centerline monuments exist, will the surveyor be required to establish said monuments for the "Record of Survey"?

No.

4. In the specs under GC 2.6.10 Surveys, Lines and Grades it calls for the project surveyor to set centerline blue top and red top hubs. The plans do not have a centerline profile and or cross slope on the pavement sections. Will the project surveyor be required to provide red top and blue top hubs?
No.

End of Addendum 2

ATTACHMENT B

BID # 1516-015

BID TITLE: “East West Water Transmission Main Project – Ph. 2A-2”

NOTICE: No substitution or revision to this Bid Proposal form will be accepted. Carson City will reject any Bid that is received that has changes or alterations to this document. Although the Prevailing Wages are provided in this bid document, the bidder is responsible to verify with the Labor Commissioner if any addendums have been issued. The successful bidder will be required to provide the current Prevailing Wages used in preparation of their bid within 24 hours of bid submission.

PRICES will be valid for sixty (60) calendar days after the bid opening which is indicated in the Notice to Contractors.

COMPLETION of this project is expected **PURSUANT TO THE BID DOCUMENTS.**

BIDDER acknowledges receipt of _____ Addendums.

SUMMARY

Description		Scheduled Value	Unit	Unit Price	Total Price
Schedule A:					
BP.1	Mobilization, Demobilization, Cleanup	1	LS		
BP.2	Traffic Control	1	LS		
BP.3	4" Plantmix Bituminous Pavement Type 2 Aggregate, PG 64-28 NV w/ 8" Type 2 Agg Base	49700	SF		
BP.4	24"Ø PVC C905, DR-25, 165 PSI Water Main – Bell & Spigot	2813	LF		
BP.5	16"Ø PVC C905, DR-25, 165 PSI Water Main – Bell & Spigot	0	LF		
BP.6	12"Ø PVC C900, DR-18 Water Main - Bell & Spigot	15	LF		
BP.7	24"Ø Butterfly Valve (including Flanged Coupling Adapters [FCA's])	3	EA		
BP.8	16"Ø Butterfly Valve (including FCA's)	0	EA		
BP.9	12"Ø Gate Valve	1	EA		
BP.10	24"Ø x 24"Ø x 16"Ø X 16"Ø Cross (including FCA's)	0	EA		
BP.11	24"Ø x 24"Ø x 12"Ø Tee (including FCA's, appurtenances, & tap to 12" waterline)	1	EA		
BP.12	Special Construction Crossing	6	EA		
BP.13	Install Fire Hydrant Assembly	4	EA		
BP.14	Install 3 - 4"Ø SCH40 PVC Fiber Optic Conduit w/ Pull String	2828	LF		

ATTACHMENT B

Description		Scheduled Value	Unit	Unit Price	Total Price
BP.15	Install model 3048 fiber vault with H20 Traffic Rated Lid and Bolt Down Steel Cover	4	EA		
BP.16	Install Modified Type 4R Curb Inlet	1	EA		
BP.17	Remove Bituminous Surface	6101	SY		
BP.18	Remove Curb & Gutter	1065	LF		
BP.19	Remove PCC Sidewalk or Flatwork	1075	SY		
BP.20	Remove Fence	1	LS		
BP.21	Relocate Sign	2	EA		
BP.22	Construct Curb & Gutter	489	LF		
BP.23	Construct 4" PCC Sidewalk	3568	SF		
BP.24	Construct 6" PCC Driveway Approach	1573	SF		
BP.25	Construct ADA Ramp	3793	SF		
BP.26	Construct 3' PCC Valley Gutter (6" thick)	85	SF		
BP.27	Install Flexible Guide Posts (Glue-Down)	12	EA		
BP.28	Construct Fence	130	LF		
BP.29	1 1/2" Mill & Overlay	6251	SY		
BP.30	Adjust Existing Utility to Grade	27	EA		
BP.31	Waterborne Paint	1	LS		
BP.32	Signage & Striping	0	LS		
BP.33	Remove & Replace Landscaping	1	LS		
BP.34	Stormwater Protection	1	LS		
BP.35	Remove Existing Drop Inlet	1	EA		
BP.36 Total Base Bid Price (Schedule A)					

BP.37 Total Base (Schedule A) Bid Price Written in Words