



**CONCRETE WASHOUT
SIGN DETAIL**
NTS

PLAN
NTS

NOTES:

1. WHERE POSSIBLE, CONCRETE SUPPLIERS SHALL CONDUCT WASHOUT ACTIVITIES AT THEIR OWN PLANTS OR DISPATCH FACILITIES.
2. AN EFFECTIVE MEANS OF ELIMINATING THE DISCHARGE OF WATER FROM THE WASHOUT CONCRETE SHALL BE PROVIDED.
3. CONCRETE WASHOUT FACILITIES SHALL NOT BE USED FOR THE DISPOSAL OF EXCESS CONCRETE AND CEMENT. TRUCKS SHALL NOT BE ALLOWED TO BACK TURN AND DISPOSE OF RESIDUAL LOADS.
4. LOCATE WASHOUT AREAS A MINIMUM OF 50 FEET FROM WATER WAYS AND STORM DRAIN SYSTEM INLETS.
5. WHEN THE WASHOUT IS 75 PERCENT FULL, IT MUST BE CLEANED OR A NEW WASHOUT MUST BE CONSTRUCTED. DISPOSE OF WASTE AT LEAST ONCE A WEEK.
6. A CONCRETE WASHOUT SIGN SHALL BE INSTALLED WITHIN 15 FEET OF THE TEMPORARY CONCRETE WASHOUT BASIN.

NO.	REVISION	DATE	STANDARD DETAIL FOR PUBLIC WORKS CONSTRUCTION	SECTION CARSON CITY
			CONCRETE WASHOUT BASIN	DRAWING NO. C-1.2.6
				DATE SEP 2017
APPROVED BY: 				
		9/17		